No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
1	Sacramento County Main Jail	9996252	129807		D4011	Supplemental Components	Fire Pump Controller		1
2	Sacramento County Main Jail	9859526	129499	EQ-1032972	D5017	Automatic Transfer Switch	ATS	600 AMP	1
3	Sacramento County Main Jail	9859495	129753	EQ-1032973	D5017	Automatic Transfer Switch	ATS	800 AMP	1
4	Sacramento County Main Jail	9859456	129652	EQ-1032974	D5017	Automatic Transfer Switch	ATS	1000 AMP	1
5	Sacramento County Main Jail	9960680			C1039	Cell Door Hardware	Electronic Security		1
6	Sacramento County Main Jail	9960679			E1047	Cell Doors	Security Doors, Swinging		1
7	Sacramento County Main Jail	9859521	129555	EQ-1028926	E1047	Detention Equipment	Security Doors & Hardware, Rolling		1
8	Sacramento County Main Jail	9859617	129859	EQ-1028927	E1047	Detention Equipment	Security Doors & Hardware, Rolling		1
9	Sacramento County Main Jail	9859757	129626	EQ-1028928	E1047	Detention Equipment	Security Doors & Hardware, Rolling		1
10	Sacramento County Main Jail	9859728	129515	EQ-1028929	E1047	Detention Equipment	Security Doors & Hardware, Rolling		1
11	Sacramento County Main Jail	9859500	129658	EQ-1028930	E1047	Detention Equipment	Security Doors & Hardware, Rolling		1
12	Sacramento County Main Jail	9859347	129909	EQ-1028931	E1047	Detention Equipment	Security Doors & Hardware, Rolling		1
13	Sacramento County Main Jail	9859408	129915	EQ-1028932	E1047	Detention Equipment	Security Doors & Hardware, Rolling		1
14	Sacramento County Main Jail	9859786	129831	EQ-1028933	E1047	Detention Equipment	Security Doors & Hardware, Rolling		1
15	Sacramento County Main Jail	9927090	130413		D5023	Distribution Panel	120/208 V	600 AMP	1
16	Sacramento County Main Jail	10385458			C1039	Door Hardware	Electronic Security		1
17	Sacramento County Main Jail	10385307			C1039	Door Hardware	Swinging		1
18	Sacramento County Main Jail	9922875	130003		D5045	Emergency & Exit Lighting System	Full Interior Upgrade, LED		1
19	Sacramento County Main Jail	9996265	129803	EQ-1028918	D2016	Emergency Plumbing Fixtures	Eye Wash		1
20	Sacramento County Main Jail	9859673	129460	EQ-1036916	D2016	Emergency Plumbing Fixtures	Eye Wash & Shower Station		1
21	Sacramento County Main Jail	9859468	129575	EQ-1036917	D2016	Emergency Plumbing Fixtures	Eye Wash & Shower Station		1
22	Sacramento County Main Jail	9996253	129805		D2016	Emergency Plumbing Fixtures	Eye Wash & Shower Station		1
23	Sacramento County Main Jail	9859726	129441	EQ-1041179	D7051	Fire Alarm Panel	Fully Addressable		1
24	Sacramento County Main Jail	9922826	130002		D7051	Fire Alarm System	Full System Upgrade, Standard Addressable		1
25	Sacramento County Main Jail	9859823	129424	EQ-1037418	D4033	Fire Extinguisher	Type ABC, up to 20 LB		1
26	Sacramento County Main Jail	9859663	129654	EQ-1036888	D4011	Fire Suppression System	Existing Sprinkler Heads, by SF		1
27	Sacramento County Main Jail	9859563	129748	EQ-1033464	D5011	Generator	Diesel	750 KW	1
28	Sacramento County Main Jail	9859829	129549	EQ-1033465	D5011	Generator	Diesel	750 KW	1
29	Sacramento County Main Jail	9859706	129973	EQ-1041981	E1042	Healthcare Equipment	Defibrillator (AED), Cabinet-Mounted		1
30	Sacramento County Main Jail	9922860	129995		E1042	Healthcare Equipment	Defibrillator (AED), Cabinet-Mounted		1

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
1	Replace	B1 - Basement 1 - B1FPMP - Fire Pump	Good	2	Lifecycle/Renewal		6	20	14	2025
2	Replace	01 - First Floor - Generator Room	Fair	3	Lifecycle/Renewal	1900	16	25	9	2025
3	Replace	01 - First Floor - Generator Room	Fair	3	Lifecycle/Renewal	1900	16	25	9	2025
4	Replace	01 - First Floor - Generator Room	Fair	3	Lifecycle/Renewal	1900	16	25	9	2025
5	Replace	All building - Throughout	Fair	3	Aged But Functional		27	30	3	2025
6	Replace	All building - Throughout	Fair	3	Lifecycle/Renewal	1989	35	40	5	2025
7	Replace	06 - Sixth Floor - 06ELV_B - Inmate Elevator	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
8	Replace	07 - Seventh Floor - 07ELVSLPELVD - Elevator	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
9	Replace	04 - Fourth Floor - 04ELV_A - Elevator	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
10	Replace	05 - Fifth Floor - 05ELV_A - Inmate Elevator	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
11	Replace	03 - Third Floor - 03ELVSLPELVD - Elevator	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
12	Replace	02 - Second Floor - 02ELV_A - Inmate Elevator A	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
13	Replace	B1 - Basement 1 - B1CTCNT - Court Control.	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
14	Replace	01 - First Floor - 01BKGWMN - Booking Women	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
15	Replace	09 - Ninth Floor - Secure Elevator Room	Fair	3	Aged But Functional		27	30	3	2025
16	Replace	All building - Throughout	Fair	3	Aged But Functional		27	30	3	2025
17	Replace	All building - Throughout	Fair	3	Aged But Functional		27	30	3	2025
18	Replace	All building - Throughout	Fair	3	Aged But Functional		7	10	3	2025
19	Replace	B1 - Basement 1 - B1OFF - Office Space	Fair	3	Lifecycle/Renewal		11	20	9	2025
20	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	1989	18	20	2	2025
21	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1988	11	20	9	2025
22	Replace	B1 - Basement 1 - B1LN - Laundry	Fair	3	Lifecycle/Renewal		11	20	9	2025
23	Replace	01 - First Floor - Fire Panel Room	Fair	3	Aged But Functional	2007	13	15	2	2025
24	Upgrade/Install	All building - Throughout	Fair	3	Aged But Functional		18	20	2	2025
25	Replace	All Building - Throughout	Fair	3	Lifecycle/Renewal	1900	6	10	4	2025
26	Replace	00505 - Floor - 00505 - Space	Fair	3	Aged But Functional	1989	23	25	2	2025
27	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	23	25	2	2025
28	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	23	25	2	2025
29	Replace	B1 - Basement 1 - B1OFF - Office Space	Fair	3	Aged But Functional	2018	8	10	2	2025
30	Replace	All building - Throughout	Fair	3	Aged But Functional		8	10	2	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
1	1	17800	EA	0		1.138	31	$ 26,535.88	No dataplate	No dataplate
2	1	25000	EA	0		1.138	31	$ 37,269.50	ASCO	C9403120099XC
3	1	30000	EA	0		1.138	31	$ 44,723.40	ASCO	C940380099XC
4	1	40000	EA	0		1.138	31	$ 59,631.20	ASCO	C9403120099XC
5	1249	990	EA	0		1.138	31	$ 1,843,364.38		
6	1249	6000	EA	0		1.138	31	$ 11,171,905.32		
7	2	9348	EA	0		1.138	31	$ 27,871.62	Chicago Pneumatics	Chicago
8	2	9348	EA	0		1.138	31	$ 27,871.62	Chicago Pneumatics	Chicago
9	2	9348	EA	0		1.138	31	$ 27,871.62	Chicago Pneumatics	Chicago
10	2	9348	EA	0		1.138	31	$ 27,871.62	Chicago Pneumatics	Chicago
11	2	9348	EA	0		1.138	31	$ 27,871.62	Chicago Pneumatics	Chicago
12	2	9348	EA	0		1.138	31	$ 27,871.62	Chicago Pneumatics	Chicago
13	9	9348	EA	0		1.138	31	$ 125,422.30	Chicago Pneumatics	Chicago
14	5	9348	EA	0		1.138	31	$ 69,679.06	Chicago Pneumatics	Chicago
15	1	7000	EA	0		1.138	31	$ 10,435.46	No dataplate	No dataplate
16	144	990	EA	0		1.138	31	$ 212,525.60		
17	156	350	EA	0		1.138	31	$ 81,396.59		
18	491000	0.65	SF	0		1.138	31	$ 475,782.44		
19	1	1500	EA	0		1.138	31	$ 2,236.17	Haws	NA
20	1	2300	EA	0		1.138	31	$ 3,428.79	Bradley	No dataplate
21	1	2300	EA	0		1.138	31	$ 3,428.79	Bradley	No dataplate
22	1	2300	EA	0		1.138	31	$ 3,428.79	Haws	No dataplate
23	1	15000	EA	0		1.138	31	$ 22,361.70	Notifier	NFS-640
24	491000	3	SF	0		1.138	31	$ 2,195,918.94		
25	50	150	EA	0		1.138	31	$ 11,180.85		
26	491000	1.07	SF	0		1.138	31	$ 783,211.09		
27	1	220000	EA	0		1.138	31	$ 327,971.60	Detroit Diesel	9123-7305
28	1	220000	EA	0		1.138	31	$ 327,971.60	Detroit Diesel	9123-7305
29	15	1500	EA	0		1.138	31	$ 33,542.55	Cardiac Science Corporation	939
30	35	1500	EA	0		1.138	31	$ 78,265.95		

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
1	No dataplate		11/09/2025	7CB037C9-3C87-45A0-9D78-8C4109CAE172			blue
2	936361	ATS-1	11/09/2025	6016695B-5953-453A-B415-6AA3258D4DF4		EQ-1032972	green
3	936362	ATS-2	11/09/2025	E44D1CDF-F783-4ED3-8C52-1421DC567729		EQ-1032973	orange
4	936363	ATS-3	11/09/2025	953B3639-58C5-4D02-9A8A-D8A935A5D580		EQ-1032974	orange
5		Transfer Door	07/20/2025		Transfer Door	Transfer Door	lavender
6		Transfer Door	07/19/2025		Transfer Door	Transfer Door	blue
7		6TH FLOOR SLIDERS	10/29/2025	13219A8A-06F2-4A14-A2DB-A67241733376		EQ-1028926	green
8		7TH FLOOR SLIDERS	10/29/2025	D528C11F-9778-4822-9BC8-F86B6445C4CE		EQ-1028927	green
9		4TH FLOOR SLIDERS	10/29/2025	3C0A9DDB-EEAE-4529-A7FA-A73A5C92C312		EQ-1028928	green
10		5TH FLOOR SLIDERS	10/29/2025	58DD891E-15C1-4890-945A-94078CED5034		EQ-1028929	green
11		3RD FLOOR SLIDERS	10/29/2025	475821CE-9266-43D8-9B8D-43B9506E975F		EQ-1028930	green
12		2ND FLOOR SLIDERS	10/29/2025	81D99F49-4ADB-4C55-A35A-D8DE0BA9D3A2		EQ-1028931	green
13		BASEMENT SLIDERS	10/28/2025	AEECE73A-CC3F-46C8-958A-8BB5F36575A0		EQ-1028932	green
14		1ST FLOOR SLIDERS	10/29/2025	49C2D41E-6A71-4DBA-B363-993D49DE3C1B		EQ-1028933	green
15	No dataplate		10/30/2025	46269AE2-BE79-4F5B-A754-23076CEE0A1E			blue
16		Transfer Door	07/20/2025	[Copy of ObsID 9960680]	Transfer Door	Transfer Door	grey
17		Transfer Door	07/20/2025	[Copy of ObsID 9960680]	Transfer Door	Transfer Door	grey
18			10/30/2025	4D41EE72-1F9C-448A-AD4A-51E0D7382759			blue
19	NA		11/09/2025	9B81826A-8523-44D4-B120-2D9D6B03AD23		*EQ-1028918	blue
20	No dataplate	EYE WASH STATION	11/09/2025	685F44B1-CAB0-41E9-9E55-457A70BA8AF3		EQ-1036916	orange
21	No dataplate	EYE WASH STATION	11/09/2025	571E4D13-2F56-449F-88C2-4D892338DB03		EQ-1036917	orange
22	No dataplate		11/09/2025	2E587D1F-3D77-42C0-A5D7-66247BCCD54A			blue
23	NA	NOTIFIER	11/09/2025	157C2546-4C41-447D-BC46-E9C079AA7131		EQ-1041179	green
24			10/30/2025	ADB4E163-0FE7-4714-9575-5F4B3EC89B70			blue
25		FIRE EXTINGUISHERS	11/09/2025	51B8BA20-A702-4FF4-9FFB-0710CC725D9D		EQ-1037418	orange
26		FIRE SPRINKLER	10/30/2025	62CDFAE6-80A9-4429-BCED-E92407909F83		EQ-1036888	green
27	12E-0894	GENERATOR #2	11/09/2025	F93DE71A-2330-49AF-A285-45490A520773		EQ-1033464	orange
28	12E-0895	GENERATOR #1	11/09/2025	0604537D-C731-4065-A204-D8BF454E4907		EQ-1033465	orange
29	6011982	AED DEFIBRILLATOR	10/30/2025	5C5DAEE5-76B6-4CC6-ACD4-93A8D0B9DD88		EQ-1041981	green
30			10/30/2025	BA18047F-E0DC-474F-99BA-4091212E0B8E			blue

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
31	Sacramento County Main Jail	9922863	129993		D6061	Intercom/PA System	Public Address Upgrade, Facility-Wide		1
32	Sacramento County Main Jail	9927093	130429		D5021	Secondary Transformer	Dry, Stepdown	140 KVA	1
33	Sacramento County Main Jail	9927096	130417		D5021	Secondary Transformer	Dry, Stepdown	100 KVA	1
34	Sacramento County Main Jail	9927106	130421		D5021	Secondary Transformer	Dry, Stepdown	100 KVA	1
35	Sacramento County Main Jail	9927074	130415		D5021	Secondary Transformer	Dry, Stepdown	100 KVA	1
36	Sacramento County Main Jail	9927089	130419		D5021	Secondary Transformer	Dry, Stepdown	100 KVA	1
37	Sacramento County Main Jail	9959441	130449		D5021	Secondary Transformer	Dry, Stepdown	140 KVA	1
38	Sacramento County Main Jail	9859610	129291	EQ-1033541	D5021	Secondary Transformer	Dry, Stepdown, 225 KVA	225 KVA	1
39	Sacramento County Main Jail	9859697	129372	EQ-1033349	D5021	Secondary Transformer	Dry, Stepdown, 300 KVA	300 KVA	1
40	Sacramento County Main Jail	9922830	130005		D7031	Security/Surveillance System	Full System Upgrade, Average Density		1
41	Sacramento County Main Jail	9859582	129691	EQ-1042156	D4011	Supplemental Components	Fire Jockey Pump	.5 HP	1
42	Sacramento County Main Jail	9927084	130407		D4011	Supplemental Components	Fire Riser, Wet	4 IN	1
43	Sacramento County Main Jail	9859530	129440	EQ-1032358	D5021	Switchboard	120/208 V	600 AMP	1
44	Sacramento County Main Jail	9859723	129539	EQ-1032701	D5021	Switchboard	120/208 V	800 AMP	1
45	Sacramento County Main Jail	9859656	129449	EQ-1032356	D5021	Switchboard	120/208 V, 1200 AMP	1200 AMP	1
46	Sacramento County Main Jail	9859578	129450	EQ-1031275	D5021	Switchboard	120/208 V, 800 AMP	800 AMP	1
47	Sacramento County Main Jail	9859682	129507	EQ-1031938	D5021	Switchboard	277/480 V	2400 AMP	1
48	Sacramento County Main Jail	9859554	129632	EQ-1033728	D5021	Switchboard	277/480 V	2000 AMP	1
49	Sacramento County Main Jail	9996260	129848		D5021	Switchboard	277/480 V	2000 AMP	1
50	Sacramento County Main Jail	9922855	130262		D1012	Vertical Lift	Wheelchair, 5' Rise		1
51	Sacramento County Main Jail	9927105	130412		D5023	Distribution Panel	120/208 V	600 AMP	1
52	Sacramento County Main Jail	9996282	129844		D2012	Water Softener	Domestic Water, 300k Grains & 80 GPM	10 GAL	2
53	Sacramento County Main Jail	9859351	129634	EQ-1027656	D2061	Air Compressor	Tank-Style, 25 HP	35 HP	2
54	Sacramento County Main Jail	9859861	129731	EQ-1027657	D2061	Air Compressor	Tank-Style, 25 HP	35 HP	2
55	Sacramento County Main Jail	9859396	129564	EQ-1028972	D3061	Axial Flow Fan	In-Line, 2 HP Motor, 5001 to 10000 CFM	10000 CFM	2
56	Sacramento County Main Jail	9859665	129662	EQ-1028978	D3061	Axial Flow Fan	In-Line, 5 HP Motor, 10001 to 20000 CFM	20000 CFM	2
57	Sacramento County Main Jail	9859650	129472	EQ-1036401	D2014	Backflow Preventer	Domestic Water	6 IN	2
58	Sacramento County Main Jail	9859446	129449	EQ-1036402	D2014	Backflow Preventer	Domestic Water	6 IN	2
59	Sacramento County Main Jail	9859337	129553	EQ-1032778	D8015	BAS/HVAC Controls	DDC Control Panel		2
60	Sacramento County Main Jail	9859550	129571	EQ-1028917	D3063	Exhaust Fan	Roof or Wall-Mounted, 36"Damper, 8501 to 15000 CFM	15000 CFM	2
61	Sacramento County Main Jail	9859727	129436	EQ-1035628	D3055	Fan Coil Unit	Hydronic Terminal, 200 to 400 CFM	400 CFM	2
62	Sacramento County Main Jail	9859841	129295	EQ-1036762	D2012	Pump	Circulation, Domestic Water	1.5 HP	2
63	Sacramento County Main Jail	9859374	129359	EQ-1028916	D2012	Pump	Circulation/Booster, Domestic Water	20 HP	2
64	Sacramento County Main Jail	9859629	129456	EQ-1036005	D2012	Pump	Circulation/Booster, Domestic Water	7.5 HP	2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
31	Replace	All building - Throughout	Fair	3	Aged But Functional		18	20	2	2025
32	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional		27	30	3	2025
33	Replace	09 - Ninth Floor - Secure Elevator Room	Fair	3	Lifecycle/Renewal	2010	16	30	14	2025
34	Replace	09 - Ninth Floor - Secure Elevator Room	Fair	3	Lifecycle/Renewal	2010	16	30	14	2025
35	Replace	09 - Ninth Floor - Secure Elevator Room	Fair	3	Lifecycle/Renewal	2010	16	30	14	2025
36	Replace	09 - Ninth Floor - Secure Elevator Room	Fair	3	Lifecycle/Renewal	2011	15	30	15	2025
37	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional		26	30	4	2025
38	Replace	01 - First Floor - Generator Room	Fair	3	Lifecycle/Renewal		19	30	11	2025
39	Replace	01 - First Floor - Generator Room	Fair	3	Lifecycle/Renewal		19	30	11	2025
40	Replace	All building - Throughout	Fair	3	Aged But Functional		14	15	1	2025
41	Replace	B1 - Basement 1 - B1FPMP - Fire Pump	Fair	3	Lifecycle/Renewal	2017	9	20	11	2025
42	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Lifecycle/Renewal		36	40	4	2025
43	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	36	40	4	2025
44	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	36	40	4	2025
45	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	36	40	4	2025
46	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	36	40	4	2025
47	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	36	40	4	2025
48	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	36	40	4	2025
49	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	1989	36	40	4	2025
50	Renovate	01 - First Floor - 01DOCK - Loading Dock	Fair	3	Aged But Functional		21	25	4	2025
51	Replace	09 - Ninth Floor - Communication Room	Poor	4	Safety		30	30	0	2025
52	Replace	B1 - Basement 1 - B1BLR - Boiler	Excellent	1	Lifecycle/Renewal	2025	1	25	24	2025
53	Replace	B1 - Basement 1 - B1BLR - Boiler	Good	2	Lifecycle/Renewal	2024	2	20	18	2025
54	Replace	B1 - Basement 1 - B1BLR - Boiler	Good	2	Lifecycle/Renewal	2024	2	20	18	2025
55	Replace	B1 - Basement 1 - B1OFF - Office Space	Good	2	Lifecycle/Renewal	2020	6	20	14	2025
56	Replace	B1 - Basement 1 - B1CST - Pharmacy	Good	2	Lifecycle/Renewal	2020	6	20	14	2025
57	Replace	01 - First Floor - Main Backflow	Good	2	Lifecycle/Renewal	2023	3	30	27	2025
58	Replace	01 - First Floor - Main Backflow	Good	2	Lifecycle/Renewal	2023	3	30	27	2025
59	Replace	B1 - Basement 1 - B1BLR - Boiler	Good	2	Lifecycle/Renewal	1900	5	15	10	2025
60	Replace	02 - Second Floor - 02EXT - External	Good	2	Lifecycle/Renewal	2021	5	20	15	2025
61	Replace	B1 - Basement 1 - B1CALID - Ca Id	Good	2	Lifecycle/Renewal	2023	3	20	17	2025
62	Replace	B1 - Basement 1 - B1BLR - Boiler	Good	2	Lifecycle/Renewal	2024	2	15	13	2025
63	Replace	B1 - Basement 1 - B1BLR - Boiler	Good	2	Lifecycle/Renewal	2018	8	25	17	2025
64	Replace	B1 - Basement 1 - B1BSTPMP - Booster Pump	Good	2	Lifecycle/Renewal	1988	6	25	19	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
31	491000	1.65	SF	0		1.138	31 $	1,207,755.42		
32	1	20000	EA	0		1.138	31 $	29,815.60	Field Transformers	7487
33	1	16000	EA	0		1.138	31 $	23,852.48	Jefferson Electric	300-5043-107
34	1	16000	EA	0		1.138	31 $	23,852.48	Jefferson Electric	300-5043-107
35	1	16000	EA	0		1.138	31 $	23,852.48	Jefferson Electric	300-5043-107
36	1	16000	EA	0		1.138	31 $	23,852.48	Jefferson Electric	300-5043-107
37	1	20000	EA	0		1.138	31 $	29,815.60	Field Transformers	7487
38	1	25000	EA	0		1.138	31 $	37,269.50	Square D	CAT.225T3HF-CU
39	1	30000	EA	0		1.138	31 $	44,723.40	Square D	CAT.300T3HF-CU
40	491000	8.69	SF	0		1.138	31 $	6,357,624.52		
41	1	800	EA	0		1.138	31 $	1,192.62	Pentair Aurora	16-2484394
42	9	10000	EA	0		1.138	31 $	134,170.20		
43	1	45000	EA	0		1.138	31 $	67,085.10	Square D	CAT.49-83204-04
44	1	50000	EA	0		1.138	31 $	74,539.00	Square D	CAT4983204-03
45	1	66000	EA	0		1.138	31 $	98,391.48	Square D	CAT.49-83204-05
46	1	50000	EA	0		1.138	31 $	74,539.00	Square D	FO49-83204-17
47	1	90000	EA	25		1.138	31 $	159,775.20	Square D	NA
48	1	90000	EA	100		1.138	31 $	236,590.20	Square D	FO83204.1
49	1	90000	EA	100		1.138	31 $	236,590.20	Square D	NA
50	1	17000	EA	0		1.138	31 $	25,343.26	No dataplate	No dataplate
51	1	7000	EA	0		1.138	31 $	10,435.46	Industrial Electric	No dataplate
52	1	10700	EA	0		1.138	31 $	15,951.35		
53	1	41400	EA	10		1.138	31 $	66,429.61	Kaeser	SK 20T Sigma
54	1	41400	EA	10		1.138	31 $	66,429.61	Kaeser	SK 20T Sigma
55	1	3500	EA	0		1.138	31 $	5,217.73	Greenheck	BSQ-14HP-7-X
56	1	4400	EA	0		1.138	31 $	6,559.43	Greenheck	BSQ-200
57	1	10500	EA	0		1.138	31 $	15,653.19	Wilkins	375AST
58	1	10500	EA	0		1.138	31 $	15,653.19	Wilkins	375AST
59	1	4980	EA	0		1.138	31 $	7,424.08	Tesco	24-000
60	1	5600	EA	0		1.138	31 $	8,348.37	Greenheck	LB-54-50-X
61	1	1670	EA	0		1.138	31 $	2,489.60	York	YBSH036EL300CANNA8N00
62	1	4600	EA	0		1.138	31 $	6,857.59	Baldor Reliance	JM3154
63	3	13600	EA	0		1.138	31 $	60,823.82	Flowtherm	FMV
64	2	6800	EA	0		1.138	31 $	20,274.61	Nidec Motor Corporation	

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
31			10/30/2025	8F1024DD-1A4B-42F8-B089-91541E82B015			blue
32	0487		10/30/2025	7F2794EE-EBB4-4590-8863-FE5B5705635C			blue
33	0002		10/30/2025	D306690C-F829-41E7-8F60-5B8315A77445			blue
34	0003		10/30/2025	3A5B863C-1885-452E-872A-383740A4F14E			blue
35	0004		10/30/2025	017E5E14-850A-4312-9E41-0755EDDEB010			blue
36	0001		10/30/2025	3BD8A5E6-61DB-4363-8F96-9BE124B514BE			blue
37	0587		10/30/2025	718DEF56-43B0-40D8-8A0D-AB910213ABF3			blue
38	179382	TX-3	11/09/2025	984F984B-0DB1-43F2-8D4F-B22AC529F6C6		EQ-1033541	orange
39	179381	TX-2	11/09/2025	0110908D-BABF-4860-9A64-30E21EA401E8		EQ-1033349	green
40			10/30/2025	649D6966-ACF5-49E6-910E-AD9454310FDE			blue
41		JOCKEY PUMP	11/09/2025	643040A2-F969-4217-ACCD-AAE8CC51F343		EQ-1042156	green
42			10/30/2025	5BDFF932-1DE2-4C4C-BF87-C146DED8A8B5			blue
43	A940792	LEDB	11/09/2025	BEEE3E49-F1D6-4AA7-A2B3-EAF6C4B0ADB5		EQ-1032358	green
44	A940843	LNDB	11/09/2025	C3BA9071-D28E-432A-BA3D-22CF9C3C6FA0		EQ-1032701	orange
45	A940783	HEDB	10/30/2025	0B99850B-5BC5-46CD-B5DF-B4B85B51C3AD		EQ-1032356	green
46	A940786	HNDB-A	10/30/2025	80B17D90-5C94-4CA4-A4D2-C6DCE7E518DC		EQ-1031275	green
47	NA	LNBK1-B	11/09/2025	D4759516-1900-420A-B91F-E54567EFB228		EQ-1031938	orange
48	A916942	HNDB	11/09/2025	37CD77F6-0AF5-46C0-921D-9C8A43260CD8		EQ-1033728	orange
49	NA		11/09/2025	64AFD908-7147-47E3-B907-BED2F118E182			blue
50	No dataplate		10/30/2025	A798383B-B87C-41D6-94C6-8B10AE53F348			blue
51	No dataplate		10/30/2025	4C217470-7243-44FD-BD9C-98320E7AAD91	Industrial Electric Mfg. (IEM) panels can fail to trip during an ove		blue
52			11/09/2025	756C8EA1-E1CB-461C-BF8E-79A3953D6B77			blue
53	1256	DOOR AIR COMPRESSOR 1	11/09/2025	714518BA-9CA3-41F8-8B99-5D0D2F9404F8		EQ-1027656	green
54	1254	DOOR AIR COMPRESSOR 2	11/09/2025	B626EFEF-3537-4417-9DCE-B1AA3F38652E		EQ-1027657	green
55	16171649	EF 8	11/09/2025	DEB89F0B-0C90-4FDA-B5C6-FFF448B71BF1		EQ-1028972	green
56		EF-9, PHARMACY	11/09/2025	13C395C1-B2E6-4996-A53E-987F24077674		EQ-1028978	green
57	44463C	00505-15140-0001	11/09/2025	133191DA-AD78-4B5C-95CC-07DD5398DE05		EQ-1036401	orange
58	43519C	00505-15140-0004	11/09/2025	140E8F8E-96C9-47DA-88A9-AE55542285B0		EQ-1036402	green
59	NA	SEWAGE PUMP -1	11/09/2025	685108F4-D14C-4999-9732-E3F3C116E4CA		EQ-1032778	orange
60	16173536 20B	REF-13	11/09/2025	2C01B802-A5EE-4066-AAA9-48EE444B6DC3		EQ-1028917	green
61	230800247	CAL-ID	11/09/2025	BB954987-CBCC-4F7A-AC88-04A1E74A726E		EQ-1035628	orange
62	W2404231633	HWP 1	11/09/2025	5E562184-199F-476E-A9A3-EB415CE2CD8D		EQ-1036762	orange
63	NA	DHW BOOSTER PUMPS 3-8	11/09/2025	8898BC25-D531-4AC6-A42A-721D490E3A21	Maintenance views this as one asse	EQ-1028916	green
64		BOOSTER PUMP	11/09/2025	A7317E94-58F9-459D-A2AB-208A0C4A83E0		EQ-1036005	orange

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
65	Sacramento County Main Jail	9859677	129688	EQ-1028915	D3051	Pump	Distribution, HVAC Chilled or Condenser Water	30 HP	2
66	Sacramento County Main Jail	9859787	129785	EQ-1036323	D3051	Pump	Distribution, HVAC Chilled or Condenser Water, 26 to 50 HP	30 HP	2
67	Sacramento County Main Jail	9996256	129829		D5039	Variable Frequency Drive	VFD, by HP of Motor	30 HP	2
68	Sacramento County Main Jail	9996291	129827		D5039	Variable Frequency Drive	VFD, by HP of Motor	30 HP	2
69	Sacramento County Main Jail	9996288	129826		D5039	Variable Frequency Drive	VFD, by HP of Motor	30 HP	2
70	Sacramento County Main Jail	9996285	129828		D5039	Variable Frequency Drive	VFD, by HP of Motor	30 HP	2
71	Sacramento County Main Jail	9996251	129822		D2061	Air Compressor	Tank-Style	10 HP	2
72	Sacramento County Main Jail	9859366	129656	EQ-1038690	D2061	Air Compressor	Tank-Style, 5 HP	5 HP	2
73	Sacramento County Main Jail	9859352	129618	EQ-1039263	D2061	Air Compressor	Tank-Style, 5 HP	5 HP	2
74	Sacramento County Main Jail	9859643	129640	EQ-1036343	D2061	Air Compressor	Tank-Style, 25 HP	5 HP	2
75	Sacramento County Main Jail	9859497	129657	EQ-1035272	D3037	Air Conditioner	Air Conditioner, Portable, 1.5 to 2 TON, Replace	2 TON	2
76	Sacramento County Main Jail	9859742	129345	EQ-1041170	D3037	Air Conditioner	Air Conditioner, Portable, 1.5 to 2 TON, Replace	2 TON	2
77	Sacramento County Main Jail	9859529	129732	EQ-1035054	D3055	Air Handler	any type, Heating and Cooling Coils		2
78	Sacramento County Main Jail	9859372	129610	EQ-1035055	D3055	Air Handler	any type, Heating and Cooling Coils		2
79	Sacramento County Main Jail	9859513	129592	EQ-1035056	D3055	Air Handler	any type, Heating and Cooling Coils		2
80	Sacramento County Main Jail	9859415	129340	EQ-1035057	D3055	Air Handler	any type, Heating and Cooling Coils		2
81	Sacramento County Main Jail	9859401	129625	EQ-1035058	D3055	Air Handler	any type, Heating and Cooling Coils		2
82	Sacramento County Main Jail	9859447	129710	EQ-1035059	D3055	Air Handler	any type, Heating and Cooling Coils		2
83	Sacramento County Main Jail	9859370	129289	EQ-1035801	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 10001 to 15000 CFM	15000 CFM	2
84	Sacramento County Main Jail	9859378	129367	EQ-1035800	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 1201 to 2400 CFM	1500 CFM	2
85	Sacramento County Main Jail	9859455	129609	EQ-1035437	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 2401 to 4000 CFM	4000 CFM	2
86	Sacramento County Main Jail	9859631	129349	EQ-1035438	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 2401 to 4000 CFM	4000 CFM	2
87	Sacramento County Main Jail	9859860	129650	EQ-1035444	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 4001 to 6000 CFM	6000 CFM	2
88	Sacramento County Main Jail	9859784	129613	EQ-1035796	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 4001 to 6000 CFM	6000 CFM	2
89	Sacramento County Main Jail	9859506	129294	EQ-1035802	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 4001 to 6000 CFM	6000 CFM	2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
65	Replace	B1 - Basement 1 - B1BLR - Boiler	Good	2	Lifecycle/Renewal	2018	8	25	17	2025
66	Replace	B1 - Basement 1 - B1PUMP - Pump	Good	2	Lifecycle/Renewal	1988	6	25	19	2025
67	Replace/Install	B1 - Basement 1 - B1BSTPMP - Booster Pump	Good	2	Lifecycle/Renewal		6	20	14	2025
68	Replace/Install	B1 - Basement 1 - B1BSTPMP - Booster Pump	Good	2	Lifecycle/Renewal		6	20	14	2025
69	Replace/Install	B1 - Basement 1 - B1BSTPMP - Booster Pump	Good	2	Lifecycle/Renewal		6	20	14	2025
70	Replace/Install	B1 - Basement 1 - B1BSTPMP - Booster Pump	Good	2	Lifecycle/Renewal		6	20	14	2025
71	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal		10	20	10	2025
72	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	2003	17	20	3	2025
73	Replace	B1 - Basement 1 - B1LNMC2 - Laundry Mechanical	Fair	3	Aged But Functional	1998	18	20	2	2025
74	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	1988	18	20	2	2025
75	Replace	B1 - Basement 1 - B1CST - Pharmacy	Fair	3	Lifecycle/Renewal	2018	7	10	3	2025
76	Replace	01 - First Floor - 01BKGMEN - Booking Men	Fair	3	Aged But Functional	2006	8	10	2	2025
77	Refurbish	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	12	15	3	2025
78	Refurbish	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	11	15	4	2025
79	Refurbish	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	11	15	4	2025
80	Refurbish	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	11	15	4	2025
81	Refurbish	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	12	15	3	2025
82	Refurbish	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional	1989	13	15	2	2025
83	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
84	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	18	25	7	2025
85	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025
86	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025
87	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	1988	27	30	3	2025
88	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
89	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)		Total Cost	Make	Model
65	3	22000	EA	0		1.138	31	$	98,391.48	Flowtherm	FMV
66	1	22000	EA	0		1.138	31	$	32,797.16	G.E.	5K5286AL205B
67	1	14700	EA	0		1.138	31	$	21,914.47	ABB	No dataplate
68	1	14700	EA	0		1.138	31	$	21,914.47	ABB	No dataplate
69	1	14700	EA	0		1.138	31	$	21,914.47	ABB	No dataplate
70	1	14700	EA	0		1.138	31	$	21,914.47	ABB	No dataplate
71	1	15900	EA	0		1.138	31	$	23,703.40	Ingersoll Rand	2475
72	1	10600	EA	0		1.138	31	$	15,802.27	Kaeser	TA11
73	1	10600	EA	0		1.138	31	$	15,802.27	Curtis	CQ969A-3
74	1	41400	EA	0		1.138	31	$	61,718.29	Kaeser	SM 8
75	1	2900	EA	0		1.138	31	$	4,323.26	Movin Cool	0ffice Pro 18
76	1	2900	EA	0		1.138	31	$	4,323.26	Movin Cool	Office Pro 36
77	1	44000	EA	0		1.138	31	$	65,594.32	Q Dot Corp	
78	1	44000	EA	0		1.138	31	$	65,594.32	Q Dot Corp	
79	1	44000	EA	0		1.138	31	$	65,594.32	Q Dot Corp	
80	1	44000	EA	0		1.138	31	$	65,594.32	Q Dot Corp	
81	1	44000	EA	0		1.138	31	$	65,594.32	Q Dot Corp	
82	1	44000	EA	0		1.138	31	$	65,594.32	Q Dot Corp	
83	1	70000	EA	0		1.138	31	$	104,354.60	Trane	CCBD35BWED
84	1	15000	EA	0		1.138	31	$	22,361.70	Trane	CCDB254WOD
85	1	22000	EA	0		1.138	31	$	32,797.16	Trane	CCDB06CWED
86	1	22000	EA	0		1.138	31	$	32,797.16	Trane	CCDB06CWED
87	1	31000	EA	0		1.138	31	$	46,214.18	Trane	CCBD17BEOD
88	1	31000	EA	0		1.138	31	$	46,214.18	Trane	220000A
89	1	31000	EA	0		1.138	31	$	46,214.18	Trane	CCDB12CEOD

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
65		DCW BOOSTER PUMPS 3-8	11/09/2025	8969E6AD-49CE-42E9-8690-22B716617EF8		EQ-1028915	orange
66	KY C67045A	CHWP-3	11/09/2025	B4FAEE9F-CA6F-4200-B7A8-57A056BAF57F		EQ-1036323	orange
67	No dataplate	CBP 2 B	11/09/2025	8BC1E373-F573-417C-B1B3-E731F0FB6C82			blue
68	No dataplate	HBP 2 B	11/09/2025	18B6B655-05F8-4F55-B0BE-F85917088AD5			blue
69	No dataplate	HBP 2 A	11/09/2025	44C85FE1-D9C9-44BC-B0D1-E882549CF9E2			blue
70	No dataplate	CBP 2 A	11/09/2025	FF2337BE-0C8F-48F8-9CD0-8AB049D16E93			blue
71	NAR13283511		11/09/2025	0107C9CC-9EC9-4AFC-97DE-42043056E054			blue
72	1212	CAC AIR DRYER	11/09/2025	35742678-0488-47CC-AB99-98D65EA5A66C		EQ-1038690	green
73	08L97059 BL	LNDRY AIR COMPRESSOR	11/09/2025	D333BBAB-F928-4018-A5C3-3D71D4DCBB21		EQ-1039263	green
74	""""#1=86414_#2=86413	CONTROL AIR COMPRESSOR	11/09/2025	B4AC5806-A17C-42BB-914E-BE1F78CF6B7A		EQ-1036343	green
75	07181081180	MOVINCOOL SPOT COOLER	11/09/2025	69C3074B-9E65-4A92-B1CA-4B8F5502F140		EQ-1035272	orange
76	0705 0154 360	DVR ROOM	11/09/2025	3302DA73-038D-4347-BE13-3459E93A6FF1		EQ-1041170	green
77		ENERGY RECOVERY COIL	11/09/2025	4FCB2D0D-29D0-4941-97F5-FB78C6555815		EQ-1035054	green
78		ENERGY RECOVERY COIL	11/09/2025	2CD3A924-62F0-45EA-9DDC-9F648B576B22		EQ-1035055	green
79		ENERGY RECOVERY COIL	11/09/2025	42F81766-CEA1-427C-A021-B441A8C3F02B		EQ-1035056	green
80		ENERGY RECOVERY COIL	11/09/2025	0B0FE464-CA2E-418E-A662-7CD3822D8655		EQ-1035057	green
81		ENERGY RECOVERY COIL	11/09/2025	EEDEA8C8-CE4F-43EE-AF23-1DBD16995821		EQ-1035058	green
82		ENERGY RECOVERY COIL	11/09/2025	B38F0E39-BA3E-4714-8B83-B6AF3D423C48		EQ-1035059	green
83	K85H72024	AC1	11/09/2025	F4041F39-DCD0-45F0-88E3-8E85175B41DA		EQ-1035801	green
84	K85H72920	HV-1	11/09/2025	86F42296-78A3-4889-88F5-A240DE0F9A37		EQ-1035800	green
85	K85H72930	AC6	11/09/2025	97C5AC1D-B2AC-4D15-941E-A027AF5EA33B		EQ-1035437	green
86	K85H72931	AC7	11/09/2025	CFD2005F-2BDC-4862-9BA9-8CF7988FB085		EQ-1035438	green
87	K85H72925	AC15	11/09/2025	E7046553-8CBE-458E-9EA3-50D5135B6204		EQ-1035444	green
88	K86B91342	AC18	11/09/2025	4539BB90-B92B-44B8-AB3B-8962D04E167F		EQ-1035796	green
89	K85H722929	AC2	11/09/2025	00A5DEEB-4792-4CA4-A2E6-1654E2BD015F		EQ-1035802	green

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
90	Sacramento County Main Jail	9859803	129473	EQ-1035439	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
91	Sacramento County Main Jail	9859833	129285	EQ-1035440	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
92	Sacramento County Main Jail	9859365	129434	EQ-1035441	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
93	Sacramento County Main Jail	9859790	129378	EQ-1035442	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
94	Sacramento County Main Jail	9859646	129701	EQ-1035634	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
95	Sacramento County Main Jail	9859641	129325	EQ-1035794	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
96	Sacramento County Main Jail	9859769	129559	EQ-1035795	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
97	Sacramento County Main Jail	9859830	129455	EQ-1035798	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
98	Sacramento County Main Jail	9859472	129524	EQ-1035799	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
99	Sacramento County Main Jail	9859765	129776	EQ-1035803	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
100	Sacramento County Main Jail	9859809	129599	EQ-1035805	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 6001 to 8000 CFM	8000 CFM	2
101	Sacramento County Main Jail	9859645	129279	EQ-1035443	D3055	Air Handler	Interior AHU, Easy/Moderate Access, 8001 to 10000 CFM	10000 CFM	2
102	Sacramento County Main Jail	9859637	129406	EQ-1034012	D3061	Axial Flow Fan	In-Line, 1 HP Motor, 3001 to 5000 CFM	5000 CFM	2
103	Sacramento County Main Jail	9859783	129469	EQ-1034277	D3061	Axial Flow Fan	In-Line, 1 HP Motor, 3001 to 5000 CFM	5000 CFM	2
104	Sacramento County Main Jail	9859827	129409	EQ-1034357	D3061	Axial Flow Fan	In-Line, 5 HP Motor, 10001 to 20000 CFM	20000 CFM	2
105	Sacramento County Main Jail	9859680	129423	EQ-1034840	D3061	Axial Flow Fan	In-Line, 5 HP Motor, 10001 to 20000 CFM	20000 CFM	2
106	Sacramento County Main Jail	9859612	129444	EQ-1034842	D3061	Axial Flow Fan	In-Line, 5 HP Motor, 10001 to 20000 CFM	20000 CFM	2
107	Sacramento County Main Jail	9859672	129687	EQ-1034844	D3061	Axial Flow Fan	In-Line, 5 HP Motor, 10001 to 20000 CFM	20000 CFM	2
108	Sacramento County Main Jail	9859635	129382	EQ-1034358	D3061	Axial Flow Fan	In-Line, 7.5 HP Motor, 20001 to 30000 CFM	30000 CFM	2
109	Sacramento County Main Jail	9859740	129495	EQ-1034010	D3061	Axial Flow Fan	In-Line, 10 HP Motor, 30001 to 40000 CFM	40000 CFM	2
110	Sacramento County Main Jail	9859493	129667	EQ-1034838	D3061	Axial Flow Fan	In-Line, 10 HP Motor, 30001 to 40000 CFM	40000 CFM	2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
90	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
91	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
92	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	1988	28	30	2	2025
93	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	1988	27	30	3	2025
94	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
95	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
96	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
97	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
98	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
99	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
100	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
101	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	1988	27	30	3	2025
102	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional	1988	18	20	2	2025
103	Replace	02 - Second Floor - 02CUST - Custodial Closet	Fair	3	Aged But Functional	1988	18	20	2	2025
104	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	1988	18	20	2	2025
105	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Lifecycle/Renewal	1988	16	20	4	2025
106	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Lifecycle/Renewal	1988	16	20	4	2025
107	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Lifecycle/Renewal	1988	16	20	4	2025
108	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Lifecycle/Renewal	1988	11	20	9	2025
109	Replace	B1 - Basement 1 - Property	Fair	3	Aged But Functional	1988	18	20	2	2025
110	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Lifecycle/Renewal	1988	13	20	7	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)		Total Cost	Make	Model
90	1	40000	EA	0		1.138	31	$	59,631.20	Trane	CCDB258EED
91	1	40000	EA	0		1.138	31	$	59,631.20	Trane	CCDB12CCCD
92	1	40000	EA	0		1.138	31	$	59,631.20	Trane	CCDB12CWED
93	1	40000	EA	0		1.138	31	$	59,631.20	Trane	CCDB17BWED
94	1	40000	EA	0		1.138	31	$	59,631.20	Trane	CCDB31BWED
95	1	40000	EA	0		1.138	31	$	59,631.20	Trane	N/A
96	1	40000	EA	0		1.138	31	$	59,631.20	Trane	420000A
97	1	40000	EA	0		1.138	31	$	59,631.20	Trane	CCDB17BEOD
98	1	40000	EA	0		1.138	31	$	59,631.20	Trane	N/A
99	1	40000	EA	0		1.138	31	$	59,631.20	Trane	CCBD21EWED
100	1	40000	EA	0		1.138	31	$	59,631.20	Trane	CCDB14CWED
101	1	49000	EA	0		1.138	31	$	73,048.22	Trane	CCDB35BWED
102	1	2800	EA	0		1.138	31	$	4,174.18	Jenn Aire	122ILBADFSH
103	1	2800	EA	0		1.138	31	$	4,174.18	Trane	
104	1	4400	EA	0		1.138	31	$	6,559.43	Trane	36B-9-1HC
105	1	4400	EA	0		1.138	31	$	6,559.43	Trane	30B-9-1HC
106	1	4400	EA	0		1.138	31	$	6,559.43	Trane	130B-9-1MC
107	1	4400	EA	0		1.138	31	$	6,559.43	Trane	NA
108	1	5600	EA	0		1.138	31	$	8,348.37	No dataplate	No dataplate
109	1	7000	EA	0		1.138	31	$	10,435.46	Trane	33B-9-1 HC
110	1	7000	EA	0		1.138	31	$	10,435.46	Trane	CA35

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
90	K85J72933	AC8	11/09/2025	7CE19294-976A-47CC-A178-008A0AA5C401		EQ-1035439	green
91	K85J72928	AC11	11/09/2025	0C10654D-D0FD-4B84-8066-68EB1F8884AE		EQ-1035440	green
92	K85H72932	AC12	11/09/2025	49205B67-4224-43A4-AA07-3F63A7803D33		EQ-1035441	green
93	K85H72924	AC13	11/09/2025	21BC58C8-529B-4517-9FE3-735A40A08D60		EQ-1035442	green
94	K85H72921	AC5	11/09/2025	76C43C1D-6778-4AF2-8985-931F11F8DB73		EQ-1035634	green
95	K86B91340	AC16	11/09/2025	B3694B7C-3F3C-420E-90EE-33679D37FD40		EQ-1035794	green
96	K86B91341	AC17	11/09/2025	4C6954BE-48A9-4B37-9861-CFB42CCE6D67		EQ-1035795	green
97	K85H72923	AC9	11/09/2025	2937F9E3-7FAB-4826-9393-D1E6F39A24DE		EQ-1035798	green
98	K85H72027	AC10	11/09/2025	1E4E59C5-6D3B-4778-B7D8-315C153CEA28		EQ-1035799	green
99	K85H72922	AC4	11/09/2025	325D8336-990C-4870-817F-39D145FC94FA		EQ-1035803	green
100	K85H72026	AC3	11/09/2025	5245D584-09E3-4BF1-8893-7CA89DFF94AB		EQ-1035805	green
101	K85H72025	AC14	11/09/2025	3B8CE8EA-2D91-4995-8991-92DE07C4BAF4		EQ-1035443	green
102		EF 10	11/09/2025	60E9F31A-7B96-4FBD-9E1B-636289151C55		EQ-1034012	green
103		EF 13	11/09/2025	95EF704E-8FF8-4AA7-9A23-6B4E7EF9CE74	Lock broken, no access.	EQ-1034277	green
104	L85F29129	RF 4	11/09/2025	D4793E44-CC75-4606-98E7-186508E38574		EQ-1034357	green
105	L85F29125	RF 3	11/09/2025	F14C2873-847F-4B66-8BEB-D5BE374A43F9	Motor was replaced.	EQ-1034840	green
106	L85F29128 (6)	RF 9	11/09/2025	EB3F889E-FE3C-4137-BC11-4AE6CDD26D8D	Motor was replaced.	EQ-1034842	green
107	NA	RF 10	11/09/2025	F53F6F5D-AA0F-4BF2-A27C-1BB60E8D6D2B		EQ-1034844	orange
108	No dataplate	RF 5	11/09/2025	F972A7C9-8DD2-4BA8-A590-3B3BFC1125B1		EQ-1034358	orange
109	L85F29122	EF 7	11/09/2025	78FF884E-3854-4A25-BF81-F24A3B51F760		EQ-1034010	green
110	NA	RF 1	11/09/2025	CC834EB0-A35C-46A4-8974-8802965F826A		EQ-1034838	orange

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
111	Sacramento County Main Jail	9859438	129531	EQ-1034839	D3061	Axial Flow Fan	In-Line, 10 HP Motor, 30001 to 40000 CFM	40000 CFM	2
112	Sacramento County Main Jail	9859492	129280	EQ-1036400	D2014	Backflow Preventer	Domestic Water	.75 IN	2
113	Sacramento County Main Jail	9859551	129374	EQ-1036403	D2014	Backflow Preventer	Domestic Water	0.75 IN	2
114	Sacramento County Main Jail	9859811	129715	EQ-1036405	D2014	Backflow Preventer	Domestic Water	1 IN	2
115	Sacramento County Main Jail	9859576	129649	EQ-1036406	D2014	Backflow Preventer	Domestic Water	1 IN	2
116	Sacramento County Main Jail	9859700	129433	EQ-1036407	D2014	Backflow Preventer	Domestic Water	2 IN	2
117	Sacramento County Main Jail	9859832	129673	EQ-1036408	D2014	Backflow Preventer	Domestic Water	1 IN	2
118	Sacramento County Main Jail	9859659	129421	EQ-1036661	D2014	Backflow Preventer	Domestic Water	1 IN	2
119	Sacramento County Main Jail	9859767	129386	EQ-1038843	D2014	Backflow Preventer	Domestic Water	3 IN	2
120	Sacramento County Main Jail	9859573	129356	EQ-1041716	D2014	Backflow Preventer	Domestic Water	2 IN	2
121	Sacramento County Main Jail	9859435	129740	EQ-1041717	D2014	Backflow Preventer	Domestic Water	1 IN	2
122	Sacramento County Main Jail	9859640	129514	EQ-1030722	D2014	Backflow Preventer	Domestic Water, 1 IN	1 IN	2
123	Sacramento County Main Jail	9859357	129411	EQ-1038805	D4011	Backflow Preventer	Fire Suppression	8 IN	2
124	Sacramento County Main Jail	9859669	129592	EQ-1028921	D1057	Baggage Handling System	Conveyor		2
125	Sacramento County Main Jail	9859835	129476	EQ-1036722	D1057	Baggage Handling System	Conveyor		2
126	Sacramento County Main Jail	9996267	129872		D1057	Baggage Handling System	Conveyor		2
127	Sacramento County Main Jail	9859690	129328	EQ-1031414	D8015	BAS/HVAC Controls	DDC Control Panel		2
128	Sacramento County Main Jail	9859425	129609	EQ-1032568	D8015	BAS/HVAC Controls	DDC Control Panel		2
129	Sacramento County Main Jail	9859402	129902	EQ-1032569	D8015	BAS/HVAC Controls	DDC Control Panel		2
130	Sacramento County Main Jail	9859428	129641	EQ-1032570	D8015	BAS/HVAC Controls	DDC Control Panel		2
131	Sacramento County Main Jail	9859681	129286	EQ-1032777	D8015	BAS/HVAC Controls	DDC Control Panel		2
132	Sacramento County Main Jail	9859471	129544	EQ-1032996	D8015	BAS/HVAC Controls	DDC Control Panel		2
133	Sacramento County Main Jail	9859619	129722	EQ-1032997	D8015	BAS/HVAC Controls	DDC Control Panel		2
134	Sacramento County Main Jail	9859735	129541	EQ-1033015	D8015	BAS/HVAC Controls	DDC Control Panel		2
135	Sacramento County Main Jail	9859520	129801	EQ-1033055	D8015	BAS/HVAC Controls	DDC Control Panel		2
136	Sacramento County Main Jail	9859577	129720	EQ-1033056	D8015	BAS/HVAC Controls	DDC Control Panel		2
137	Sacramento County Main Jail	9859603	129466	EQ-1033756	D8015	BAS/HVAC Controls	DDC Control Panel		2
138	Sacramento County Main Jail	9859781	129683	EQ-1033757	D8015	BAS/HVAC Controls	DDC Control Panel		2
139	Sacramento County Main Jail	9859609	129620	EQ-1033760	D8015	BAS/HVAC Controls	DDC Control Panel		2
140	Sacramento County Main Jail	9859358	129347	EQ-1036804	D8015	BAS/HVAC Controls	DDC Control Panel		2
141	Sacramento County Main Jail	9859587	129318	EQ-1036805	D8015	BAS/HVAC Controls	DDC Control Panel		2
142	Sacramento County Main Jail	9859708	129467	EQ-1036808	D8015	BAS/HVAC Controls	DDC Control Panel		2
143	Sacramento County Main Jail	9859525	129624	EQ-1036809	D8015	BAS/HVAC Controls	DDC Control Panel		2
144	Sacramento County Main Jail	9859539	129568	EQ-1036810	D8015	BAS/HVAC Controls	DDC Control Panel		2
145	Sacramento County Main Jail	9859534	129611	EQ-1036831	D8015	BAS/HVAC Controls	DDC Control Panel		2
146	Sacramento County Main Jail	9859344	129723	EQ-1036832	D8015	BAS/HVAC Controls	DDC Control Panel		2
147	Sacramento County Main Jail	9859560	129595	EQ-1036833	D8015	BAS/HVAC Controls	DDC Control Panel		2
148	Sacramento County Main Jail	9859683	129308	EQ-1036849	D8015	BAS/HVAC Controls	DDC Control Panel		2
149	Sacramento County Main Jail	9859442	129711	EQ-1036850	D8015	BAS/HVAC Controls	DDC Control Panel		2
150	Sacramento County Main Jail	9859844	129587	EQ-1037008	D8015	BAS/HVAC Controls	DDC Control Panel		2
151	Sacramento County Main Jail	9996248	129889		D8015	BAS/HVAC Controls	DDC Control Panel	20	2
152	Sacramento County Main Jail	9859592	129555	EQ-1041916	D2012	Boiler	Gas, Domestic	1000 MBH	2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
111	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	18	20	2	2025
112	Replace	01 - First Floor - 01DOCK - Loading Dock	Fair	3	Aged But Functional	1989	27	30	3	2025
113	Replace	B1 - Basement 1 - B1WMC1 - Mechanical	Fair	3	Aged But Functional	1989	27	30	3	2025
114	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	16	30	14	2025
115	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	16	30	14	2025
116	Replace	S1 - Site	Fair	3	Aged But Functional	1989	28	30	2	2025
117	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal		20	30	10	2025
118	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	1900	26	30	4	2025
119	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2004	22	30	8	2025
120	Replace	01 - First Floor - Main Backflow	Fair	3	Lifecycle/Renewal	2005	21	30	9	2025
121	Replace	02 - Second Floor - 02CSTMED(1) - Customer Common	Fair	3	Lifecycle/Renewal	2008	18	30	12	2025
122	Replace	B1 - Basement 1 - B1LNMC1 - Laundry Mechanical	Fair	3	Lifecycle/Renewal	2000	26	30	4	2025
123	Replace	B1 - Basement 1 - B1FPMP - Fire Pump	Fair	3	Lifecycle/Renewal	2004	22	30	8	2025
124	Replace	01 - First Floor - 01BKGWMN - Booking Women	Fair	3	Aged But Functional		18	25	7	2025
125	Replace	01 - First Floor - 01BKGMEN - Booking Men	Fair	3	Lifecycle/Renewal	1988	11	25	14	2025
126	Replace	B1 - Basement 1 - Property	Fair	3	Lifecycle/Renewal		13	25	12	2025
127	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	9	15	6	2025
128	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Lifecycle/Renewal		8	15	7	2025
129	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Lifecycle/Renewal		9	15	6	2025
130	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	1900	6	15	9	2025
131	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	1900	7	15	8	2025
132	Replace	B1 - Basement 1 - B1PUMP - Pump	Fair	3	Aged But Functional	1989	13	15	2	2025
133	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2017	9	15	6	2025
134	Replace	B1 - Basement 1 - B1PUMP - Pump	Fair	3	Aged But Functional	1989	13	15	2	2025
135	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1900	13	15	2	2025
136	Replace	B1 - Basement 1 - B1WMC1 - Mechanical	Fair	3	Aged But Functional	1989	13	15	2	2025
137	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	11	15	4	2025
138	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	11	15	4	2025
139	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	11	15	4	2025
140	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	13	15	2	2025
141	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional	1989	13	15	2	2025
142	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	13	15	2	2025
143	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1989	13	15	2	2025
144	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	1989	13	15	2	2025
145	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1989	13	15	2	2025
146	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	1989	13	15	2	2025
147	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	13	15	2	2025
148	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	13	15	2	2025
149	Replace	02 - Second Floor - East Electrical Room	Fair	3	Aged But Functional	1989	13	15	2	2025
150	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	1989	13	15	2	2025
151	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal		9	15	6	2025
152	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2015	11	25	14	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
111	1	7000	EA	0		1.138	31	$ 10,435.46	Trane	40B-9-1HC
112	1	1100	EA	0		1.138	31	$ 1,639.86	Watts	909
113	1	1100	EA	0		1.138	31	$ 1,639.86	Watts	909
114	1	1400	EA	0		1.138	31	$ 2,087.09	Watts	909
115	1	1400	EA	0		1.138	31	$ 2,087.09	Watts	909
116	1	3200	EA	0		1.138	31	$ 4,770.50	Febco	765
117	1	1400	EA	0		1.138	31	$ 2,087.09	Watts	009 M-2
118	1	1400	EA	0		1.138	31	$ 2,087.09	Nibco	No dataplate
119	1	5200	EA	0		1.138	31	$ 7,752.06	Watts	909
120	1	3200	EA	0		1.138	31	$ 4,770.50	Watts	909
121	1	1400	EA	0		1.138	31	$ 2,087.09	Watts	909
122	1	1400	EA	0		1.138	31	$ 2,087.09	Watts	909
123	1	14400	EA	0		1.138	31	$ 21,467.23	Watts	909 M-1
124	1	30000	EA	0		1.138	31	$ 44,723.40	White Conveyors Inc	5204
125	1	30000	EA	0		1.138	31	$ 44,723.40	White Machine Company	
126	1	30000	EA	0		1.138	31	$ 44,723.40		
127	1	4980	EA	0		1.138	31	$ 7,424.08	No dataplate	No dataplate
128	1	4980	EA	0		1.138	31	$ 7,424.08	Toshiba Houston	
129	1	4980	EA	0		1.138	31	$ 7,424.08	Toshiba Houston	
130	1	4980	EA	0		1.138	31	$ 7,424.08	Syncroflo	NONE
131	1	4980	EA	0		1.138	31	$ 7,424.08	Furnas	35C005A000A2E1A38AA
132	1	4980	EA	0		1.138	31	$ 7,424.08	Rte Delta	NA
133	1	4980	EA	0		1.138	31	$ 7,424.08	Johnson Controls	NA
134	1	4980	EA	0		1.138	31	$ 7,424.08	Rte Delta	NA
135	1	4980	EA	0		1.138	31	$ 7,424.08	Rte Delta	
136	1	4980	EA	0		1.138	31	$ 7,424.08	Hydronix	953-403-404
137	1	4980	EA	0		1.138	31	$ 7,424.08	Toshiba Houston	NA
138	1	4980	EA	0		1.138	31	$ 7,424.08	Toshiba Houston	NA
139	1	4980	EA	0		1.138	31	$ 7,424.08	Toshiba Houston	NA
140	1	4980	EA	0		1.138	31	$ 7,424.08	JCI	DSC-8500
141	1	4980	EA	0		1.138	31	$ 7,424.08	Johnson Controls	DSC-8500
142	1	4980	EA	0		1.138	31	$ 7,424.08	Johnson Controls	NA
143	1	4980	EA	0		1.138	31	$ 7,424.08	JCI	DSC-8500
144	1	4980	EA	0		1.138	31	$ 7,424.08	JCI	DSC-8500
145	1	4980	EA	0		1.138	31	$ 7,424.08	Johnson Controls	DSC-8500
146	1	4980	EA	0		1.138	31	$ 7,424.08	Johnson Controls	DSC-8500
147	1	4980	EA	0		1.138	31	$ 7,424.08	Johnson Controls	DSC-8500
148	1	4980	EA	0		1.138	31	$ 7,424.08	Johnson Controls	
149	1	4980	EA	0		1.138	31	$ 7,424.08	Johnson Controls	NA
150	1	4980	EA	0		1.138	31	$ 7,424.08	Johnson Controls	DSC-8500
151	1	4980	EA	0		1.138	31	$ 7,424.08	No dataplate	No dataplate
152	1	47500	EA	0		1.138	31	$ 70,812.05	Harsco Industrial Patterson-	D1000-MFD

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
111	L85F29124	RF 2	11/09/2025	DBFA4363-3507-4057-A83C-51CDD32884D5		EQ-1034839	green
112	344136	00505-15140-0003	11/09/2025	804E59BF-305C-4B55-BA11-2542DA233E1E		EQ-1036400	orange
113	455897	00505-15140-0005	11/09/2025	79C31BB7-872E-4079-9AF9-C64F19C2AFC7		EQ-1036403	orange
114	541271	00505-15140-0007	11/09/2025	791F2F16-D7B4-4D19-B423-3EF135D610F9		EQ-1036405	green
115	540489	00505-15140-0008	11/09/2025	1546C122-3B58-4D66-A5D3-1C8827DDAF74		EQ-1036406	orange
116	HO35746	00505-15140-0009	11/09/2025	663B516B-A813-44DF-AAE6-030552F1515A		EQ-1036407	green
117	204559	00505-15140-0011	11/09/2025	F22C653B-C2E5-496D-8FA4-0CD7C358081A		EQ-1036408	green
118	No dataplate	00505-15140-0013	11/09/2025	8EE8791A-3812-4F3E-ACF9-ED290B8BDD19		EQ-1036661	orange
119	549583	00505-15140-0010	11/09/2025	84980AD9-CDD9-406E-87B2-0C1B15184901		EQ-1038843	green
120	557141	UNKNOWN	11/09/2025	19AB8178-71E3-447E-AB31-F6BDC867A3F9		EQ-1041716	green
121	627707	UNKNOWN	11/09/2025	B641248F-8BF8-4880-9F5D-03A6E1A08753		EQ-1041717	green
122	633383	UNKNOWN	10/30/2025	8C763C16-00D4-4ED9-B6D0-50E17A8C2A18		EQ-1030722	green
123	626344	00505-15140-0002	11/09/2025	A77024F9-96F9-4F1A-AEF2-8CB7193C96C3		EQ-1038805	green
124		WOMENS CONVEYOR	10/30/2025	140A05EF-D014-41D4-AD79-8F57ACA62BCB		EQ-1028921No conveyor in	green
125		MALE CONVEYOR	11/08/2025	DE258661-9A0A-471F-BBC1-2CB18218A4C6		EQ-1036722No conveyor in	orange
126		PROPERTY CONVEYOR	11/08/2025	0BD2EA6B-EFF7-4300-9E42-50A38026539B		No conveyor in our cost libra	blue
127	No dataplate	EF 5	11/09/2025	99F4F3C9-EAFD-49A8-914D-4BB2AAC9F2A6		EQ-1031414	orange
128	UNK	EXHAUST FAN-6	10/29/2025	AFFCE193-553B-447D-AC71-7A30A9AFD68C		EQ-1032568	green
129	UNK	EXHAUST FAN-5	10/30/2025	E5070388-E5FD-4B8E-B61D-3E0F39AF3268		EQ-1032569	green
130	PROD.85137	CW BOOSTER-1	11/09/2025	AE5B4950-E7CE-479F-B507-89CA37A62C4C		EQ-1032570	orange
131	31G87058	S-1	11/09/2025	09D2BD58-F75F-4AF1-A9D0-24C384A95ABF		EQ-1032777	orange
132	NA	F.O.P.	11/09/2025	D8A78614-361A-414D-9F51-1D3F05F27FCE		EQ-1032996	orange
133	NA	BOOSTER PUMP/HW BOOST	11/09/2025	831DE8AD-317C-4A68-A448-D364C9F95897		EQ-1032997	orange
134	NA	F.O.P.	11/09/2025	5B6DF728-0619-489B-9A71-478B8C6481AC		EQ-1033015	orange
135	UNK	F.O.P.	11/09/2025	1A5E0371-6484-490C-9457-A344375486D6		EQ-1033055	orange
136	UNK	SEWAGE PUMP-1	11/09/2025	A0BEE720-D673-48C4-95E8-E8DBB70EE0D7		EQ-1033056	orange
137	NA	SUPPLY FAN-8	11/09/2025	F51C45C9-95C3-4B15-B8B8-3A09E949663D		EQ-1033756	orange
138	NA	SUPPLY FAN-7	11/09/2025	DD27705F-5668-4A98-8C45-D867DF6EE5E6		EQ-1033757	orange
139	NA	SUPPLY FAN-6	11/09/2025	ECE4E68C-641C-4FDC-9561-B7C14533DD38		EQ-1033760	orange
140	UNK	DSC-3	11/09/2025	63F9BA9F-DE27-4911-876A-9761A186802D		EQ-1036804	orange
141	NONE	DSC-6	11/09/2025	1C5E752C-6CFD-4AD4-AD3E-46406712C67E		EQ-1036805	orange
142	NA	DSC 4	11/09/2025	541AE2B9-6E66-4611-97A6-FA71BC10890D		EQ-1036808	orange
143	UNK	DSC - 9	11/09/2025	6C0CCE9E-5224-4E4F-88B2-68DD9C2C55D7		EQ-1036809	orange
144	UNK	DSC-5	11/09/2025	7B1FA6A1-0E54-43C2-BFFD-DB9643B87910		EQ-1036810	orange
145	UNK	DSC-7	11/09/2025	E8DFE258-E4E3-409A-8982-774A2034F18A		EQ-1036831	orange
146	UNK	DSC-8	11/09/2025	B57CC3B4-3605-44F8-8562-3700B70B4058		EQ-1036832	orange
147	UNK	DSC-1	11/09/2025	31E5B3E4-F9BE-4DDC-A15F-B28F9F34FE4D		EQ-1036833	orange
148	UNK	DSC 2	11/09/2025	524890A1-9AE7-43F4-ADC6-E0097EE35BE4		EQ-1036849	orange
149	NA	DSC 4	11/09/2025	B25ECABF-5C58-4AB7-8674-3670288243A7		EQ-1036850	orange
150		DSC-6	11/09/2025	72F5162E-6BE5-4AFC-BAD9-EEC13E6B6E0A		EQ-1037008	orange
151	No dataplate	EF 6	11/09/2025	89012DEE-60D9-4718-8998-336A0CAAAD7E			blue
152	FW27-14-37887	HOT WATER HEATER #5	11/09/2025	C450A0B0-346A-4BA0-906D-0C2864949EA9		EQ-1041916	green

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
153	Sacramento County Main Jail	9859709	129496	EQ-1041917	D2012	Boiler	Gas, Domestic	2000 MBH	2
154	Sacramento County Main Jail	9859608	129348	EQ-1041919	D2012	Boiler	Gas, Domestic	2000 MBH	2
155	Sacramento County Main Jail	9859599	129274	EQ-1041920	D2012	Boiler	Gas, Domestic	2000 MBH	2
156	Sacramento County Main Jail	9859460	129320	EQ-1041921	D2012	Boiler	Gas, Domestic	200 MBH	2
157	Sacramento County Main Jail	9859419	129733	EQ-1041918	D3021	Boiler	Gas, HVAC	3000 MBH	2
158	Sacramento County Main Jail	9859547	129483	EQ-1035723	D3021	Boiler	Gas, HVAC, 2501 to 5000 MBH	3200 MBH	2
159	Sacramento County Main Jail	9859406	129766	EQ-1035755	D3031	Cooling Tower	Closed Circuit (Fluid Cooler), 26 to 100 TON	30 TON	2
160	Sacramento County Main Jail	10013259			E1047	Detention Equipment	Toilet & Wash Basin, Stainless Steel		2
161	Sacramento County Main Jail	9859808	129795	EQ-1031612	D5023	Distribution Panel	120/208 V	125 AMP	2
162	Sacramento County Main Jail	9859581	129457	EQ-1032351	D5023	Distribution Panel	120/208 V	225 AMP	2
163	Sacramento County Main Jail	9927080	130373		D5023	Distribution Panel	120/208 V	225 AMP	2
164	Sacramento County Main Jail	9927082	130384		D5023	Distribution Panel	120/208 V	200 AMP	2
165	Sacramento County Main Jail	9927073	130378		D5023	Distribution Panel	120/208 V	200 AMP	2
166	Sacramento County Main Jail	9859548	129879	EQ-1031835	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
167	Sacramento County Main Jail	9859515	129547	EQ-1031847	D5023	Distribution Panel	120/208 V, 200 AMP	225 AMP	2
168	Sacramento County Main Jail	9859776	129598	EQ-1032079	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
169	Sacramento County Main Jail	9859774	129690	EQ-1032131	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
170	Sacramento County Main Jail	9859800	129778	EQ-1032133	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
171	Sacramento County Main Jail	9859546	129855	EQ-1032134	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
172	Sacramento County Main Jail	9859817	129965	EQ-1032135	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
173	Sacramento County Main Jail	9859465	129929	EQ-1032355	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
174	Sacramento County Main Jail	9859719	129742	EQ-1032357	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
175	Sacramento County Main Jail	9859584	129562	EQ-1032359	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
176	Sacramento County Main Jail	9859591	129833	EQ-1032509	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
177	Sacramento County Main Jail	9859693	129930	EQ-1032529	D5023	Distribution Panel	120/208 V, 200 AMP	100 AMP	2
178	Sacramento County Main Jail	9859729	129365	EQ-1031624	D5023	Distribution Panel	120/208 V, 400 AMP	225 AMP	2
179	Sacramento County Main Jail	9859393	129293	EQ-1031839	D5023	Distribution Panel	120/208 V, 400 AMP	400 AMP	2
180	Sacramento County Main Jail	9859595	129324	EQ-1032352	D5023	Distribution Panel	120/208 V, 400 AMP	400 AMP	2
181	Sacramento County Main Jail	9859488	129484	EQ-1031276	D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
182	Sacramento County Main Jail	9859355	129630	EQ-1031409	D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
183	Sacramento County Main Jail	9859427	129633	EQ-1031813	D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
184	Sacramento County Main Jail	9859371	129590	EQ-1032136	D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
185	Sacramento County Main Jail	9859568	129547	EQ-1032137	D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
186	Sacramento County Main Jail	9859567	129646	EQ-1032350	D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
187	Sacramento County Main Jail	9859389	129671	EQ-1032360	D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
188	Sacramento County Main Jail	9859593	129779	EQ-1032526	D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
189	Sacramento County Main Jail	9927092	130383		D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
190	Sacramento County Main Jail	9927079	130379		D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
191	Sacramento County Main Jail	9859840	129341	EQ-1031812	D5023	Distribution Panel	120/240 V, Residential Style, 100 AMP	100 AMP	2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
153	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2015	11	25	14	2025
154	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2014	12	25	13	2025
155	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2014	12	25	13	2025
156	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2014	12	25	13	2025
157	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2015	11	30	19	2025
158	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	1988	27	30	3	2025
159	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025
160	Replace	Throughout	Fair	3	Aged But Functional		26	30	4	2025
161	Replace	B1 - Basement 1 - Fiscal	Fair	3	Aged But Functional	1989	27	30	3	2025
162	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	1989	27	30	3	2025
163	Replace	02 - Second Floor - Electrical Room	Fair	3	Aged But Functional		27	30	3	2025
164	Replace	05 - Fifth Floor - Electrical Room	Fair	3	Aged But Functional		27	30	3	2025
165	Replace	03 - Third Floor - Electrical Room	Fair	3	Aged But Functional		27	30	3	2025
166	Replace	06 - Sixth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
167	Replace	03 - Third Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
168	Replace	01 - First Floor - Court Hallway - Electrical Closet	Fair	3	Aged But Functional	1989	27	30	3	2025
169	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
170	Replace	02 - Second Floor - Electrical Room East	Fair	3	Aged But Functional	1989	27	30	3	2025
171	Replace	02 - Second Floor - 02CUST - Custodial Closet	Fair	3	Aged But Functional	1989	27	30	3	2025
172	Replace	02 - Second Floor - 02CUST - Custodial Closet	Fair	3	Aged But Functional	1989	27	30	3	2025
173	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	27	30	3	2025
174	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	27	30	3	2025
175	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	27	30	3	2025
176	Replace	01 - First Floor - 01BKGMEN - Booking Men	Fair	3	Aged But Functional	1989	27	30	3	2025
177	Replace	02 - Second Floor - Electrical Room East	Fair	3	Aged But Functional	1989	27	30	3	2025
178	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional	1989	27	30	3	2025
179	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional	1989	27	30	3	2025
180	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional	1989	27	30	3	2025
181	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	27	30	3	2025
182	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
183	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional	1989	27	30	3	2025
184	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
185	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	1989	27	30	3	2025
186	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	1989	27	30	3	2025
187	Replace	04 - Fourth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
188	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
189	Replace	04 - Fourth Floor - Electrical Room	Fair	3	Aged But Functional		27	30	3	2025
190	Replace	03 - Third Floor - Electrical Room	Fair	3	Aged But Functional		27	30	3	2025
191	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	1989	27	30	3	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
153	1	47500	EA	25	2000 MBH	1.138	31	$ 84,325.80	Harsco Industrial Patterson-	D2000-MFD
154	1	47500	EA	25	2000 MBH	1.138	31	$ 84,325.80	Harsco Industrial Patterson-	D2000-MFD
155	1	47500	EA	25	2000 MBH	1.138	31	$ 84,325.80	Harsco Industrial Patterson-	D2000-MFD
156	1	47500	EA	25	2000 MBH	1.138	31	$ 84,325.80	Harsco Industrial Patterson-	D2000-MFD
157	1	135000	EA	0		1.138	31	$ 201,255.30	Bryan	AB 300-S-15-FDG-LX
158	1	135000	EA	0		1.138	31	$ 201,255.30	Bryan	L48-S-15-FDG
159	1	45000	EA	0		1.138	31	$ 67,085.10	Baltimore Air Coil	VX1-27-3RP
160	1100	3500	EA	0		1.138	31	$ 5,739,503.00		
161	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	NQOD 442M 2250V
162	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	CAT# 83204-14
163	1	2000	EA	0		1.138	31	$ 2,981.56		
164	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	No dataplate
165	1	2000	EA	0		1.138	31	$ 2,981.56		
166	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	49-83204-13
167	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	
168	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	49-83204-14
169	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	CAT# 49-83204-13
170	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	CAT# 49-83204-14
171	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	CAT# 49-83204-14
172	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	CAT# 49-83204-01
173	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	TYPE.NQOB
174	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	CAT.49-83204-14
175	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	CAT.49-83204-13
176	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	FO.49-83204-14
177	1	2000	EA	0		1.138	31	$ 2,981.56	Square D	49-83204-13
178	1	6000	EA	0		1.138	31	$ 8,944.68	Square D	CAT.49-83204-13
179	1	6000	EA	0		1.138	31	$ 8,944.68	Square D	CAT.49-83204-13
180	1	6000	EA	0		1.138	31	$ 8,944.68	Square D	CAT.49-83204-13
181	1	1100	EA	0		1.138	31	$ 1,639.86	Westinghouse	SRF-51000 CCC IT
182	1	1100	EA	0		1.138	31	$ 1,639.86	Square D	49-83204-14
183	1	1100	EA	0		1.138	31	$ 1,639.86	Square D	CAT.49-83204-14
184	1	1100	EA	0		1.138	31	$ 1,639.86	Square D	CAT# 49-83204-13
185	1	1100	EA	0		1.138	31	$ 1,639.86	Square D	CAT# 49-83204-13
186	1	1100	EA	0		1.138	31	$ 1,639.86	Square D	CAT# 49-83204-13
187	1	1100	EA	0		1.138	31	$ 1,639.86	Square D	CAT.49-83204-13
188	1	1100	EA	0		1.138	31	$ 1,639.86	Square D	49-83204-13
189	1	1100	EA	0		1.138	31	$ 1,639.86	Square D	No dataplate
190	1	1100	EA	0		1.138	31	$ 1,639.86		
191	1	1100	EA	0		1.138	31	$ 1,639.86	Square D	CAT.49-83204-14

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
153	FZ21-14-37776	HOT WATER HEATER #4	11/09/2025	6033DB89-5C00-46AE-8236-1CBD37F1B961		EQ-1041917	green
154	FZ33-14-37952	HOT WATER HEATER #1	11/09/2025	A061BFA2-AABF-484F-A7F7-87EE393B7789		EQ-1041919	green
155	FZZ1-14-377	HOT WATER HEATER #2	11/09/2025	8A6BB200-6AC9-4F6F-9ED3-26F21EF8F4D5		EQ-1041920	green
156	FZ33-14-37951	HOT WATER HEATER #3	11/09/2025	8DA8C97C-7086-4B35-9D51-EEB839BA9F3C		EQ-1041921	green
157	100193	STEAM BOILER #2	11/09/2025	7B770961-8E6C-4B6E-BB8C-68CCE5AFE5F4		EQ-1041918	green
158	60736	STEAM BOILER 1	11/09/2025	22012D79-9E2D-4437-A92B-5D4B68BE85EE		EQ-1035723	green
159	85-0205M	EVAP COOLER	11/09/2025	281D2955-E3F0-4E08-B5C0-F0758792760B		EQ-1035755	green
160		Toilet & Sink	11/13/2025				blue
161	UNK	LNB3	11/09/2025	53C55998-B740-4296-90CA-8122CFE88CBD		EQ-1031612	orange
162	NONE	PANEL HEB1	11/09/2025	3E11E58B-76C6-48EB-8FDF-FD5BF5786221		EQ-1032351	orange
163			10/30/2025	49752E19-F72C-4480-8D7D-D57F2A3D1F5F			blue
164	No dataplate		10/30/2025	56E67768-A5F0-4580-9FB0-874BCC8A1F88			blue
165			10/30/2025	18261A50-DFAF-4663-8D52-3FD6C338343B			blue
166	NONE	PANEL LE61	10/30/2025	A439649E-99DE-4E7F-B784-07D3794E1CDD		EQ-1031835	green
167	UNK	PANEL LN32	10/30/2025	E2DF500F-493C-4AA3-AD45-1EC1D094BC88		EQ-1031847	green
168	NONE	PANEL HE12	10/30/2025	750A4647-37D4-45DC-8D88-DD4BA9095B73		EQ-1032079	green
169	NONE	PANEL LEP1	10/30/2025	A6EEDC56-CAA5-45CC-A3D1-9B7E79B43EC4		EQ-1032131	green
170	NONE	PANEL HN21	10/30/2025	91ECEB10-E9A7-43AB-975C-B13F57F8D4EA		EQ-1032133	green
171	NONE	PANEL HN22	10/30/2025	AB36C458-4A65-471F-8AC4-F06B0ED35B4F		EQ-1032134	green
172	NONE	PANEL LN23	10/30/2025	D16843B8-32EE-49D3-A4C4-8557A34C7726		EQ-1032135	green
173	CAT.49-83204-13	PANEL LE11	10/30/2025	AB78D96C-20CC-4578-9100-7818F8633DD6		EQ-1032355	green
174	UNK	PANEL HE11	10/30/2025	9AC9E959-AE57-45D7-A51A-CFD4DF60F976		EQ-1032357	green
175	UNK	PANEL LN11	10/30/2025	2833D090-705F-4724-A0D2-9E200600684C		EQ-1032359	green
176	UNK	PANEL HN13	10/30/2025	EFB11A23-E2BE-4C81-961B-12172399996A		EQ-1032509	green
177	NONE	PANEL LN24	10/30/2025	ACEFC6A0-0B44-4F87-98FB-FC446E301872		EQ-1032529	green
178	NONE	PANEL LNBK2	11/09/2025	8D3C8C56-0B1A-4291-A87B-DF49445F115D		EQ-1031624	orange
179	NONE	PANEL LEBK	11/09/2025	D06F556E-684B-40E6-876A-E7A24C9A1E0D		EQ-1031839	orange
180	UNK	LNBK 1B	11/09/2025	99321106-85C9-494D-B324-06E26069FC1B		EQ-1032352	orange
181	UNK	PANEL HN11	10/30/2025	52631129-45F6-4A34-9E9D-990DE9C9C51B		EQ-1031276	green
182	UNK	PANEL HNB2	11/09/2025	F37DE036-F553-4D83-AD0B-186CCBD02F9A		EQ-1031409	orange
183	NONE	PANEL HNBK	11/09/2025	C68EB11A-D6E9-42EB-ADFA-FA2B224343B7		EQ-1031813	orange
184	NONE	PANEL LNB2	11/09/2025	790288B0-3F16-4D64-8929-971B74E84A5F		EQ-1032136	orange
185	NONE	PANEL LNB1	11/09/2025	D301829F-7078-4EA8-986E-7F71B62C2711		EQ-1032137	orange
186	NONE	PANEL LEB1	11/09/2025	8824A9E9-6DA1-42BE-A121-14DB5F86C1BC		EQ-1032350	orange
187	UNK	PANELLE41	11/09/2025	2CBDFCFA-824D-44A8-A47C-6437963D1117		EQ-1032360	orange
188	NONE	PANEL LEB2	11/09/2025	309C4DAF-7852-4D9C-80DB-EC9ADE6D0CCE		EQ-1032526	orange
189	No dataplate		10/30/2025	3EE9DDCC-A3C4-40F5-B05C-D15E5940CFE2			blue
190			10/30/2025	5E74AD7E-3C8B-40AD-A275-B5A0EC5DA217			blue
191	NONE	PANEL HNB1	11/09/2025	BEBD3E4D-508D-447B-9475-028783EE2CE1		EQ-1031812	orange

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
192	Sacramento County Main Jail	9859846	129927	EQ-1040186	D5023	Distribution Panel	120/240 V, Residential Style, 100 AMP	100 AMP	2
193	Sacramento County Main Jail	9859810	129625	EQ-1031410	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
194	Sacramento County Main Jail	9859453	129711	EQ-1031613	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
195	Sacramento County Main Jail	9859662	129960	EQ-1031620	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
196	Sacramento County Main Jail	9859400	129968	EQ-1031621	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
197	Sacramento County Main Jail	9859632	129869	EQ-1031810	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
198	Sacramento County Main Jail	9859847	129542	EQ-1031811	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
199	Sacramento County Main Jail	9859463	129606	EQ-1031814	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
200	Sacramento County Main Jail	9859379	129935	EQ-1031836	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
201	Sacramento County Main Jail	9859745	129669	EQ-1031846	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
202	Sacramento County Main Jail	9859484	129688	EQ-1031848	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
203	Sacramento County Main Jail	9859780	129443	EQ-1031849	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
204	Sacramento County Main Jail	9859804	129806	EQ-1032132	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
205	Sacramento County Main Jail	9859624	129530	EQ-1032353	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
206	Sacramento County Main Jail	9859443	129767	EQ-1032354	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
207	Sacramento County Main Jail	9859760	129874	EQ-1032361	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
208	Sacramento County Main Jail	9859807	129721	EQ-1032362	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
209	Sacramento County Main Jail	9859597	129691	EQ-1032507	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
210	Sacramento County Main Jail	9859481	129921	EQ-1032512	D5023	Distribution Panel	277/480 V, 200 AMP		2
211	Sacramento County Main Jail	9859480	129814	EQ-1032523	D5023	Distribution Panel	277/480 V, 200 AMP		2
212	Sacramento County Main Jail	9859828	129667	EQ-1032524	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
213	Sacramento County Main Jail	9859710	129441	EQ-1032525	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
214	Sacramento County Main Jail	9859730	129886	EQ-1032527	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
215	Sacramento County Main Jail	9859429	129745	EQ-1032528	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
216	Sacramento County Main Jail	9859364	129557	EQ-1032530	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
217	Sacramento County Main Jail	9859555	129977	EQ-1032531	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
218	Sacramento County Main Jail	9859707	129705	EQ-1032532	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
219	Sacramento County Main Jail	9859820	129845	EQ-1032633	D5023	Distribution Panel	277/480 V, 200 AMP	225 AMP	2
220	Sacramento County Main Jail	9959426	130353		D2016	Drinking Fountain	Floor-Mounted, Interior Basic		2
221	Sacramento County Main Jail	9922816	130001		D5031	Electrical System	Wiring & Switches, Average or Low Density/Complexity		1
222	Sacramento County Main Jail	9859459	129717	EQ-1034278	D3063	Exhaust Fan	Roof or Wall-Mounted, 12" Damper, 501 to 1000 CFM	1000 CFM	2
223	Sacramento County Main Jail	9859510	129545	EQ-1034821	D3063	Exhaust Fan	Roof or Wall-Mounted, 16" Damper, 1001 to 2000 CFM	2000 CFM	2
224	Sacramento County Main Jail	9859747	129561	EQ-1034832	D3063	Exhaust Fan	Roof or Wall-Mounted, 16" Damper, 1001 to 2000 CFM	2000 CFM	2
225	Sacramento County Main Jail	9859349	129583	EQ-1034833	D3063	Exhaust Fan	Roof or Wall-Mounted, 16" Damper, 1001 to 2000 CFM	2000 CFM	2
226	Sacramento County Main Jail	9996266	129879		D3063	Exhaust Fan	Roof or Wall-Mounted, 24" Damper	5000 CFM	2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
192	Replace	01 - First Floor - Fire Panel Room	Fair	3	Aged But Functional	1989	27	30	3	2025
193	Replace	08 - Eighth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
194	Replace	07 - Seventh Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
195	Replace	07 - Seventh Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
196	Replace	07 - Seventh Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
197	Replace	07 - Seventh Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
198	Replace	07 - Seventh Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
199	Replace	B1 - Basement 1 - B1LN - Laundry	Fair	3	Aged But Functional	1989	27	30	3	2025
200	Replace	07 - Seventh Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
201	Replace	08 - Eighth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
202	Replace	06 - Sixth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
203	Replace	06 - Sixth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
204	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
205	Replace	01 - First Floor - 01BKGMEN - Booking Men	Fair	3	Aged But Functional	1989	27	30	3	2025
206	Replace	01 - First Floor - 01BKGMEN - Booking Men	Fair	3	Aged But Functional	1989	27	30	3	2025
207	Replace	00505 - Floor - 00505 - Space	Fair	3	Aged But Functional	1989	27	30	3	2025
208	Replace	05 - Fifth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
209	Replace	04 - Fourth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
210	Replace	04 - Fourth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
211	Replace	02 - Second Floor - 02CUST - Custodial Closet	Fair	3	Aged But Functional	1989	27	30	3	2025
212	Replace	02 - Second Floor - Electrical Room East	Fair	3	Aged But Functional	1989	27	30	3	2025
213	Replace	08 - Eighth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
214	Replace	02 - Second Floor - Electrical Room East	Fair	3	Aged But Functional	1989	27	30	3	2025
215	Replace	02 - Second Floor - 02CUST - Custodial Closet	Fair	3	Aged But Functional	1989	27	30	3	2025
216	Replace	00505 - Floor - 00505 - Space	Fair	3	Aged But Functional	1989	27	30	3	2025
217	Replace	04 - Fourth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
218	Replace	05 - Fifth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
219	Replace	04 - Fourth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
220	Replace	07 - Seventh Floor - 07WINREC - 7 West Indoor Recreatio	Fair	3	Aged But Functional		13	15	2	2025
221	Replace	All building - Throughout	Fair	3	Lifecycle/Renewal		36	40	4	2025
222	Replace	All Building - Electrical Rooms	Fair	3	Lifecycle/Renewal	1988	16	20	4	2025
223	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	1988	18	20	2	2025
224	Replace	R12 - Roof Level 12 - R12ROOF - Roof	Fair	3	Aged But Functional	1988	18	20	2	2025
225	Replace	R12 - Roof Level 12 - R12ROOF - Roof	Fair	3	Aged But Functional	1988	18	20	2	2025
226	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	1988	18	20	2	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
192	1	1100	EA	0		1.138	31	$ 1,639.86	Square D	5904247
193	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
194	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-14
195	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
196	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
197	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-14
198	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-14
199	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	CAT.49-83204-14
200	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
201	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
202	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
203	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
204	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	CAT# 49-83204-13
205	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	TYPE.NQOB
206	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	CAT.NQOD 442L225
207	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	CAT.49-83204-13
208	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	CAT.49-83204-13
209	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-14
210	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-14
211	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-01
212	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	B49-83204-13
213	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
214	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-12
215	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
216	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
217	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
218	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	49-83204-13
219	1	3000	EA	0		1.138	31	$ 4,472.34	Square D	FO.17-13405A
220	1	900	EA	0		1.138	31	$ 1,341.70		
221	491000	2.5	SF	0		1.138	31	$ 1,829,932.45		
222	6	1400	EA	0		1.138	31	$ 12,522.55	General Electric	
223	1	2400	EA	0		1.138	31	$ 3,577.87	Cook-Ace	8200245-00 10/84
224	1	2400	EA	0		1.138	31	$ 3,577.87	Cook	150C33
225	1	2400	EA	0		1.138	31	$ 3,577.87	Exit-aire	Illegible
226	1	3000	EA	0		1.138	31	$ 4,472.34	Cook-Ace	215C51

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
192		PANEL HN12	10/30/2025	41A72D2B-F75E-432F-9251-1EB3408E0BC4		EQ-1040186	green
193	UNK	PANEL LN 82	10/30/2025	A40E7B66-65AD-4EE9-A0B8-E357973DBB92		EQ-1031410	green
194	UNK	PANEL HE71	10/30/2025	73C6545C-B3CB-40C9-8976-722FF34321E9		EQ-1031613	green
195	NONE	PANEL LN71	10/30/2025	6B4EAB77-70E6-4793-BCF8-9FEF32FEF307		EQ-1031620	green
196	NONE	PANEL LN72	10/29/2025	681511F7-6011-4BD1-8B5A-DD82BF51677B		EQ-1031621	green
197	NONE	PANEL HN71	10/30/2025	7617AEF4-FF16-43C2-8B27-675520267127		EQ-1031810	green
198	NONE	PANEL HN72	10/30/2025	BDF76202-3F89-498F-BD61-950A4D7FCD5F		EQ-1031811	green
199	NONE	PANEL HNBL	10/30/2025	322F5A30-E6A5-49D6-8BFF-BEE449BC7BD5		EQ-1031814	green
200	UNK	PANEL LE71	10/30/2025	E31BA9DA-9B7F-40A3-95C9-3C72B1E71317		EQ-1031836	green
201	NONE	PANEL LN 81	10/30/2025	FEFC9901-8D99-4E95-AF19-FC89779E9AF2		EQ-1031846	green
202	NONE	PANEL LN61	10/30/2025	CFC5FC52-9B39-4748-8668-9096EC29AB85		EQ-1031848	green
203	NONE	PANEL LN62	10/30/2025	170300C8-195B-4972-8EE1-FD5984B664BE		EQ-1031849	green
204	NONE	PANEL LNP1	10/30/2025	DA4AAF6E-2A66-4AA0-AF82-18F5D4CF881D		EQ-1032132	green
205	CAT.49-83204-13	PANEL LN 13	10/30/2025	9E738389-29A0-46ED-9B50-AA4534ED00AE		EQ-1032353	green
206	UNK	LE 13	10/30/2025	3F371E3A-17AB-4723-9443-966420792C81		EQ-1032354	green
207	UNK	PANEL LN41	10/30/2025	8BF7727B-B517-4EDC-B360-FE052E172F7D		EQ-1032361	green
208	UNK	PANEL LN 52	10/30/2025	BEE35FB8-7E61-4418-8BF4-0C8A8FC1F1F6		EQ-1032362	green
209	NONE	PANEL HE41	10/30/2025	260F1F80-59CD-42AE-BC39-B571F2F6A1A3		EQ-1032507	green
210	NONE	PANEL HN42	10/30/2025	0C257AA2-E711-4D18-BDFA-ACC10D060F97		EQ-1032512	green
211	NONE	PANEL LE22	10/30/2025	3FFE50BB-4C11-4973-B22F-27473A6383F8		EQ-1032523	green
212	NONE	PANEL LE 21	10/30/2025	68F6CF0F-6E1E-4595-9D4A-5D1685A79051		EQ-1032524	green
213	UNK	PANEL LE81	10/30/2025	546583D0-A4EB-4ECD-9CA5-846D83AE9C05		EQ-1032525	green
214	NONE	PANEL LN21	10/30/2025	89E0CAAA-20A1-41A3-BF3E-7B60405D3700		EQ-1032527	green
215	NONE	PANEL LN22	10/30/2025	4C71AA52-DEE2-4442-B177-3633D046DA8C		EQ-1032528	green
216	NONE	PANEL LN31	10/30/2025	698791EA-1D0C-43E3-A68B-F99C6D73B716		EQ-1032530	green
217	NONE	PANEL LN42	10/30/2025	20EDC438-630F-4595-A577-86C53E648AB6		EQ-1032531	green
218	NONE	PANEL LN51	10/30/2025	9690F78D-23AE-48E1-A265-E17610D619A1		EQ-1032532	green
219	A799534	HN41	10/30/2025	93C7F134-FDCE-4A36-81ED-520E4D2C2CF1		EQ-1032633	green
220			10/30/2025	1CD87C55-54F4-48EA-97D6-9594FDF68F1F			blue
221			10/30/2025	49C9A06B-0BDB-4D92-8F1D-595454828C61			blue
222		EF 14	11/09/2025	921B9C80-35BB-45AF-8F61-D22EC69C20C6	6 total fans but maintenance views	EQ-1034278	orange
223	245C5B	REF 7A & 7B	11/09/2025	133CA388-E57B-42AF-9A2B-6F3BFA3065F2		EQ-1034821	green
224	52077255-00	REF 10	11/09/2025	CF1251A8-EF96-4908-AACB-0768CDD6525D		EQ-1034832	green
225	Illegible	REF 11	11/09/2025	EB850C2E-7D9B-4B9A-98A8-E7CF4346F71C		EQ-1034833	green
226	Inaccessible	EF-7B	11/09/2025	ED3278E2-BB00-4E47-9E3C-8278C9C9DBE5			blue

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
227	Sacramento County Main Jail	9859570	129362	EQ-1028925	D3063	Exhaust Fan	Roof or Wall-Mounted, 28" Damper, 5001 to 8500 CFM	8500 CFM	2
228	Sacramento County Main Jail	9859501	129317	EQ-1034819	D3063	Exhaust Fan	Roof or Wall-Mounted, 28" Damper, 5001 to 8500 CFM	8500 CFM	2
229	Sacramento County Main Jail	9859763	129739	EQ-1034024	D3063	Exhaust Fan	Roof or Wall-Mounted, 36"Damper, 8501 to 15000 CFM	15000 CFM	2
230	Sacramento County Main Jail	9859777	129331	EQ-1034025	D3063	Exhaust Fan	Roof or Wall-Mounted, 36"Damper, 8501 to 15000 CFM	15000 CFM	2
231	Sacramento County Main Jail	9859373	129332	EQ-1034026	D3063	Exhaust Fan	Roof or Wall-Mounted, 36"Damper, 8501 to 15000 CFM	15000 CFM	2
232	Sacramento County Main Jail	9859724	129336	EQ-1034820	D3063	Exhaust Fan	Roof or Wall-Mounted, 36"Damper, 8501 to 15000 CFM	15000 CFM	2
233	Sacramento County Main Jail	9859512	129445	EQ-1028937	D3063	Exhaust Fan	Roof or Wall-Mounted, 42" Damper, 15001 to 20000 CFM	20000 CFM	2
234	Sacramento County Main Jail	9859796	129596	EQ-1034818	D3063	Exhaust Fan	Roof or Wall-Mounted, 42" Damper, 15001 to 20000 CFM	20000 CFM	2
235	Sacramento County Main Jail	9922812	129982		B2051	Exterior Door	Aluminum-Framed & Glazed, Standard Swing		2
236	Sacramento County Main Jail	9922810	129983		B2051	Exterior Door	Steel, Commercial		2
237	Sacramento County Main Jail	9959437	130477		B2011	Exterior Walls	Concrete, Clean & Seal		2
238	Sacramento County Main Jail	9859375	129664	EQ-1034817	D3063	Fan	Centrifugal, 12" Diameter, 100 to 1000 CFM		2
239	Sacramento County Main Jail	9859788	129570	EQ-1034822	D3063	Fan	Centrifugal, 16 to 20 HP Motor, 50001 to 75000 CFM	75000 CFM	2
240	Sacramento County Main Jail	9859537	129419	EQ-1034823	D3063	Fan	Centrifugal, 16 to 20 HP Motor, 50001 to 75000 CFM	75000 CFM	2
241	Sacramento County Main Jail	9859549	129644	EQ-1034843	D3063	Fan	Centrifugal, 16 to 20 HP Motor, 50001 to 75000 CFM	75000 CFM	2
242	Sacramento County Main Jail	9859789	129480	EQ-1027648	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
243	Sacramento County Main Jail	9859464	129377	EQ-1028922	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
244	Sacramento County Main Jail	9859775	129659	EQ-1028923	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
245	Sacramento County Main Jail	9859598	129780	EQ-1028924	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
246	Sacramento County Main Jail	9859605	129494	EQ-1034088	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
247	Sacramento County Main Jail	9859518	129724	EQ-1034104	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
248	Sacramento County Main Jail	9859403	129358	EQ-1034351	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
227	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	1987	18	20	2	2025
228	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	1988	18	20	2	2025
229	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	1988	17	20	3	2025
230	Replace	02 - Second Floor - 02MRNSTA - Nurse's Station	Fair	3	Lifecycle/Renewal	1900	13	20	7	2025
231	Replace	02 - Second Floor - 02MRNSTA - Nurse's Station	Fair	3	Lifecycle/Renewal	1900	13	20	7	2025
232	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	1988	17	20	3	2025
233	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	1987	18	20	2	2025
234	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	1988	18	20	2	2025
235	Replace	Building Exterior	Fair	3	Aged But Functional		27	30	3	2025
236	Replace	Building Exterior	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
237	Replace	Building Exterior	Fair	3	Lifecycle/Renewal		12	20	8	2025
238	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1989	23	25	2	2025
239	Replace	R12 - Roof Level 12 - R12ROOF - Roof	Fair	3	Aged But Functional	1988	23	25	2	2025
240	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025
241	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025
242	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Lifecycle/Renewal	1988	20	25	5	2025
243	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1987	23	25	2	2025
244	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1987	23	25	2	2025
245	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1987	23	25	2	2025
246	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	1988	23	25	2	2025
247	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Lifecycle/Renewal	1988	23	25	2	2025
248	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
227	1	4000	EA	0		1.138	31	$ 5,963.12	Trane	300C99
228	1	4000	EA	0		1.138	31	$ 5,963.12	Exit-aire	SVJ145TTDR5331AA
229	1	5600	EA	0		1.138	31	$ 8,348.37	Loren-Cook Co.	300CT 9 B
230	1	5600	EA	0		1.138	31	$ 8,348.37		
231	1	5600	EA	0		1.138	31	$ 8,348.37		
232	1	5600	EA	0		1.138	31	$ 8,348.37	Marathon Electric	300C8B
233	1	11000	EA	0		1.138	31	$ 16,398.58	Trane	#50
234	1	11000	EA	0		1.138	31	$ 16,398.58	Loren-Cook Co.	245 VBB
235	8	1300	EA	0		1.138	31	$ 15,504.11		
236	2	4060	EA	0		1.138	31	$ 12,105.13		
237	122800	1.54	SF	0		1.138	31	$ 281,924.39		
238	1	1400	EA	0		1.138	31	$ 2,087.09	Trane	
239	1	48000	EA	0		1.138	31	$ 71,557.44	Trane	40-B-9-111F
240	1	48000	EA	0		1.138	31	$ 71,557.44	Trane	40B-9-1HF
241	1	48000	EA	0		1.138	31	$ 71,557.44	Trane	40B-9-1HF
242	1	65000	EA	0		1.138	31	$ 96,900.70	Century	NA
243	1	65000	EA	0		1.138	31	$ 96,900.70	Trane	CAFB36C12CAIHSSS0000000
244	1	65000	EA	0		1.138	31	$ 96,900.70	Trane	CAFB33C12CA1 HNSC 00000
245	1	65000	EA	0		1.138	31	$ 96,900.70	Trane	CAF833C11CA1HP50000000
246	1	65000	EA	0		1.138	31	$ 96,900.70	Trane	CAFB27S11CBSHLSS
247	1	65000	EA	0		1.138	31	$ 96,900.70	Trane	CABB60011CA2H
248	1	65000	EA	0		1.138	31	$ 96,900.70	Trane	CAFB33C12CA1H550

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
227	NA	EF 6	11/09/2025	A9F81425-74FF-4B01-8999-4BDB59F13048		EQ-1028925	orange
228		REF 5A	11/09/2025	9F6970C5-A61F-4638-A9D0-4B9CF2AE4525		EQ-1034819	orange
229	LCTB	REF 12	11/09/2025	F1403292-FD69-427C-BD80-FEA8C279688D		EQ-1034024	green
230		ROOF EXHAUST FAN 8	11/09/2025	3D22B514-236F-412F-84D0-CB17185F4FAB	Respiration equipment was needed	EQ-1034025	green
231		ROOF EXHAUST FAN 9	11/09/2025	AC6354FC-F54E-449E-B595-CC21F935D066	Respiration equipment was needed	EQ-1034026	green
232		REF 6B	11/09/2025	17D8C255-E79E-478E-B3FA-57B0AD91B467		EQ-1034820	orange
233		GARAGE SALLYPORT MAKE I	11/09/2025	2B83EA48-1D8B-4618-8A75-EE134444E336		EQ-1028937	green
234	""""6200245-00-10186	REF 04	11/09/2025	5E4BFCFE-E864-4BF5-8E35-B3DE89D3931C		EQ-1034818	green
235			10/30/2025	027D898D-DD9A-4868-9951-040B32B8D93F			blue
236			10/30/2025	6E7E8D59-6017-41BE-B30A-E5FE2225F1C5			blue
237			10/29/2025	75C85DAD-084B-4C21-8E78-FADD47E9B1E3			blue
238		EF 15	10/30/2025	15D2CCB5-4FE8-4762-AFCF-FF1FFCEE09E1		EQ-1034817	green
239	L85M33551	SPF 2	11/09/2025	E0DC51C5-315B-47B7-90A7-DFFFF5FE0AC6	No access.	EQ-1034822	green
240	L85M83552	SPF 3	11/09/2025	7D39FDB1-4ED5-4A4E-BAD9-B9DED74AC058		EQ-1034823	green
241	L85M33551	SPF 1	11/09/2025	CFD871A7-1FF5-445C-8DB0-D024210DEF37		EQ-1034843	orange
242	NA	SF 5	11/09/2025	70509B82-8731-47BB-82FB-5F05BD642A97		EQ-1027648	orange
243	286892206	EXHAUST FAN 1	11/09/2025	C240AE7F-DCC6-44B5-8CD9-DB1CD07F3BCF		EQ-1028922	orange
244	K87C07079	EF 2	11/09/2025	6293058C-8823-44CF-890E-9F4EC7EBDEE1		EQ-1028923	orange
245	K56892309	EF 5	11/09/2025	401EF1B8-446D-4F08-B58A-06B33729AE04		EQ-1028924	orange
246	K86B92322	EF 12	11/09/2025	BF36A16D-7D7B-4551-8CF6-5F672E704D6E		EQ-1034088	green
247	K86B92319	RF 6	11/09/2025	DD7ED765-442F-4E84-A69D-FD0B7423D028		EQ-1034104	green
248	K8CB92307	EF 4	11/09/2025	14AC6DDB-C4FE-461F-BF39-571EC5CA5A4A	Full access was not available.	EQ-1034351	green

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
249	Sacramento County Main Jail	9859797	129268	EQ-1034352	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
250	Sacramento County Main Jail	9859475	129682	EQ-1034353	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
251	Sacramento County Main Jail	9859676	129713	EQ-1034354	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
252	Sacramento County Main Jail	9859485	129761	EQ-1034355	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
253	Sacramento County Main Jail	9859694	129278	EQ-1034356	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
254	Sacramento County Main Jail	9859565	129477	EQ-1034834	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
255	Sacramento County Main Jail	9859562	129459	EQ-1034835	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
256	Sacramento County Main Jail	9859384	129551	EQ-1034836	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
257	Sacramento County Main Jail	9859848	129789	EQ-1034837	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM		2
258	Sacramento County Main Jail	9859773	129357	EQ-1034841	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
259	Sacramento County Main Jail	9859543	129369	EQ-1041221	D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
260	Sacramento County Main Jail	9996264	129901		D3063	Fan	Centrifugal, 21 to 25 HP Motor, 75001 to 100000 CFM	100000 CFM	2
261	Sacramento County Main Jail	9859350	129361	EQ-1034110	D3055	Fan Coil Unit	Hydronic Terminal, 401 to 800 CFM	800 CFM	2
262	Sacramento County Main Jail	10308840	129361	EQ-1034110	D3055	Fan Coil Unit	Hydronic Terminal, 401 to 800 CFM	800 CFM	2
263	Sacramento County Main Jail	9960674	130184		G2062	Fences & Gates	Secure Fence, Chain Link 10', With Razor Wire		2
264	Sacramento County Main Jail	9959433	130448		D1011	Freight Elevator	Hydraulic, 2 Floors	4000 LB	2
265	Sacramento County Main Jail	9996276	129883		D3055	Horizontal Radiator	Horizontal Radiator, 300-600 KW, Replace	500 KW	2
266	Sacramento County Main Jail	9996279	129877		D3055	Horizontal Radiator	Horizontal Radiator, 300-600 KW, Replace	500 KW	2
267	Sacramento County Main Jail	9959422	130226		D3051	HVAC System	Hydronic Piping, 4-Pipe		2
268	Sacramento County Main Jail	9922825	129991		C1031	Interior Door	Steel, Standard		2
269	Sacramento County Main Jail	10013452			D5045	Interior Lighting System	Full Upgrade, Medium Density & Standard Fixtures		2
270	Sacramento County Main Jail	9859336	129392	EQ-1037009	D5041	Lighting Controls	Dimming Panel, Standard		2
271	Sacramento County Main Jail	9927081	130375		D5041	Lighting Controls	Dimming Panel, Standard		2
272	Sacramento County Main Jail	9927088	130386		D5041	Lighting Controls	Dimming Panel, Standard		2
273	Sacramento County Main Jail	9927085	130424		D5041	Lighting Controls	Dimming Panel, Standard		2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
249	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	1988	23	25	2	2025
250	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Lifecycle/Renewal	1988	20	25	5	2025
251	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025
252	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Lifecycle/Renewal	1988	16	25	9	2025
253	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Lifecycle/Renewal	1988	16	25	9	2025
254	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025
255	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025
256	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1988	22	25	3	2025
257	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025
258	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1988	23	25	2	2025
259	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1989	23	25	2	2025
260	Replace	R12 - Roof Level 12 - R12ROOF - Roof	Fair	3	Aged But Functional	1989	23	25	2	2025
261	Replace	All Building - Throughout	Fair	3	Lifecycle/Renewal	1900	14	20	6	2025
262	Replace	All Building - Throughout	Fair	3	Lifecycle/Renewal	1900	15	20	5	2025
263	Replace	S1 - Site	Fair	3	Aged But Functional		23	25	2	2025
264	Renovate	All Building - Freight Elevator	Fair	3	Aged But Functional		27	30	3	2025
265	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional		18	20	2	2025
266	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional		18	20	2	2025
267	Replace	All building - Throughout	Fair	3	Lifecycle/Renewal	1989	35	40	5	2025
268	Replace	All building - Throughout	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
269	Replace	Throughout	Fair	3	Lifecycle/Renewal		16	20	4	2025
270	Replace	01 - First Floor - Court Hallway - Electrical Closet	Fair	3	Aged But Functional	1989	17	20	3	2025
271	Replace	02 - Second Floor - Electrical Room	Fair	3	Aged But Functional		17	20	3	2025
272	Replace	08 - Eighth Floor - Electrical Room	Fair	3	Aged But Functional		17	20	3	2025
273	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional		17	20	3	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)		Total Cost	Make	Model
249	1	65000	EA	0		1.138	31	$	96,900.70	Trane	CAFB27512CBSHMSS
250	1	65000	EA	0		1.138	31	$	96,900.70	Century	NA
251	1	65000	EA	0		1.138	31	$	96,900.70	Trane	CAFB30C11CC1H
252	1	65000	EA	0		1.138	31	$	96,900.70	Reliance	NA
253	1	65000	EA	0		1.138	31	$	96,900.70	Reliance	NA
254	1	65000	EA	0		1.138	31	$	96,900.70	Trane	CAFB60C12CA2H
255	1	65000	EA	0		1.138	31	$	96,900.70	Trane	CAFB60C12CA2H
256	1	65000	EA	0		1.138	31	$	96,900.70	Trane	N/A
257	1	65000	EA	0		1.138	31	$	96,900.70	Trane	CAFB33C11CC1H
258	1	65000	EA	0		1.138	31	$	96,900.70	Trane	N/A
259	1	65000	EA	0		1.138	31	$	96,900.70	Trane	CAFB33C12CA1HSSS000000
260	1	65000	EA	0		1.138	31	$	96,900.70	Illegible	Illegible
261	200	1670	EA	0		1.138	31	$	497,920.52	Anemostat	
262	200	1670	EA	0		1.138	31	$	497,920.52	Anemostat	
263	400	61.51	LF	0		1.138	31	$	36,679.15		
264	1	60000	EA	0		1.138	31	$	89,446.80	No dataplate	No dataplate
265	1	15000	EA	0		1.138	31	$	22,361.70	McQuay	0HS 27F-10
266	1	15000	EA	0		1.138	31	$	22,361.70	Perfex	No dataplate
267	491000	8	SF	0		1.138	31	$	5,855,783.84		
268	300	600	EA	0		1.138	31	$	268,340.40		
269	491000	4.5	SF	0		1.138	31	$	3,293,878.41		
270	1	1760	EA	0		1.138	31	$	2,623.77	Square D	
271	1	1760	EA	0		1.138	31	$	2,623.77		
272	1	1760	EA	0		1.138	31	$	2,623.77	No dataplate	No dataplate
273	1	1760	EA	0		1.138	31	$	2,623.77		

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
249	K86B92321	EF 11	11/09/2025	34DA8745-DDD0-4565-80BE-9E5D7D8EF3E0		EQ-1034352	green
250	NA	SF 4	11/09/2025	956FB9F1-AB00-4691-A5D4-541D42C089DA		EQ-1034353	orange
251	K86B92316	SF 6	11/09/2025	BE9B0E64-6573-4808-AC47-C96ECA849A55		EQ-1034354	green
252	NA	SF 7	11/09/2025	D3BDF0EF-EE3F-4638-8766-8B14C90D68C2		EQ-1034355	orange
253	NA	SF 8	11/09/2025	D45D6A15-7ACF-48D4-A0F5-6C589E98EC5A		EQ-1034356	orange
254	K86B92314	SF 1	11/09/2025	4C123983-2DF6-46A0-A2ED-A3AEACDD41E3		EQ-1034834	green
255	K86B92315	SF 2	11/09/2025	90748A8A-7568-44C6-93C5-9887CBC46018		EQ-1034835	green
256	K85H72926	SF 9	11/09/2025	8E5C94A6-EAB5-4E75-9619-409D1416765A		EQ-1034836	green
257	K86B92311	SF 3	11/09/2025	F6AEDC83-4F67-47CF-8DF6-ED00FCD696CA		EQ-1034837	green
258	N/A	RF 7	11/09/2025	923360C5-8B79-483C-800F-BE179E93983B	Full access was not available.	EQ-1034841	green
259	K86B92308	EF-3	11/09/2025	761392A5-B9DE-47CB-B8B2-FB2728F23CEE		EQ-1041221	green
260	Illegible		11/09/2025	8B102E4E-7E40-4638-8320-1653898AB2BC			blue
261		VARIABLE AIR VOLUME BOX	11/07/2025	DDFF7DB5-782E-44A0-AC45-2897B004D77C		EQ-1034110	orange
262		VARIABLE AIR VOLUME BOX	11/08/2025	[Copy of ObsID 9859350]		EQ-1034110	grey
263			10/30/2025	A5706DDB-1AB6-4E11-A159-7FB1847D3D71			blue
264	No dataplate		10/30/2025	9C4096A1-0D6F-448D-BD4C-B592D23A44E5			blue
265	B 5560 S27F001	RAD 2	11/08/2025	1C2CAB42-7E21-4F1A-A13D-D78EBB1A81C4		No horizontal radiator in ou	blue
266	No dataplate		11/08/2025	E753A25D-392B-446E-A8E7-B5B555E80A42		No horizontal radiator in ou	blue
267			10/30/2025	5146C810-2A4C-4093-864E-68DF351F11D1			blue
268			10/30/2025	32A48201-C12C-4883-8C88-0A0D516BB116			lavender
269			11/13/2025				grey
270	UNK	PANEL LCP12E	11/09/2025	7530720C-858C-49D4-AA80-6A842ED51B9E		EQ-1037009	orange
271			10/30/2025	8E02A9E0-762F-4931-82D6-B56FC0870F69			blue
272	No dataplate		10/30/2025	658750E3-1E4A-48C3-97C9-114F3E12D243			blue
273			10/30/2025	760FC3FA-18C1-4C4C-BE35-67E8C167E72E			blue

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
274	Sacramento County Main Jail	9927098	130422		D5041	Lighting Controls	Dimming Panel, Standard		2
275	Sacramento County Main Jail	9927077	130381		D5041	Lighting Controls	Dimming Panel, Standard		2
276	Sacramento County Main Jail	9859454	129668	EQ-1037378	E1015	Loading Dock Equipment	Dock Leveler		2
277	Sacramento County Main Jail	9859816	129773	EQ-1037379	E1015	Loading Dock Equipment	Dock Leveler		2
278	Sacramento County Main Jail	9959424	130287		D5039	Motor	AHU or Pump	20 HP	2
279	Sacramento County Main Jail	9859791	129760	EQ-1032417	D5023	Motor Control Center	w/ Main Breaker	600 AMP	2
280	Sacramento County Main Jail	9922836	130261		D5023	Motor Control Center	w/ Main Breaker	800 AMP	2
281	Sacramento County Main Jail	9859437	129872	EQ-1032420	D5023	Motor Control Center	w/ Main Breaker, 1200 AMP	1200 AMP	2
282	Sacramento County Main Jail	9859738	129910	EQ-1032363	D5023	Motor Control Center	w/ Main Breaker, 300 AMP	300 AMP	2
283	Sacramento County Main Jail	9859866	129387	EQ-1032418	D5023	Motor Control Center	w/ Main Breaker, 600 AMP	600 AMP	2
284	Sacramento County Main Jail	9859759	129697	EQ-1032419	D5023	Motor Control Center	w/ Main Breaker, 300 AMP	300 Amps	2
285	Sacramento County Main Jail	9859754	129543	EQ-1032421	D5023	Motor Control Center	w/ Main Breaker, 600 AMP	600 AMP	2
286	Sacramento County Main Jail	9859499	129305	EQ-1041172	D3055	Packaged Unit	RTU, Pad or Roof-Mounted, 4 TON	4 TON	2
287	Sacramento County Main Jail	9859362	129342	EQ-1041173	D3055	Packaged Unit	RTU, Pad or Roof-Mounted, 4 TON	4 TON	2
288	Sacramento County Main Jail	9922818	129998		D2014	Plumbing System	Supply & Sanitary, Medium Density (excludes fixtures)		2
289	Sacramento County Main Jail	9859654	129402	EQ-1036009	D2012	Pump	Circulation, Domestic Water	2 HP	2
290	Sacramento County Main Jail	9859398	129322	EQ-1038937	D2012	Pump	Circulation, Domestic Water, 0.5 HP	.5 HP	2
291	Sacramento County Main Jail	9859718	129728	EQ-1036008	D2012	Pump	Circulation/Booster, Domestic Water	2 HP	2
292	Sacramento County Main Jail	9859674	129716	EQ-1042071	D2012	Pump	Circulation/Booster, Domestic Water	5 HP	2
293	Sacramento County Main Jail	9859825	129700	EQ-1042072	D2012	Pump	Circulation/Booster, Domestic Water	15 HP	2
294	Sacramento County Main Jail	9859545	129679	EQ-1042073	D2012	Pump	Circulation/Booster, Domestic Water	10 HP	2
295	Sacramento County Main Jail	9859752	129708	EQ-1042074	D2012	Pump	Circulation/Booster, Domestic Water	10 HP	2
296	Sacramento County Main Jail	9859505	129351	EQ-1028914	D3051	Pump	Distribution, HVAC Chilled or Condenser Water, 1 to 3 HP	1 HP	2
297	Sacramento County Main Jail	9859367	129695	EQ-1036759	D3051	Pump	Distribution, HVAC Chilled or Condenser Water, 1 to 3 HP	3 HP	2
298	Sacramento County Main Jail	9859602	129703	EQ-1036761	D3051	Pump	Distribution, HVAC Chilled or Condenser Water, 1 to 3 HP	3 HP	2
299	Sacramento County Main Jail	9859580	129319	EQ-1036321	D3051	Pump	Distribution, HVAC Chilled or Condenser Water, 26 to 50 HP	30 HP	2
300	Sacramento County Main Jail	9859348	129501	EQ-1036322	D3051	Pump	Distribution, HVAC Chilled or Condenser Water, 26 to 50 HP	30 HP	2
301	Sacramento County Main Jail	9859761	129670	EQ-1036557	D3051	Pump	Distribution, HVAC Heating Water	3 HP	2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
274	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional		17	20	3	2025
275	Replace	03 - Third Floor - Electrical Room	Fair	3	Aged But Functional		17	20	3	2025
276	Replace	01 - First Floor - 01DOCK - Loading Dock	Fair	3	Aged But Functional	1988	22	25	3	2025
277	Replace	01 - First Floor - 01DOCK - Loading Dock	Fair	3	Aged But Functional	1900	22	25	3	2025
278	Replace	01 - First Floor - 01BKGMEN - Booking Men	Fair	3	Aged But Functional		14	18	4	2025
279	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	1989	27	30	3	2025
280	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional		27	30	3	2025
281	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
282	Replace	00505 - Floor - 00505 - Space	Fair	3	Aged But Functional	1989	27	30	3	2025
283	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
284	Replace	00505 - Floor - 00505 - Space	Fair	3	Aged But Functional	1989	27	30	3	2025
285	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
286	Replace	R12 - Roof Level 12 - R12ROOF - Roof	Fair	3	Aged But Functional	1995	18	20	2	2025
287	Replace	R12 - Roof Level 12 - R12ROOF - Roof	Fair	3	Aged But Functional	1995	18	20	2	2025
288	Replace	All building - Throughout	Fair	3	Aged But Functional	1989	36	40	4	2025
289	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	1988	13	15	2	2025
290	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	2004	13	15	2	2025
291	Replace	B1 - Basement 1 - B1BSTPMP - Booster Pump	Fair	3	Lifecycle/Renewal	1988	8	15	7	2025
292	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2017	9	25	16	2025
293	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2017	9	25	16	2025
294	Replace	B1 - Basement 1 - B1WMC1 - Mechanical	Fair	3	Lifecycle/Renewal	2017	9	25	16	2025
295	Replace	B1 - Basement 1 - B1WMC1 - Mechanical	Fair	3	Lifecycle/Renewal	2017	9	25	16	2025
296	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Lifecycle/Renewal	2012	12	15	3	2025
297	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	1988	11	15	4	2025
298	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	1988	12	15	3	2025
299	Replace	B1 - Basement 1 - B1PUMP - Pump	Fair	3	Aged But Functional	1988	22	25	3	2025
300	Replace	B1 - Basement 1 - B1PUMP - Pump	Fair	3	Aged But Functional	1988	22	25	3	2025
301	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	1988	10	15	5	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
274	1	1760	EA	0		1.138	31	$ 2,623.77		
275	1	1760	EA	0		1.138	31	$ 2,623.77	No dataplate	No dataplate
276	1	11330	EA	0		1.138	31	$ 16,890.54		
277	1	11330	EA	0		1.138	31	$ 16,890.54		
278	1	5300	EA	0		1.138	31	$ 7,901.13	Baldor	Illegible
279	1	15000	EA	0		1.138	31	$ 22,361.70	Square D	CAT.49-83204-7
280	1	15000	EA	0		1.138	31	$ 22,361.70	Square D	No dataplate
281	1	28000	EA	0		1.138	31	$ 41,741.84	Square D	FO.49-83204-11
282	1	15000	EA	0		1.138	31	$ 22,361.70	Square D	CAT# 49-83204-10
283	1	15000	EA	0		1.138	31	$ 22,361.70	Square D	CAT.49-83204-08
284	1	15000	EA	0		1.138	31	$ 22,361.70	Square D	CAT.49-83204-9
285	1	15000	EA	0		1.138	31	$ 22,361.70	Square D	FO.49-83204-12
286	1	9000	EA	0		1.138	31	$ 13,417.02	Carrier	50HJ-012-611HE
287	1	9000	EA	0		1.138	31	$ 13,417.02	Carrier	50HJ-012-611HE
288	491000	11	SF	0		1.138	31	$ 8,051,702.78		
289	1	4600	EA	0		1.138	31	$ 6,857.59	Paco	03-157016300111562
290	1	2600	EA	0		1.138	31	$ 3,876.03	Grundfos	UP 26-99
291	2	5100	EA	0		1.138	31	$ 15,205.96	Bell and Gossett	3531
292	1	7600	EA	0		1.138	31	$ 11,329.93	Vaughan	CEM2333T
293	1	7600	EA	0		1.138	31	$ 11,329.93	Vaughan	CEM2333T
294	1	6800	EA	0		1.138	31	$ 10,137.30	Vaughan	CEM3774T
295	1	6800	EA	0		1.138	31	$ 10,137.30	Vaughan	CEM3774T
296	2	5100	EA	0		1.138	31	$ 15,205.96	Hoffman	WCD12-20B-MA
297	1	5100	EA	0		1.138	31	$ 7,602.98	Gossett & Bell	11-15955-133201
298	1	5100	EA	0		1.138	31	$ 7,602.98	Bell and Gossett	11-15955-133201
299	1	22000	EA	0		1.138	31	$ 32,797.16	G.E.	5K5286AL205B
300	1	22000	EA	0		1.138	31	$ 32,797.16	Paco	11-501231A01
301	2	5100	EA	0		1.138	31	$ 15,205.96	Grundfos	A96610884P114360758

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
274			10/30/2025	D361A5E2-6C1A-46FB-9882-08B68E9A7B1C			blue
275	No dataplate		10/30/2025	10C9339B-D302-4006-868E-B8D799ABF2D1			blue
276		DOCK LEVELLER	11/09/2025	4B345EE8-889E-440C-A086-8689A170F4AA		EQ-1037378	green
277		LOADING DOCK	11/09/2025	6864158C-35F3-47E7-AAB7-DF7022019255		EQ-1037379	orange
278	Illegible		10/30/2025	23296E3D-FDB1-4FFE-8CBA-D81805C0E937			blue
279	CO42339	MCC-EB1	11/09/2025	116A8A81-4755-43DA-9AB3-32C44D4C4976		EQ-1032417	orange
280	No dataplate		10/30/2025	26FA2E68-16A9-497E-8EED-C25D04A261E9			blue
281	B953299	MCC-EP1	10/30/2025	5E4895A6-FEA3-4612-AF38-ACD955B59C06		EQ-1032420	green
282	'''''0042345, 0042346, AN	MCC-B1	10/30/2025	2037958A-1498-4892-9DE2-6F69A596B660		EQ-1032363	green
283	CO42357	MCC-EB2	11/09/2025	89CD3DD5-0033-4B38-85B9-E1DD82CE3AAC		EQ-1032418	orange
284	CO42348	MCC-EB3	10/30/2025	F4F82058-F4C8-4D82-850E-5FA0B9456ED5		EQ-1032419	green
285	CO42650	MCC-EP2	10/30/2025	CF1BC88B-754C-4B74-ABEF-BF4071681D37		EQ-1032421	green
286	4294G30646	AC-19	11/09/2025	56883AB1-8240-471D-B21C-34D72F6AE25F		EQ-1041172	green
287	4294G30645	AC-20	11/08/2025	72ECA4EC-B44C-4B63-A4FC-BC664266F4AD		EQ-1041173	green
288			10/30/2025	FFE2F39F-14DA-4201-8427-DEA3746DAA66			blue
289	KY G67049	HCP 1	11/09/2025	727269C2-B5C4-4C70-AA29-F296247B7082	The motor has been replaced.	EQ-1036009	orange
290		LAUNDRY HEAT EXCHANGEF	11/09/2025	DA950DF2-32EE-4890-B7F2-26B2A00B6A55		EQ-1038937	green
291	15050677	HOT WATER BOOSTER PUM	11/09/2025	8F5ABEA4-038E-4F66-A68C-EB073CD9CBD8		EQ-1036008	orange
292	Z1705040372	SP-1, PUMP NO. 1	11/09/2025	6AA6ABC5-3C95-4C53-92EF-FCABEE71D4E2		EQ-1042071	green
293	Z1705040397	SP-1, PUMP NO. 2	11/09/2025	8C35641F-A923-4AA0-96DB-B6A896978F22		EQ-1042072	green
294	F1706085946	SP-2, PUMP NO. 2	11/09/2025	3C65CA0C-D903-4CAA-9A14-4FE2E4D78BC0		EQ-1042073	green
295	F1706085953	SP-2, PUMP NO. 1	11/09/2025	2CABEFE1-AE00-4988-85D5-C0FE34D659DB		EQ-1042074	green
296		CONDENSATE PUMPS	11/09/2025	CB3758B3-F820-414D-8813-14FC44B91BCD		EQ-1028914	green
297	GY G67055B	CWP 1	11/09/2025	CC916154-E345-4728-8CAB-EB1A30CC268D		EQ-1036759	orange
298	GY G67055A	CWP 2	11/09/2025	430CECE7-4CA1-4A24-8869-147147377008		EQ-1036761	orange
299	KY C67054B	CHWP-2	11/09/2025	31E8606C-CC60-4185-9B07-D6B380B3CC61	The motor has been replaced	EQ-1036321	orange
300	KYG67054C	CHWP-1	11/09/2025	CB94F965-A6A7-4A4C-9128-B763D362D706	New motor	EQ-1036322	orange
301	0758	MAKE UP WATER PUMPS	11/09/2025	6C8A0EBA-2CDE-450F-8151-F82DC6BC5467		EQ-1036557	green

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
302	Sacramento County Main Jail	9859494	129489	EQ-1036562	D3051	Pump	Distribution, HVAC Heating Water	1.5 HP	2
303	Sacramento County Main Jail	9859450	129490	EQ-1036563	D3051	Pump	Distribution, HVAC Heating Water	3 HP	2
304	Sacramento County Main Jail	9996250	129839		D3051	Pump	Distribution, HVAC Heating Water	1.5 HP	2
305	Sacramento County Main Jail	9996268	129838		D3051	Pump	Distribution, HVAC Heating Water	1.5 HP	2
306	Sacramento County Main Jail	9859532	129798	EQ-1042154	D4011	Pump	Fire Suppression, 50 HP		2
307	Sacramento County Main Jail	9859826	129518	EQ-1036341	D3013	Pump	Fuel Oil	.75 HP	2
308	Sacramento County Main Jail	9859380	129660	EQ-1035827	D2031	Pump	Sump	20 HP	2
309	Sacramento County Main Jail	9996257	129870		C1061	Raised Floors	Access Flooring, w/ Laminate		2
310	Sacramento County Main Jail	9859341	129767	EQ-1039624	B3015	Roofing	Modified Bitumen		2
311	Sacramento County Main Jail	9996273	129860		D5021	Secondary Transformer	Dry, Stepdown	15 KVA	2
312	Sacramento County Main Jail	9996278	129867		D5021	Secondary Transformer	Dry, Stepdown	15 KVA	2
313	Sacramento County Main Jail	9927078	130406		D5021	Secondary Transformer	Dry, Stepdown	75 KVA	2
314	Sacramento County Main Jail	9927087	130405		D5021	Secondary Transformer	Dry, Stepdown	37 KVA	2
315	Sacramento County Main Jail	9996263	129861		D5021	Secondary Transformer	Dry, Stepdown	15 KVA	2
316	Sacramento County Main Jail	9996258	129851		D5021	Secondary Transformer	Dry, Stepdown	15 KVA	2
317	Sacramento County Main Jail	9996249	129864		D5021	Secondary Transformer	Dry, Stepdown	30 KVA	2
318	Sacramento County Main Jail	9927100	130418		D5021	Secondary Transformer	Dry, Stepdown	63 KVA	2
319	Sacramento County Main Jail	9996294	129891		D5021	Secondary Transformer	Dry, Stepdown	30 KVA	2
320	Sacramento County Main Jail	9996277	129850		D5021	Secondary Transformer	Dry, Stepdown	30 KVA	2
321	Sacramento County Main Jail	9996259	129865		D5021	Secondary Transformer	Dry, Stepdown	15 KVA	2
322	Sacramento County Main Jail	9927072	130416		D5021	Secondary Transformer	Dry, Stepdown	63 KVA	2
323	Sacramento County Main Jail	9927076	130403		D5021	Secondary Transformer	Dry, Stepdown	37 KVA	2
324	Sacramento County Main Jail	9927104	130430		D5021	Secondary Transformer	Dry, Stepdown	70 KVA	2
325	Sacramento County Main Jail	9927091	130414		D5021	Secondary Transformer	Dry, Stepdown	63 KVA	2
326	Sacramento County Main Jail	9927102	130420		D5021	Secondary Transformer	Dry, Stepdown	63 KVA	2
327	Sacramento County Main Jail	9996286	129892		D5021	Secondary Transformer	Dry, Stepdown	30 KVA	2
328	Sacramento County Main Jail	9927110	130404		D5021	Secondary Transformer	Dry, Stepdown	37 KVA	2
329	Sacramento County Main Jail	9927097	130402		D5021	Secondary Transformer	Dry, Stepdown	70 KVA	2
330	Sacramento County Main Jail	9927103	130409		D5021	Secondary Transformer	Dry, Stepdown	75 KVA	2
331	Sacramento County Main Jail	9996284	129913		D5021	Secondary Transformer	Dry, Stepdown	15 KVA	2
332	Sacramento County Main Jail	9859575	129682	EQ-1033295	D5021	Secondary Transformer	Dry, Stepdown, 30 KVA		2
333	Sacramento County Main Jail	9859418	129642	EQ-1033296	D5021	Secondary Transformer	Dry, Stepdown, 30 KVA		2
334	Sacramento County Main Jail	9859535	129926	EQ-1033303	D5021	Secondary Transformer	Dry, Stepdown, 30 KVA		2
335	Sacramento County Main Jail	9859376	129512	EQ-1033337	D5021	Secondary Transformer	Dry, Stepdown, 30 KVA		2
336	Sacramento County Main Jail	9859626	129539	EQ-1033341	D5021	Secondary Transformer	Dry, Stepdown, 30 KVA		2
337	Sacramento County Main Jail	9859764	129496	EQ-1033344	D5021	Secondary Transformer	Dry, Stepdown, 30 KVA		2
338	Sacramento County Main Jail	9859420	129704	EQ-1033281	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
339	Sacramento County Main Jail	9859748	129894	EQ-1033292	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
340	Sacramento County Main Jail	9859416	129945	EQ-1033293	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
302	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2007	8	15	7	2025
303	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2011	11	15	4	2025
304	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal		12	15	3	2025
305	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal		11	15	4	2025
306	Replace	B1 - Basement 1 - B1FPMP - Fire Pump	Fair	3	Lifecycle/Renewal	2017	9	25	16	2025
307	Replace	B1 - Basement 1 - B1PUMP - Pump	Fair	3	Lifecycle/Renewal	1988	7	15	8	2025
308	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	1988	21	25	4	2025
309	Replace	B1 - Basement 1 - B1CALID - Ca Id	Fair	3	Lifecycle/Renewal		27	30	3	2025
310	Replace	Roof Level - Throughout	Fair	3	Aged But Functional	2005	18	20	2	2025
311	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
312	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Lifecycle/Renewal	1989	28	30	2	2025
313	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional		27	30	3	2025
314	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional		27	30	3	2025
315	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
316	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	1989	27	30	3	2025
317	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
318	Replace	09 - Ninth Floor - Secure Elevator Room	Fair	3	Lifecycle/Renewal	2011	15	30	15	2025
319	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
320	Replace	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	1989	27	30	3	2025
321	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
322	Replace	09 - Ninth Floor - Secure Elevator Room	Fair	3	Lifecycle/Renewal	2011	15	30	15	2025
323	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional		27	30	3	2025
324	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional		27	30	3	2025
325	Replace	09 - Ninth Floor - Secure Elevator Room	Fair	3	Lifecycle/Renewal	2011	15	30	15	2025
326	Replace	09 - Ninth Floor - Secure Elevator Room	Fair	3	Lifecycle/Renewal	2011	15	30	15	2025
327	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
328	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional		27	30	3	2025
329	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional		27	30	3	2025
330	Replace	09 - Ninth Floor - Communication Room	Fair	3	Aged But Functional	1994	27	30	3	2025
331	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
332	Replace	08 - Eighth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
333	Replace	07 - Seventh Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
334	Replace	06 - Sixth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
335	Replace	04 - Fourth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
336	Replace	03 - Third Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
337	Replace	05 - Fifth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
338	Replace	05 - Fifth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
339	Replace	07 - Seventh Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
340	Replace	08 - Eighth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
302	1	5100	EA	0		1.138	31	$ 7,602.98	US Motors	P63ACF-1165
303	1	5100	EA	0		1.138	31	$ 7,602.98	Paco	11-30121-6A6201
304	1	5100	EA	0		1.138	31	$ 7,602.98	US Motors	P63ACF-1165
305	1	5100	EA	0		1.138	31	$ 7,602.98	US Motor	P63ACE-1164
306	1	50000	EA	0		1.138	31	$ 74,539.00	Pentair Aurora	5-491-18A
307	2	2600	EA	0		1.138	31	$ 7,752.06	Viking	GG195D
308	1	13400	EA	0		1.138	31	$ 19,976.45	Paco	4540700860751682
309	225	31	SF	0		1.138	31	$ 10,398.19		
310	4500	10	SF	0		1.138	31	$ 67,085.10		
311	1	6000	EA	0		1.138	31	$ 8,944.68	Field Transformer	NA
312	1	6000	EA	0		1.138	31	$ 8,944.68	Field Transformer	NA
313	1	10000	EA	0		1.138	31	$ 14,907.80	No dataplate	No dataplate
314	1	6700	EA	0		1.138	31	$ 9,988.23	No dataplate	No dataplate
315	1	6000	EA	0		1.138	31	$ 8,944.68	Field Transformer	NA
316	1	6000	EA	0		1.138	31	$ 8,944.68	Field Transformer	NA
317	1	6700	EA	0		1.138	31	$ 9,988.23	Field Transformer	NA
318	1	10000	EA	0		1.138	31	$ 14,907.80	Jefferson Electric	423-E001-030
319	1	6700	EA	0		1.138	31	$ 9,988.23	Field Transformer	NA
320	1	6700	EA	0		1.138	31	$ 9,988.23	Field Transformer	NA
321	1	6000	EA	0		1.138	31	$ 8,944.68	Field Transformer	NA
322	1	10000	EA	0		1.138	31	$ 14,907.80	Jefferson Electric	423-E001-030
323	1	6700	EA	0		1.138	31	$ 9,988.23	No dataplate	No dataplate
324	1	10000	EA	0		1.138	31	$ 14,907.80	Field Transformers	748
325	1	10000	EA	0		1.138	31	$ 14,907.80	Jefferson Electric	423-E001-030
326	1	10000	EA	0		1.138	31	$ 14,907.80	Jefferson Electric	423-E001-030
327	1	6700	EA	0		1.138	31	$ 9,988.23	Field Transformer	NA
328	1	6700	EA	0		1.138	31	$ 9,988.23	No dataplate	No dataplate
329	1	10000	EA	0		1.138	31	$ 14,907.80	No dataplate	No dataplate
330	1	10000	EA	0		1.138	31	$ 14,907.80	Olsen	No dataplate
331	1	6000	EA	0		1.138	31	$ 8,944.68	Field Transformers	7478
332	1	6700	EA	0		1.138	31	$ 9,988.23	Square D	30T3HFCU
333	1	6700	EA	0		1.138	31	$ 9,988.23	Square D	30T3HFCU
334	1	6700	EA	0		1.138	31	$ 9,988.23	Square D	30T3HFCU
335	1	6700	EA	0		1.138	31	$ 9,988.23	Square D	3073HFCV
336	1	6700	EA	0		1.138	31	$ 9,988.23	Square D	3T3HFCU
337	1	6700	EA	0		1.138	31	$ 9,988.23	Square D	30T3HFCU
338	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	CAT.45T3HF-CU
339	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	45T3HF-CU
340	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	45T3HF-CU

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
302	NA	HWP 2	11/09/2025	0DE75B85-1923-4C32-938E-74B398F13490		EQ-1036562	orange
303	KY G67053C	HWP 3	11/09/2025	68B04BAC-8634-4256-802C-7BDFDBF0E749		EQ-1036563	orange
304	NA		11/09/2025	5A30FB78-3ACE-4E78-A24D-0C0B5D301FC3			blue
305	NA		11/09/2025	D8520050-1312-4D95-B266-80AEE0C3366A			blue
306	16-2484390	FIRE PUMP	10/30/2025	3BCD79CA-B378-4642-B70B-290881E3D560		EQ-1042154	green
307	"""85-41311A & 85-4311B	FUEL TRANSFER PUMPS	11/09/2025	7CDA2D78-3C18-4E9C-BD16-95BB3E18E216		EQ-1036341	orange
308	"""HY-G67057A/HYG67057I	SUMP PUMPS	11/09/2025	24A5EDEA-844A-41E7-9231-06EDBA75FAAE		EQ-1035827	orange
309			11/09/2025	887099F7-A1E2-47C1-A834-909E7603BBCE			blue
310		ROOF	11/08/2025	5B64C97A-DA94-4985-8687-986188982928		EQ-1039624	orange
311	1086		11/09/2025	500F77F2-511C-4E52-8193-AF92D2DFD334			blue
312	0687		11/09/2025	55263D40-FD49-4450-B2E6-344DB51775E5			blue
313	No dataplate		10/30/2025	0EC33481-813A-4274-ACF1-891CAAC2F772			blue
314	0636		10/30/2025	D63A5E6F-242A-47DC-8688-154A7A23D57A			blue
315	1086		11/09/2025	709AB8CC-C11B-4990-88BE-923FA78E8A6B			blue
316	0687		11/09/2025	788A4849-F98B-42C9-B977-FC624E860208			blue
317	0886		11/09/2025	A87E6288-EAC0-47AB-AB07-30F73C791E8A			blue
318	0003		10/30/2025	D67879A3-8146-4876-9699-6DC5A13AE639			blue
319	0686		11/09/2025	4379C4CD-D8CF-4A06-A149-B5C9987B2BA1			blue
320	0986		11/09/2025	2F544A46-11E4-4507-B727-496E4F22F2B0			blue
321	0887		11/09/2025	964CB783-84AD-4DA8-8CEB-8F1B8244459B			blue
322	0004		10/30/2025	9D788258-C1A6-4889-815E-D84C87E9E46C			blue
323	No dataplate		10/30/2025	D6C9BB53-82C3-4DF1-A059-267ED9E5AB50			blue
324	0986		10/30/2025	0A116937-8B2A-4536-B3DC-36B6F3C5627E			blue
325	0002		10/30/2025	6E1296BE-29E2-4DFE-9CC5-199F560D0026			blue
326	0001		10/30/2025	76CFE0BC-5581-4876-89A0-77B64D30EDC3			blue
327	0786		11/09/2025	5279CC8D-F31A-4AC6-9F52-FBE12EE51062			blue
328	No dataplate		10/30/2025	F42983DB-33E1-49C2-839D-645079DE494B			blue
329	No dataplate		10/30/2025	816D3C24-CA3F-4619-882E-D6C8FBC60D4F			blue
330	No dataplate		10/30/2025	E3399D00-9D57-491D-BBB9-3C32A0D97A1F			blue
331	1086		11/09/2025	66EDCE3D-97FF-4A20-8354-CEB0F7CDEDAA			blue
332	600889A006	TX-15	10/30/2025	10224AC2-A7A7-428D-BEA3-8E6E855432E6		EQ-1033295	green
333	6008889H003	TX-14	10/29/2025	8BB323DB-2D4C-4B4F-A083-255FB4E6F55B		EQ-1033296	green
334	600889A 004	TX 13	10/30/2025	87ACA7DF-8FFC-4A2B-B909-143B25F2AA75		EQ-1033303	green
335	600889A 002	TX 11	10/30/2025	F93255F6-86FE-41AC-A421-A2028635D6DF		EQ-1033337	green
336	UNK	TX 10	10/29/2025	772DDB8C-ACD7-4BD8-90B7-02CDCE6B826C		EQ-1033341	green
337	600889A 001	TX-12	10/29/2025	80AF3F21-66B1-414A-BA2C-051E1DE86F35		EQ-1033344	green
338	600890A-001	TX-6	10/30/2025	594E81EB-77E1-4FD1-B2FF-EBB3DA170916		EQ-1033281	green
339	600890A	TX-8	10/30/2025	12B66F3D-BF4F-48E6-8580-BF8180013F94		EQ-1033292	green
340	600890A 002	TX-9	10/30/2025	89EA9298-3C9F-453A-854A-064780885076		EQ-1033293	green

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
341	Sacramento County Main Jail	9859553	129967	EQ-1033298	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
342	Sacramento County Main Jail	9859766	129862	EQ-1033301	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
343	Sacramento County Main Jail	9859424	129545	EQ-1033302	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
344	Sacramento County Main Jail	9859368	129695	EQ-1033304	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
345	Sacramento County Main Jail	9859634	129619	EQ-1033342	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
346	Sacramento County Main Jail	9859836	129789	EQ-1033398	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
347	Sacramento County Main Jail	9859799	129877	EQ-1033400	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
348	Sacramento County Main Jail	9859412	129709	EQ-1033542	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
349	Sacramento County Main Jail	9859628	129651	EQ-1033550	D5021	Secondary Transformer	Dry, Stepdown, 45 KVA		2
350	Sacramento County Main Jail	9922873	130302		D2016	Shower	Ceramic Tile		2
351	Sacramento County Main Jail	9959454	130288		D2016	Shower	Valve & Showerhead		2
352	Sacramento County Main Jail	9959444	130288		D2016	Shower	Valve & Showerhead		2
353	Sacramento County Main Jail	9959439	130288		D2016	Shower	Valve & Showerhead		2
354	Sacramento County Main Jail	9960676	130193		G2031	Sidewalk	Concrete, Large Areas		3
355	Sacramento County Main Jail	9960670	130182		G2063	Signage	Property, Building or Pole-Mounted		3
356	Sacramento County Main Jail	9960671	130313		G2063	Signage	Property, Monument		3
357	Sacramento County Main Jail	9922819	130211		D2016	Sink/Lavatory	Vanity Top, Enameled Steel		3
358	Sacramento County Main Jail	9859509	129512	EQ-1028986	D3037	Split System Ductless	Single Zone, Condenser & Evaporator, 1.5 to 2 TON	2 TON	2
359	Sacramento County Main Jail	9859449	129614	EQ-1033499	D5039	Variable Frequency Drive	VFD, by HP of Motor	20 HP	2
360	Sacramento County Main Jail	9859853	129589	EQ-1033511	D5039	Variable Frequency Drive	VFD, by HP of Motor	10 HP	2
361	Sacramento County Main Jail	9859354	129508	EQ-1033748	D5039	Variable Frequency Drive	VFD, by HP of Motor	20 HP	2
362	Sacramento County Main Jail	9859519	129786	EQ-1033758	D5039	Variable Frequency Drive	VFD, by HP of Motor	10 HP	2
363	Sacramento County Main Jail	9859564	129796	EQ-1033759	D5039	Variable Frequency Drive	VFD, by HP of Motor	10 HP	2
364	Sacramento County Main Jail	9859705	129506	EQ-1041642	D5039	Variable Frequency Drive	VFD, by HP of Motor	7.5 HP	2
365	Sacramento County Main Jail	9996247	129813		D5039	Variable Frequency Drive	VFD, by HP of Motor	30 HP	2
366	Sacramento County Main Jail	9996270	129811		D5039	Variable Frequency Drive	VFD, by HP of Motor	30 HP	2
367	Sacramento County Main Jail	9996281	129812		D5039	Variable Frequency Drive	VFD, by HP of Motor	30 HP	2
368	Sacramento County Main Jail	9859330	129266	EQ-1033505	D5039	Variable Frequency Drive	VFD, by HP of Motor, 10 HP	10 HP	2
369	Sacramento County Main Jail	9859722	129797	EQ-1033753	D5039	Variable Frequency Drive	VFD, by HP of Motor, 15 HP	15 HP	2
370	Sacramento County Main Jail	9859422	129838	EQ-1033754	D5039	Variable Frequency Drive	VFD, by HP of Motor, 40 HP	40 HP	2
371	Sacramento County Main Jail	9859687	129681	EQ-1033755	D5039	Variable Frequency Drive	VFD, by HP of Motor, 40 HP	40 HP	2
372	Sacramento County Main Jail	9859801	129330	EQ-1033504	D5039	Variable Frequency Drive	VFD, by HP of Motor, 5 HP	5 HP	2
373	Sacramento County Main Jail	9859713	129395	EQ-1041643	D5039	Variable Frequency Drive	VFD, by HP of Motor, 5 HP	5 HP	2
374	Sacramento County Main Jail	9859696	129337	EQ-1033747	D5039	Variable Frequency Drive	VFD, by HP of Motor, 7.5 HP	7.5 HP	2
375	Sacramento County Main Jail	9859679	129653	EQ-1036793	D8015	BAS/HVAC Controls	Extensive/Robust BMS or Smart Building System		2
376	Sacramento County Main Jail	9927109	130411		D5023	Distribution Panel	120/208 V	225 AMP	2
377	Sacramento County Main Jail	9927086	130410		D5023	Distribution Panel	120/240 V, Residential Style	100 AMP	2
378	Sacramento County Main Jail	9927068	130408		D5023	Distribution Panel	277/480 V	225 AMP	2
379	Sacramento County Main Jail	9922841	129999		D3055	HVAC System	Ductwork w/ VAV/FCU, High Density		2

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
341	Replace	07 - Seventh Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
342	Replace	06 - Sixth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
343	Replace	08 - Eighth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
344	Replace	05 - Fifth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
345	Replace	03 - Third Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
346	Replace	04 - Fourth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
347	Replace	06 - Sixth Floor - Electrical Room	Fair	3	Aged But Functional	1988	27	30	3	2025
348	Replace	04 - Fourth Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
349	Replace	03 - Third Floor - Electrical Room	Fair	3	Aged But Functional	1989	27	30	3	2025
350	Replace	All building - Throughout	Fair	3	Aged But Functional		27	30	3	2025
351	Replace	All building - Throughout	Fair	3	Aged But Functional		26	30	4	2025
352	Replace	All building - Throughout	Fair	3	Aged But Functional		26	30	4	2025
353	Replace	All building - Throughout	Fair	3	Aged But Functional		26	30	4	2025
354	Replace	S1 - Site	Fair	3	Lifecycle/Renewal	1989	37	50	13	2025
355	Replace/Install	S1 - Site	Fair	3	Aged But Functional		18	20	2	2025
356	Replace/Install	S1 - Site	Fair	3	Aged But Functional		18	20	2	2025
357	Replace	All building - Throughout	Fair	3	Aged But Functional		27	30	3	2025
358	Replace	02 - Second Floor - 02EXT - External	Fair	3	Aged But Functional	2005	13	15	2	2025
359	Replace/Install	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Lifecycle/Renewal	1900	15	20	5	2025
360	Replace/Install	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Lifecycle/Renewal	1900	15	20	5	2025
361	Replace/Install	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Lifecycle/Renewal	1900	15	20	5	2025
362	Replace/Install	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	15	20	5	2025
363	Replace/Install	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Lifecycle/Renewal	1900	15	20	5	2025
364	Replace/Install	B1 - Basement 1 - B1WTRTNK - East Mechanical	Fair	3	Aged But Functional	2001	18	20	2	2025
365	Replace/Install	B1 - Basement 1 - B1PUMP - Pump	Fair	3	Lifecycle/Renewal	2011	15	20	5	2025
366	Replace/Install	B1 - Basement 1 - B1PUMP - Pump	Fair	3	Lifecycle/Renewal	2011	15	20	5	2025
367	Replace/Install	B1 - Basement 1 - B1PUMP - Pump	Fair	3	Lifecycle/Renewal	2017	9	20	11	2025
368	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Lifecycle/Renewal	1900	15	20	5	2025
369	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1989	18	20	2	2025
370	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Lifecycle/Renewal		11	20	9	2025
371	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Fair	3	Aged But Functional	1989	18	20	2	2025
372	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Lifecycle/Renewal	1900	15	20	5	2025
373	Replace	09 - Ninth Floor - 09MEC - Core Mechanical Room	Fair	3	Aged But Functional	2001	18	20	2	2025
374	Replace	B1 - Basement 1 - B1MC1 - Mechanical Room	Fair	3	Lifecycle/Renewal	1900	15	20	5	2025
375	Install	All Building - Throughout	Poor	4	Performance/Integrity	1989	15	15	0	2025
376	Replace	09 - Ninth Floor - Communication Room	Poor	4	Safety		30	30	0	2025
377	Replace	09 - Ninth Floor - Communication Room	Poor	4	Safety		30	30	0	2025
378	Replace	09 - Ninth Floor - Communication Room	Poor	4	Safety		30	30	0	2025
379	Replace	All building - Throughout	Poor	4	Performance/Integrity		30	30	0	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
341	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	45T3HF-CU
342	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	45T3HF-CU
343	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	45T3HF-CU
344	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	
345	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	45T3HF-CU
346	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	45T3 HF-CU
347	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	45T3HFCU
348	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	
349	1	7600	EA	0		1.138	31	$ 11,329.93	Square D	
350	8	2500	EA	0		1.138	31	$ 29,815.60		
351	120	800	EA	0		1.138	31	$ 143,114.88		
352	120	800	EA	0		1.138	31	$ 143,114.88		
353	120	800	EA	0		1.138	31	$ 143,114.88		
354	1000	9	SF	0		1.138	31	$ 13,417.02		
355	1	1500	EA	0		1.138	31	$ 2,236.17		
356	1	3000	EA	0		1.138	31	$ 4,472.34		
357	35	1100	EA	0		1.138	31	$ 57,395.03		
358	1	4800	EA	0		1.138	31	$ 7,155.74	Carrier	38HDC024331
359	1	10000	EA	0		1.138	31	$ 14,907.80	ABB/ASEA Brown Boveri	ACH 550
360	1	7000	EA	0		1.138	31	$ 10,435.46	ABB/ASEA Brown Boveri	ACH 400
361	1	10000	EA	0		1.138	31	$ 14,907.80	ABB/ASEA Brown Boveri	ACH 400
362	1	7000	EA	0		1.138	31	$ 10,435.46	ABB	NA
363	1	7000	EA	0		1.138	31	$ 10,435.46	ABB	NA
364	1	6200	EA	0		1.138	31	$ 9,242.84	ABB/ASEA Brown Boveri	ACH 400
365	1	14700	EA	0		1.138	31	$ 21,914.47	ABB	ACH550-VCR-045A-4
366	1	14700	EA	0		1.138	31	$ 21,914.47	ABB	ACH550-VCR-045A-4
367	1	14700	EA	0		1.138	31	$ 21,914.47	ABB	ACH550-VCR-045A-4+F267
368	1	7000	EA	0		1.138	31	$ 10,435.46	ABB/ASEA Brown Boveri	ACH 400
369	1	8800	EA	0		1.138	31	$ 13,118.86	Toshiba Houston	
370	1	17000	EA	0		1.138	31	$ 25,343.26	Toshiba Houston	
371	1	17000	EA	0		1.138	31	$ 25,343.26	Toshiba Houston	
372	1	5300	EA	0		1.138	31	$ 7,901.13	ABB/ASEA Brown Boveri	ACH 400
373	1	5300	EA	0		1.138	31	$ 7,901.13	ABB/ASEA Brown Boveri	ACH 401C00932
374	1	6200	EA	0		1.138	31	$ 9,242.84	ABB/ASEA Brown Boveri	ACH 550
375	491000	6	SF	0		1.138	31	$ 4,391,837.88		
376	1	2000	EA	0		1.138	31	$ 2,981.56		
377	1	1100	EA	0		1.138	31	$ 1,639.86	No dataplate	No dataplate
378	1	3000	EA	0		1.138	31	$ 4,472.34		
379	491000	8	SF	0		1.138	31	$ 5,855,783.84		

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
341	600890A 010	TX-20	10/30/2025	AD9EB1F4-014F-40A4-BCB2-89D2E230AD4D		EQ-1033298	green
342	600890A 009	TX 19	10/30/2025	2B366F3C-DC18-4E24-B93B-EB8253502F78		EQ-1033301	green
343	800890A 122	TX 21	10/29/2025	D18137F5-B6B7-46DE-BDCD-19D65A971EA7		EQ-1033302	green
344	600890-011	TX-18	10/30/2025	A459B022-C1F1-4C91-A73B-53E54A69D6A3		EQ-1033304	green
345	600890A 007	TX 4	10/29/2025	92EC5E70-95B0-4B7F-857F-BDDAB814FADD		EQ-1033342	green
346	600890A 008	TX-5	10/30/2025	ED884CAA-C17D-4F1B-868A-8E0EA5772232		EQ-1033398	green
347	600880A 006	TX-7	10/30/2025	41E8A66D-B514-4428-840C-D71FB85CBC9C		EQ-1033400	green
348	600890A004	TX-17	10/30/2025	7472FBFF-9EB0-43DC-8303-A6F48B3CD306		EQ-1033542	green
349	600890A	TX-16	10/30/2025	2C59FE10-B5E7-4053-9675-E9EE759F4872		EQ-1033550	green
350			10/30/2025	2E25C444-9700-456C-BBCA-C39E2387A31D			blue
351			10/30/2025	BBFEBB20-9309-4F11-BA64-5713E575B64F			blue
352			10/29/2025	BBFEBB20-9309-4F11-BA64-5713E575B64F			blue
353			10/29/2025	BBFEBB20-9309-4F11-BA64-5713E575B64F			blue
354			10/30/2025	5C3898DC-0D73-4F1F-8D31-9CA22DD6EA94			blue
355			10/30/2025	ED2F9493-B680-4AB6-B0EF-09416FC54E3D			blue
356			10/30/2025	AD47C0E6-D1C3-47FD-9076-AA2FBAE21154			blue
357		Sink/Lavatory	10/30/2025	8AD91451-C2A3-4C9D-90DA-2E218B69327D			blue
358	3500X97320	CENTRAL CONTROL AC	11/09/2025	7176137F-B250-4AB6-8568-174C28D22A3A		EQ-1028986	orange
359	2054900107	AIR CONDITIONER-14	11/09/2025	09625459-AB16-4B5A-871A-33001B4DF0A8		EQ-1033499	green
360	2001900276	AIR CONDITIONER 10	11/09/2025	0E2F7A50-58B5-459A-AB44-6B6C4173561C		EQ-1033511	orange
361	1011900719	AIR CONDITONER 1	11/09/2025	47584703-58A3-4950-B9B9-1E074F3EE10A		EQ-1033748	orange
362	NA	RETURN FAN-7	11/09/2025	A0F3E517-2D74-470B-8CEC-EE848B9767E6		EQ-1033758	orange
363	NA	SUPPLY FAN-2	11/09/2025	6C7C1904-57F2-4C07-96E5-6C089B598F82		EQ-1033759	orange
364	2012000298	RETURN FAN-5	11/09/2025	C6B10A42-9973-4641-B69F-8E4040A38793		EQ-1041642	green
365	2113903544	CWP 1	11/09/2025	01EDACA7-AFEF-479C-B4B3-4B6AD583E5BD			blue
366	2113904089	CWP 3	11/09/2025	B1541DBF-F22A-42C0-925E-5364B8DF2E54			blue
367	2173602473	CWP 2	11/09/2025	45B4FB45-1D00-48EA-9FDD-A349FA6AD643			blue
368	2012500262	RETURN FAN-1	11/09/2025	F28956C7-6324-4B44-ABBF-C5A6F3C34D89		EQ-1033505	orange
369	UNK	AIR CONDITIONER-16	10/30/2025	6E239779-C1BD-4CA2-9090-45B57B9CC9EF		EQ-1033753	green
370	UNK	SUPPLY FAN-1	10/30/2025	30DF010C-9DAC-46CF-B123-8280ECB27081		EQ-1033754	orange
371	UNK	RETURN FAN-6	10/30/2025	4630E2B6-3144-440C-8BE5-42278E6E8DCC		EQ-1033755	green
372	2012000367	RETURN FAN 9	11/09/2025	25EE97C7-D015-4500-A787-A93069E33E66		EQ-1033504	orange
373	2012500272	AC-17	11/09/2025	E4A26124-7668-45FC-A8DB-6E2B65EB652A		EQ-1041643	green
374	2042101724	AIR CONDITONER 3	11/09/2025	D704F092-5FD5-4D7F-BDB8-FA2BC23ED577		EQ-1033747	orange
375		HVAC CONTROL PANEL	11/09/2025	ACC764C5-BC47-4CD5-B377-2E2CCAB5657E	Bas system is aged and slow to reac	EQ-1036793	orange
376			10/30/2025	049F90BE-2DBD-4471-B3FE-3620A6A9690C	Industrial Electric Mfg. (IEM) panels can fail to trip during an ove		blue
377	No dataplate		10/30/2025	9E1345CA-7DF2-40C0-9E6A-F94DBA6FB665	Industrial Electric Mfg. (IEM) panels can fail to trip during an ove		blue
378			10/30/2025	406B7B77-D47E-4453-A558-5C4D4A64C234	Industrial Electric Mfg. (IEM) panels can fail to trip during an ove		blue
379			10/30/2025	0FACF990-01FB-44C6-902A-B68D571547DD	In some areas return and supply registers are located within a fe		blue

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
380	Sacramento County Main Jail	9859758	129663	EQ-1031277	D5041	Lighting Controls	Dimming Panel, Standard		2
381	Sacramento County Main Jail	9859805	129916	EQ-1036835	D5041	Lighting Controls	Dimming Panel, Standard		2
382	Sacramento County Main Jail	9859852	129757	EQ-1036836	D5041	Lighting Controls	Dimming Panel, Standard		2
383	Sacramento County Main Jail	9859433	129519	EQ-1036837	D5041	Lighting Controls	Dimming Panel, Standard		2
384	Sacramento County Main Jail	9859692	129957	EQ-1036851	D5041	Lighting Controls	Dimming Panel, Standard		2
385	Sacramento County Main Jail	9859411	129974	EQ-1036852	D5041	Lighting Controls	Dimming Panel, Standard		2
386	Sacramento County Main Jail	9859772	129666	EQ-1036853	D5041	Lighting Controls	Dimming Panel, Standard		2
387	Sacramento County Main Jail	9859684	129861	EQ-1036854	D5041	Lighting Controls	Dimming Panel, Standard		2
388	Sacramento County Main Jail	9859627	129549	EQ-1037003	D5041	Lighting Controls	Dimming Panel, Standard		2
389	Sacramento County Main Jail	9859528	129937	EQ-1037004	D5041	Lighting Controls	Dimming Panel, Standard		2
390	Sacramento County Main Jail	9859385	129655	EQ-1037005	D5041	Lighting Controls	Dimming Panel, Standard		2
391	Sacramento County Main Jail	9859360	129962	EQ-1037006	D5041	Lighting Controls	Dimming Panel, Standard		2
392	Sacramento County Main Jail	9859569	129870	EQ-1037007	D5041	Lighting Controls	Dimming Panel, Standard		2
393	Sacramento County Main Jail	9996280	129919		D5081	Lightning Protection System	Metal		2
394	Sacramento County Main Jail	10314082			F1024	Corridor	Reconfigure		2
395	Sacramento County Main Jail	10314092			F3011	Demolition & Disposal	Wall Openings		2
396	Sacramento County Main Jail	10015363			P2032	Engineering Study	Structural, Seismic		2
397	Sacramento County Main Jail	10314083			F1024	Interview Rooms	Accessible		2
398	Sacramento County Main Jail	10314024			F1024	Medical Room	New Construction		2
399	Sacramento County Main Jail	9859668	129550	FSE-1037238	E1038	Foodservice Equipment	Range/Oven, 6-Burner		3
400	Sacramento County Main Jail	9859410	129350	FSE-1037240	E1038	Foodservice Equipment	Range/Oven, 6-Burner		3
401	Sacramento County Main Jail	9859862	129426	FSE-1037242	E1038	Foodservice Equipment	Range/Oven, 6-Burner		3
402	Sacramento County Main Jail	9859491	129380	FSE-1037239	E1038	Foodservice Equipment	Range/Oven, 8-Burner		3
403	Sacramento County Main Jail	9996290	129824		D3029	Boiler Supplemental Components	Expansion Tank	50 GAL	3
404	Sacramento County Main Jail	9859744	129284	EQ-1027661	D3029	Boiler Supplemental Components	Expansion Tank, 11 to 30 GAL	30 GAL	3
405	Sacramento County Main Jail	9859441	129867	EQ-1027532	D3029	Boiler Supplemental Components	Expansion Tank, 176 to 250 GAL	250 GAL	3
406	Sacramento County Main Jail	9859689	129801	EQ-1027533	D3029	Boiler Supplemental Components	Expansion Tank, 176 to 250 GAL	250 GAL	3
407	Sacramento County Main Jail	9859431	129890	EQ-1027534	D3029	Boiler Supplemental Components	Expansion Tank, 176 to 250 GAL	250 GAL	3
408	Sacramento County Main Jail	9859621	129808	EQ-1027535	D3029	Boiler Supplemental Components	Expansion Tank, 176 to 250 GAL	250 GAL	3
409	Sacramento County Main Jail	9859390	129600	EQ-1027649	D3029	Boiler Supplemental Components	Expansion Tank, 176 to 250 GAL	250 GAL	3
410	Sacramento County Main Jail	9859391	129804	EQ-1027650	D3029	Boiler Supplemental Components	Expansion Tank, 176 to 250 GAL	250 GAL	3
411	Sacramento County Main Jail	9859486	129782	EQ-1027652	D3029	Boiler Supplemental Components	Expansion Tank, 176 to 250 GAL	250 GAL	3
412	Sacramento County Main Jail	9859399	129589	EQ-1027653	D3029	Boiler Supplemental Components	Expansion Tank, 176 to 250 GAL	250 GAL	3

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
380	Replace	01 - First Floor - 01BKGMEN - Booking Men	Poor	4	Performance/Integrity	1989	19	20	1	2025
381	Replace	03 - Third Floor - Electrical Room	Poor	4	Performance/Integrity	1989	19	20	1	2025
382	Replace	04 - Fourth Floor - Electrical Room	Poor	4	Performance/Integrity	1989	19	20	1	2025
383	Replace	05 - Fifth Floor - Electrical Room	Poor	4	Performance/Integrity	1989	19	20	1	2025
384	Replace	02 - Second Floor - 02CUST - Custodial Closet	Poor	4	Performance/Integrity	1989	19	20	1	2025
385	Replace	02 - Second Floor - Electrical Room East	Poor	4	Performance/Integrity	1989	19	20	1	2025
386	Replace	04 - Fourth Floor - Electrical Room	Poor	4	Performance/Integrity	1989	19	20	1	2025
387	Replace	05 - Fifth Floor - Electrical Room	Poor	4	Performance/Integrity	1989	19	20	1	2025
388	Replace	07 - Seventh Floor - Electrical Room	Poor	4	Performance/Integrity	1989	19	20	1	2025
389	Replace	07 - Seventh Floor - Electrical Room	Poor	4	Performance/Integrity	1989	19	20	1	2025
390	Replace	08 - Eighth Floor - Electrical Room	Poor	4	Performance/Integrity	1989	19	20	1	2025
391	Replace	06 - Sixth Floor - Electrical Room	Poor	4	Performance/Integrity	1989	19	20	1	2025
392	Replace	06 - Sixth Floor - Electrical Room	Poor	4	Performance/Integrity	1989	19	20	1	2025
393	Replace	Roof Level - Throughout	Failed	5	Safety		40	40	0	2025
394	Replace	Medical Room	NA	6	Retrofit/Adaptation		25	25	0	2026
395	Remove Wall section	Accessible Corridors	NA	6	Retrofit/Adaptation		0	0	0	2026
396	Evaluate/Report	Throughout	NA	6	Performance/Integrity		0	0	0	2025
397	Replace	Elevator Core	NA	6	Retrofit/Adaptation		35	35	0	2026
398	Replace	Each Floor	NA	6	Retrofit/Adaptation		35	35	0	2026
399	Replace	B1 - Basement 1 - B1KIT - Kitchen	Excellent	1	Lifecycle/Renewal	2025	1	15	14	2025
400	Replace	B1 - Basement 1 - B1KIT - Kitchen	Excellent	1	Lifecycle/Renewal	2025	1	15	14	2025
401	Replace	B1 - Basement 1 - B1KIT - Kitchen	Excellent	1	Lifecycle/Renewal	2025	1	15	14	2025
402	Replace	B1 - Basement 1 - B1KIT - Kitchen	Excellent	1	Lifecycle/Renewal	2025	1	15	14	2025
403	Replace	B1 - Basement 1 - B1BSTPMP - Booster Pump	Good	2	Lifecycle/Renewal	2012	14	40	26	2025
404	Replace	B1 - Basement 1 - B1BLR - Boiler	Good	2	Lifecycle/Renewal	2018	8	40	32	2025
405	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Good	2	Lifecycle/Renewal	2018	8	40	32	2025
406	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Good	2	Lifecycle/Renewal	2018	8	40	32	2025
407	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Good	2	Lifecycle/Renewal	2018	8	40	32	2025
408	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Good	2	Lifecycle/Renewal	2018	8	40	32	2025
409	Replace	09 - Ninth Floor - 09EMEC - East Mechanical Room	Good	2	Lifecycle/Renewal	2018	8	40	32	2025
410	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Good	2	Lifecycle/Renewal	2018	8	40	32	2025
411	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Good	2	Lifecycle/Renewal	2018	8	40	32	2025
412	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Good	2	Lifecycle/Renewal	2018	8	40	32	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
380	1	1760	EA	0		1.138	31	$ 2,623.77	Lighting Control Panel	
381	1	1760	EA	0		1.138	31	$ 2,623.77		
382	1	1760	EA	0		1.138	31	$ 2,623.77		
383	1	1760	EA	0		1.138	31	$ 2,623.77		
384	1	1760	EA	0		1.138	31	$ 2,623.77	Square D	
385	1	1760	EA	0		1.138	31	$ 2,623.77	Square D	
386	1	1760	EA	0		1.138	31	$ 2,623.77		
387	1	1760	EA	0		1.138	31	$ 2,623.77	Square D	
388	1	1760	EA	0		1.138	31	$ 2,623.77	Square D	
389	1	1760	EA	0		1.138	31	$ 2,623.77	Square D	
390	1	1760	EA	0		1.138	31	$ 2,623.77	Square D	
391	1	1760	EA	0		1.138	31	$ 2,623.77	Square D	
392	1	1760	EA	0		1.138	31	$ 2,623.77	Square D	
393	1	4200	EA	0		1.138	31	$ 6,261.28		
394	120	175	SF	0		1.138	31	$ 31,306.38		
395	480	124	SF	0		1.138	31	$ 88,731.23		
396	1	20000	EA	0		1.138	31	$ 29,815.60		
397	5268	240	SF	0		1.138	31	$ 1,884,822.97		
398	1596	200	SF	0		1.138	31	$ 475,856.98		
399	1	6000	EA	0		1.138	31	$ 8,944.68	Vulcan	No dataplate
400	1	6000	EA	0		1.138	31	$ 8,944.68	Vulcan	No dataplate
401	1	6000	EA	0		1.138	31	$ 8,944.68	Vulcan	No dataplate
402	1	7400	EA	0		1.138	31	$ 11,031.77	Vulcan	No dataplate
403	1	2700	EA	0		1.138	31	$ 4,025.11	WESSELS	FX300V
404	1	2180	EA	0		1.138	31	$ 3,249.90	Wessels	FXA-700
405	1	5200	EA	0		1.138	31	$ 7,752.06	Wessels	FXA-700
406	1	5200	EA	0		1.138	31	$ 7,752.06	Wessels	FXA-700
407	1	5200	EA	0		1.138	31	$ 7,752.06	Wessels	FXA-700
408	1	5200	EA	0		1.138	31	$ 7,752.06	Wessels	FXA-700
409	1	5200	EA	0		1.138	31	$ 7,752.06	Wessels	FXA-700
410	1	5200	EA	0		1.138	31	$ 7,752.06	Wessels	FXA-700
411	1	5200	EA	0		1.138	31	$ 7,752.06	Wessels	FXA-700
412	1	5200	EA	0		1.138	31	$ 7,752.06	Wessels	FXA-700

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
380	UNK	PANEL LCP13	10/26/2025	FD8D01A6-8EFF-4562-B81B-9D75E8A3692F	Past its expected useful life and sho	EQ-1031277	green
381	UNK	PANEL LCP32	10/26/2025	1780E308-F308-4A27-94BD-1CD421FB608E	Past its expected useful life and sho	EQ-1036835	green
382	UNK	PANEL LCP41	10/27/2025	3E52E721-496E-442E-818B-2FF47D580B7B	Past its expected useful life and sho	EQ-1036836	green
383	UNK	PANEL LCP 52	10/26/2025	449DB8D4-2C4A-40FA-9751-B99ACDECD607	Past its expected useful life and sho	EQ-1036837	green
384	UNK	PANEL LCP 22	10/26/2025	C5553919-DB71-4B83-B16D-D8989D2044AF	Past its expected useful life and nee	EQ-1036851	green
385	UNK	PANEL LCP-21	10/26/2025	20880644-12DB-482F-B32A-DFA6DAE1CC30	Past its expected useful life and sho	EQ-1036852	green
386	UNK	PANEL LCP42	10/26/2025	C455F78A-A5C7-4095-B564-69881C257490	Past its expected useful life and sho	EQ-1036853	green
387	UNK	PANEL LCP51	10/27/2025	A1C4BC68-97E2-49F0-B6EC-9A7FA1D131B6	Past its expected useful life and sho	EQ-1036854	green
388	UNK	LCP 72	10/26/2025	F5E91CD5-FCAA-4AF7-8D9C-5B2489D0AF62	Past its expected useful life and sho	EQ-1037003	green
389	UNK	PANEL LCP 71	10/27/2025	B734853F-3B15-4604-925A-FECA715FC862	Past its expected useful life and sho	EQ-1037004	green
390	UNK	PANEL LCP 81	10/26/2025	22939F79-0EE3-4C23-933F-85695B1B0F95	Past its expected useful life and sho	EQ-1037005	green
391	UNK	PANEL LCP 62	10/26/2025	7AA6414A-B286-4AAA-9CB1-F2B8E5B6BE93	Past its expected useful life and sho	EQ-1037006	green
392	UNK	PANEL LCP61	10/26/2025	DDEE8D31-B422-44B6-AEA2-1EE1FA86258D	Past its expected useful life and sho	EQ-1037007	green
393			11/08/2025	11691D3A-6AA2-4559-AD62-ACAE93FB42BA	Lightening protection needs to be replaced/updated to be more		blue
394			02/10/2026				grey
395			02/10/2026				grey
396			11/12/2025		Minor cracks were observed. Buildings constructed in the 1980s		grey
397			02/11/2026				grey
398			02/12/2026				grey
399	No dataplate		11/09/2025	124101DA-EFAA-4479-9AAB-065D0958837D		FSE-1037238	orange
400	No dataplate		11/08/2025	5A4AAE9F-0B7B-4C8D-9755-0DAA5228536F		FSE-1037240	orange
401	No dataplate		11/09/2025	D17BCF3C-9383-489F-AE9E-72E641B2AA50		FSE-1037242	orange
402	No dataplate		11/08/2025	503F0C50-A620-4CB5-8E5E-213FB6228550		FSE-1037239	orange
403	NA		11/09/2025	2D905584-C85C-4FE3-88E7-7B35926DBA7F			blue
404	D5949.6C	DHW EXPANSION TANK	11/09/2025	C2B76383-9E36-4B2C-9088-C80B2583D6F6		EQ-1027661	green
405	271912	HEATING HOT WATER TANK	10/30/2025	E4D9CFE5-0D5B-4257-AC45-8E26964C2748		EQ-1027532	green
406	272923	HOT WATER TANK 2B	10/30/2025	5101616C-A876-4E25-9772-ABF54FBC482C		EQ-1027533	green
407	272917	COLD WATER TANK 2A	10/30/2025	CDE39C7A-EDC5-45A7-A577-1170853A7629		EQ-1027534	green
408	272919	COLD HYDRO PNEUMATIC T	10/30/2025	EC525C33-15ED-49A2-BD4E-933378999923		EQ-1027535	green
409	272916	COLD HYDRO PNEUMATIC T	10/30/2025	ABE55C9D-06F9-48CC-86B1-B28BD40D5A2B		EQ-1027649	green
410	272913	HOT HYDRO PNEUMATIC TA	10/30/2025	BBED312A-770C-4C07-80A5-F4822B9003C2		EQ-1027650	green
411	272915	COLD HYDRO PNEUMATIC T	10/30/2025	007B029A-5652-48F8-A579-E7C9A4302D2B		EQ-1027652	green
412	272918	COLD HYDRO PNEUMATIC T	10/30/2025	001AF9D9-3BEC-4E6D-918F-57CEF3668ABB		EQ-1027653	green

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
413	Sacramento County Main Jail	9859483	129536	EQ-1027654	D3029	Boiler Supplemental Components	Expansion Tank, 176 to 250 GAL	250 GAL	3
414	Sacramento County Main Jail	9859842	129277	FSE-1037234	E1038	Foodservice Equipment	Convection Oven, Single		3
415	Sacramento County Main Jail	9859477	129676	FSE-1037235	E1038	Foodservice Equipment	Convection Oven, Single		3
416	Sacramento County Main Jail	9859451	129270	FSE-1037236	E1038	Foodservice Equipment	Convection Oven, Single		3
417	Sacramento County Main Jail	9859854	129626	FSE-1037237	E1038	Foodservice Equipment	Convection Oven, Single		3
418	Sacramento County Main Jail	9859630	129368	FSE-1039486	E1038	Foodservice Equipment	Convection Oven, Single		3
419	Sacramento County Main Jail	9859461	129538	FSE-1039487	E1038	Foodservice Equipment	Convection Oven, Single		3
420	Sacramento County Main Jail	9859556	129577	FSE-1039488	E1038	Foodservice Equipment	Convection Oven, Single		3
421	Sacramento County Main Jail	9859611	129418	FSE-1039489	E1038	Foodservice Equipment	Convection Oven, Single		3
422	Sacramento County Main Jail	9859482	129777	FSE-1039490	E1038	Foodservice Equipment	Convection Oven, Single		3
423	Sacramento County Main Jail	9859541	129511	FSE-1039491	E1038	Foodservice Equipment	Convection Oven, Single		3
424	Sacramento County Main Jail	9859423	129774	FSE-1039492	E1038	Foodservice Equipment	Convection Oven, Single		3
425	Sacramento County Main Jail	9859743	129515	FSE-1039493	E1038	Foodservice Equipment	Convection Oven, Single		3
426	Sacramento County Main Jail	9859845	129465	FSE-1039494	E1038	Foodservice Equipment	Convection Oven, Single		3
427	Sacramento County Main Jail	9859812	129482	FSE-1039495	E1038	Foodservice Equipment	Convection Oven, Single		3
428	Sacramento County Main Jail	9859538	129829	FSE-1029158	E1038	Foodservice Equipment	Icemaker, Freestanding		3
429	Sacramento County Main Jail	9859328	129858	FSE-1029160	E1038	Foodservice Equipment	Icemaker, Freestanding		3
430	Sacramento County Main Jail	9859666	129560	EQ-1030948	E1061	Residential Appliances	Clothes Dryer		3
431	Sacramento County Main Jail	9859572	129924	EQ-1030947	E1061	Residential Appliances	Washer		3
432	Sacramento County Main Jail	9859770	129316	EQ-1027658	D2011	Storage Tank	Domestic Water	720 GAL	3
433	Sacramento County Main Jail	9859470	129734	EQ-1027659	D2011	Storage Tank	Domestic Water	720 GAL	3
434	Sacramento County Main Jail	9859785	129622	EQ-1027660	D2011	Storage Tank	Domestic Water	720 GAL	3
435	Sacramento County Main Jail	9859714	129343	EQ-1036883	G3011	Storage Tank	Site Water, Above-Ground	250000 GAL	3
436	Sacramento County Main Jail	9996269	129825		D3029	Boiler Supplemental Components	Expansion Tank	50 GAL	3
437	Sacramento County Main Jail	9960666	130194		G2068	Bollard	Concrete or Metal		3
438	Sacramento County Main Jail	9959440	130436		E2013	Casework	Cabinetry, High-End or Laboratory		3
439	Sacramento County Main Jail	9922833	130299		C2057	Ceiling Finishes	any flat surface		3
440	Sacramento County Main Jail	9959446	130441		C2052	Ceiling Finishes	Wood Paneling		3
441	Sacramento County Main Jail	9922882	130244		E1038	Commercial Kitchen Line	Preparation Tables/Areas		3
442	Sacramento County Main Jail	9959455	129996		D2016	Drinking Fountain	Wall-Mounted, Bi-Level		3
443	Sacramento County Main Jail	9859855	129658	EQ-1028918	D2016	Drinking Fountain	Wall-Mounted, Single-Level		3
444	Sacramento County Main Jail	9859746	129917	EQ-1028919	D2016	Drinking Fountain	Wall-Mounted, Single-Level		3
445	Sacramento County Main Jail	9959443	130318		D2016	Drinking Fountain	Wall-Mounted, Single-Level		3
446	Sacramento County Main Jail	9959451	130456		D1011	Elevator Cab Finishes	High-End		3
447	Sacramento County Main Jail	9959419	130450		D1011	Elevator Cab Finishes	High-End		3
448	Sacramento County Main Jail	9959457	130451		D1011	Elevator Cab Finishes	High-End		3
449	Sacramento County Main Jail	9959458	130471		D1011	Elevator Cab Finishes	High-End		3
450	Sacramento County Main Jail	9959461	130447		D1011	Elevator Cab Finishes	High-End		3
451	Sacramento County Main Jail	9959418	130466		D1011	Elevator Cab Finishes	High-End		3
452	Sacramento County Main Jail	9959456	130465		D1011	Elevator Cab Finishes	High-End		3

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
413	Replace	09 - Ninth Floor - 09WMEC - West Mechanical Room	Good	2	Lifecycle/Renewal	2018	8	40	32	2025
414	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
415	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
416	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
417	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
418	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
419	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
420	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
421	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
422	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
423	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
424	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
425	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
426	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
427	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2024	2	10	8	2025
428	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2021	5	15	10	2025
429	Replace	B1 - Basement 1 - B1KIT - Kitchen	Good	2	Lifecycle/Renewal	2021	5	15	10	2025
430	Replace	07 - Seventh Floor - 07WINREC - 7 West Indoor Recreatio	Good	2	Lifecycle/Renewal	2023	3	15	12	2025
431	Replace	07 - Seventh Floor - 07WCLS - 7 West Classroom	Good	2	Lifecycle/Renewal	2023	3	15	12	2025
432	Replace	B1 - Basement 1 - B1BLR - Boiler	Good	2	Lifecycle/Renewal	2018	8	30	22	2025
433	Replace	B1 - Basement 1 - B1BLR - Boiler	Good	2	Lifecycle/Renewal	2018	8	30	22	2025
434	Replace	B1 - Basement 1 - B1BLR - Boiler	Good	2	Lifecycle/Renewal	2018	8	30	22	2025
435	Replace/Install	B1 - Basement 1 - B1FPMP - Fire Pump	Good	2	Lifecycle/Renewal	1988	6	30	24	2025
436	Replace	B1 - Basement 1 - B1BSTPMP - Booster Pump	Fair	3	Lifecycle/Renewal	2008	18	40	22	2025
437	Replace	S1 - Site	Fair	3	Aged But Functional		27	30	3	2025
438	Replace	All building - Throughout	Fair	3	Lifecycle/Renewal		17	20	3	2025
439	Prep & Paint	All building - Throughout	Fair	3	Aged But Functional		7	10	3	2025
440	Replace	All building - Throughout	Fair	3	Lifecycle/Renewal		28	30	2	2025
441	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		18	20	2	2025
442	Replace	Hallways & Common Areas	Fair	3	Aged But Functional		12	15	3	2025
443	Replace	B1 - Basement 1 - B1OFF - Office Space	Fair	3	Lifecycle/Renewal	2020	6	15	9	2025
444	Replace	02 - Second Floor - 02CST - 02cst	Fair	3	Lifecycle/Renewal	2020	6	15	9	2025
445	Replace	All building - Throughout	Fair	3	Aged But Functional		13	15	2	2025
446	Replace	All Building - Secure Elevator	Fair	3	Aged But Functional		18	20	2	2025
447	Replace	All Building - Secure Elevator	Fair	3	Aged But Functional		18	20	2	2025
448	Replace	All Building - Secure Elevator	Fair	3	Aged But Functional		18	20	2	2025
449	Replace	All building - Court Elevator	Fair	3	Lifecycle/Renewal	1989	18	20	2	2025
450	Replace	All Building - Freight Elevator	Fair	3	Aged But Functional		18	20	2	2025
451	Replace	All building - Lobby Elevator	Fair	3	Aged But Functional		18	20	2	2025
452	Replace	All building - Lobby Elevator	Fair	3	Aged But Functional		18	20	2	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
413	1	5200	EA	0		1.138	31	$ 7,752.06	Wessels	FXA-700
414	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
415	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
416	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
417	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
418	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
419	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
420	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
421	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
422	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
423	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
424	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
425	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
426	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
427	1	5600	EA	0		1.138	31	$ 8,348.37	Vulcan	No dataplate
428	1	6700	EA	0		1.138	31	$ 9,988.23	Vogt	
429	1	6700	EA	0		1.138	31	$ 9,988.23	Vogt	
430	1	650	EA	0		1.138	31	$ 969.01	G.E.	GTD33EASK0WW
431	1	850	EA	0		1.138	31	$ 1,267.16	G.E.	GTW335ASN2WW
432	1	6000	EA	0		1.138	31	$ 8,944.68	NST Niles Steel Tank	720 Gal
433	1	6000	EA	0		1.138	31	$ 8,944.68	NST Niles Steel Tank	720 Gal
434	1	6000	EA	0		1.138	31	$ 8,944.68	NST Niles Steel Tank	720 Gal
435	2	250000	EA	0		1.138	31	$ 745,390.00		
436	1	2700	EA	0		1.138	31	$ 4,025.11	No dataplate	No dataplate
437	10	1000	EA	0		1.138	31	$ 14,907.80		
438	80	500	LF	0		1.138	31	$ 59,631.20		
439	95000	2	SF	0		1.138	31	$ 283,248.20		
440	98200	14	SF	0		1.138	31	$ 2,049,524.34		
441	200	300	LF	0		1.138	31	$ 89,446.80		
442	5	1500	EA	0		1.138	31	$ 11,180.85		
443	1	1200	EA	0		1.138	31	$ 1,788.94	Elkay	LZWSR_1D
444	1	1200	EA	0		1.138	31	$ 1,788.94	Elkay	LZWSR_1D
445	5	1200	EA	0		1.138	31	$ 8,944.68		
446	1	16000	EA	0		1.138	31	$ 23,852.48	No dataplate	No dataplate
447	1	16000	EA	0		1.138	31	$ 23,852.48	No dataplate	No dataplate
448	1	16000	EA	0		1.138	31	$ 23,852.48	No dataplate	No dataplate
449	1	16000	EA	0		1.138	31	$ 23,852.48	No dataplate	No dataplate
450	1	16000	EA	0		1.138	31	$ 23,852.48	No dataplate	No dataplate
451	1	16000	EA	0		1.138	31	$ 23,852.48	No dataplate	No dataplate
452	1	16000	EA	0		1.138	31	$ 23,852.48	No dataplate	No dataplate

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
413	272921	COLD HYDRO PNEUMATIC T	10/30/2025	98D559F7-D4BC-4C47-9274-FEB3394F0439		EQ-1027654	green
414	No dataplate		11/09/2025	1CE85961-1C83-4762-AB99-CB4E61D24153		FSE-1037234	orange
415	No dataplate		11/09/2025	F2390C61-3679-44A9-AE3C-0821F6ADE2A2		FSE-1037235	orange
416	No dataplate		11/09/2025	95C38ACE-06CD-494D-ACE6-78254155E240		FSE-1037236	orange
417	No dataplate		11/09/2025	D8095327-4337-4958-96D9-1632C87A324A		FSE-1037237	orange
418	No dataplate		11/09/2025	5D0D66A5-13AB-4467-AD41-5C37C7D4C7DA		FSE-1039486	orange
419	No dataplate		11/09/2025	7204BECD-798C-4071-BD1A-C0B9C2100119		FSE-1039487	orange
420	No dataplate		11/09/2025	75522070-A509-47A6-9AF6-B72BF3B9349F		FSE-1039488	orange
421	No dataplate		11/09/2025	B3D9D0F6-E00B-4CEA-9495-94B94007CC2B		FSE-1039489	orange
422	No dataplate		11/09/2025	B1FE8419-E1EB-4550-8E2B-942E21E341EA		FSE-1039490	orange
423	No dataplate		11/09/2025	0911645B-BA03-4C9B-BEA4-7A00E6740CDB		FSE-1039491	orange
424	No dataplate		11/09/2025	8E0BE10B-C192-4647-8F7E-A0F98AB75930		FSE-1039492	orange
425	No dataplate		11/09/2025	7C630CF4-DC0E-4ADC-A25D-6B08C072C65B		FSE-1039493	orange
426	No dataplate		11/09/2025	E9672AA9-734E-454E-9453-86837580EBD4		FSE-1039494	orange
427	No dataplate		11/09/2025	AAC0953D-30E4-4850-9C55-53A9603E3B88		FSE-1039495	orange
428			10/30/2025	0D2040A6-EC06-4658-8E81-804C44C41FB0		FSE-1029158	green
429			10/30/2025	CA857656-7791-4C48-9558-E3F3D0C16B74		FSE-1029160	green
430	LV559299C	7W DRYER	10/30/2025	793DEE72-0501-4E32-83BE-6C686FC0D0E8		EQ-1030948	green
431	VV115066G	7W WASHING MACHINE	10/30/2025	D842B8E0-E4FE-4C7F-BD1F-E4267F5C4CBD		EQ-1030947	green
432	105681-02	HW STORAGE TANK 2, LAUN	11/09/2025	05758701-276B-4F04-979D-E53F7002FE01		EQ-1027658	green
433	105681-03	HOT WATER TANK 3	11/09/2025	11D71E7C-F079-4000-A959-BB0983DA6AC2		EQ-1027659	green
434	105681-04	HOT WATERR STORAGE TAN	11/09/2025	1BC0A200-47E6-4C6D-9A82-0D18B12CB79D		EQ-1027660	green
435		WATER TANKS	11/09/2025	655453DD-5384-4E1D-9C65-6BC632320F9F		EQ-1036883	orange
436	No dataplate		11/09/2025	E1D4ABD5-62E4-4617-B2FD-EF299C5D0A08			blue
437			10/30/2025	64FEF76A-DB7D-46CE-9810-B0F44FA513B6			blue
438			10/30/2025	1E17B693-F397-452A-887F-CFE17C5F2A0A			blue
439			10/30/2025	F0293718-820E-4FA0-A3ED-DB2F27570CF8			blue
440			10/30/2025	F58CE999-AC1E-49D9-909C-42E9CAD2FA57			blue
441			10/30/2025	560345E5-4424-43BF-A447-5FEC7F239A19			blue
442			10/30/2025	0B7F99FD-F9DD-4FB1-8EA0-CAFD7792F52D			blue
443	200117677	SHOP DRINKING FOUNTAIN	11/09/2025	1422D6F2-BC54-441C-9FB1-C4785C015DC7		EQ-1028918	green
444	201006651	2ND FLOOR DRINKING FOUN	10/30/2025	9136147C-5A9D-4530-9E7D-C39F25B12E00		EQ-1028919	green
445			10/30/2025	4B5DDDCD-6273-4566-9F1A-A28E577B5643			blue
446	No dataplate		10/30/2025	627A524A-D1A1-4632-8DF7-FC95F74AA98E			blue
447	No dataplate	D	10/30/2025	FE28C602-49A6-4BC6-A9C2-4BAFC0EE3F81			blue
448	No dataplate		10/30/2025	6E3BADFC-878D-4212-9546-9E38AAE746BA			blue
449	No dataplate		10/30/2025	E7DE6073-4157-4B2D-A58C-678D82CE52D7			blue
450	No dataplate		10/30/2025	A589F617-5FC1-4083-8C5E-0C332A77DCCF			blue
451	No dataplate		10/30/2025	9CAC7DFA-6DD5-4848-8B68-45708435A55A			blue
452	No dataplate		10/30/2025	392B12BA-95FE-4266-96DB-5F83ED38A13F			blue

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
453	Sacramento County Main Jail	9959432	130452		D1011	Elevator Cab Finishes	High-End		3
454	Sacramento County Main Jail	9996271	129906		D1011	Elevator Controls	Automatic, 1 Car		3
455	Sacramento County Main Jail	9959427	130446		D1011	Elevator Controls	Automatic, 1 Car		3
456	Sacramento County Main Jail	9996289	129904		D1011	Elevator Controls	Automatic, 1 Car		3
457	Sacramento County Main Jail	9996254	129903		D1011	Elevator Controls	Automatic, 1 Car		3
458	Sacramento County Main Jail	9996274	129905		D1011	Elevator Controls	Automatic, 1 Car		3
459	Sacramento County Main Jail	9959438	130472		D1011	Elevator Controls	Automatic, 2 Car Cluster		3
460	Sacramento County Main Jail	9959428	130468		D1011	Elevator Controls	Automatic, 3 Car Cluster		3
461	Sacramento County Main Jail	9960665	130195		G2063	Flagpole	Metal		3
462	Sacramento County Main Jail	9922878	129987		C2031	Flooring	any surface, w/ Paint or Sealant		3
463	Sacramento County Main Jail	9922861	129985		C2037	Flooring	Carpet, Commercial Standard		3
464	Sacramento County Main Jail	9922835	130263		C2032	Flooring	Ceramic Tile		3
465	Sacramento County Main Jail	9859533	129575	EQ-1040914	E1038	Foodservice Equipment	Dishwasher Commercial		3
466	Sacramento County Main Jail	9859331	129264	EQ-1037031	E1038	Foodservice Equipment	Exhaust Hood, 8 to 10 LF		3
467	Sacramento County Main Jail	9859838	129726	EQ-1037032	E1038	Foodservice Equipment	Exhaust Hood, 8 to 10 LF		3
468	Sacramento County Main Jail	9859778	129366	FSE-1037385	E1038	Foodservice Equipment	Mixer, Freestanding		3
469	Sacramento County Main Jail	9859660	129510	FSE-1041197	E1038	Foodservice Equipment	Mixer, Freestanding		3
470	Sacramento County Main Jail	9859721	129747	FSE-1041785	E1038	Foodservice Equipment	Mixer, Freestanding		3
471	Sacramento County Main Jail	9859792	129857	FSE-1037271	E1038	Foodservice Equipment	Steam Kettle		3
472	Sacramento County Main Jail	9859388	129818	FSE-1037272	E1038	Foodservice Equipment	Steam Kettle		3
473	Sacramento County Main Jail	9859671	129802	FSE-1039485	E1038	Foodservice Equipment	Steam Kettle		3
474	Sacramento County Main Jail	9859536	129821	FSE-1039496	E1038	Foodservice Equipment	Steamer, Tabletop		3
475	Sacramento County Main Jail	9996287	129837		E1038	Foodservice Equipment	Walk-In, Condenser for Refrigerator/Freezer	15 TON	3
476	Sacramento County Main Jail	9922877	130232		E1038	Foodservice Equipment	Walk-In, Evaporator for Refigerator/Freezer		3
477	Sacramento County Main Jail	9922848	130239		E1038	Foodservice Equipment	Walk-In, Evaporator for Refigerator/Freezer		3
478	Sacramento County Main Jail	9922854	130237		E1038	Foodservice Equipment	Walk-In, Evaporator for Refigerator/Freezer		3
479	Sacramento County Main Jail	9922864	130231		E1038	Foodservice Equipment	Walk-In, Evaporator for Refigerator/Freezer		3
480	Sacramento County Main Jail	9922842	130241		E1038	Foodservice Equipment	Walk-In, Evaporator for Refigerator/Freezer		3
481	Sacramento County Main Jail	9922822	130243		E1038	Foodservice Equipment	Walk-In, Evaporator for Refigerator/Freezer		3
482	Sacramento County Main Jail	9922853	130230		E1038	Foodservice Equipment	Walk-In, Freezer	2400 CFM	3
483	Sacramento County Main Jail	9922811	130236		E1038	Foodservice Equipment	Walk-In, Freezer	2300 CFM	3
484	Sacramento County Main Jail	9922831	130238		E1038	Foodservice Equipment	Walk-In, Freezer	2000 CFM	3
485	Sacramento County Main Jail	9922814	130240		E1038	Foodservice Equipment	Walk-In, Freezer	2000 CFM	3
486	Sacramento County Main Jail	9922852	130242		E1038	Foodservice Equipment	Walk-In, Freezer	2000 CFM	3
487	Sacramento County Main Jail	9922881	129981		B2022	Glazing	any type by SF		3

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
453	Replace	All Building - Secure Elevator	Fair	3	Aged But Functional		18	20	2	2025
454	Replace	09 - Ninth Floor - Secure Elevator Control Room	Fair	3	Lifecycle/Renewal		17	20	3	2025
455	Replace	All Building - Freight Elevator	Fair	3	Aged But Functional		18	20	2	2025
456	Replace	09 - Ninth Floor - Secure Elevator Control Room	Fair	3	Lifecycle/Renewal		17	20	3	2025
457	Replace	09 - Ninth Floor - Secure Elevator Control Room	Fair	3	Lifecycle/Renewal		17	20	3	2025
458	Replace	09 - Ninth Floor - Secure Elevator Control Room	Fair	3	Lifecycle/Renewal		17	20	3	2025
459	Replace	All building - Court Elevator	Fair	3	Aged But Functional	1989	18	20	2	2025
460	Replace	All building - Lobby Elevator	Fair	3	Aged But Functional		18	20	2	2025
461	Replace	S1 - Site	Fair	3	Aged But Functional		28	30	2	2025
462	Prep & Paint	All building - Throughout	Fair	3	Aged But Functional		8	10	2	2025
463	Replace	All building - Throughout	Fair	3	Aged But Functional		8	10	2	2025
464	Replace	01 - First Floor - Office	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
465	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional	2007	8	10	2	2025
466	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Lifecycle/Renewal	1988	9	15	6	2025
467	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Lifecycle/Renewal	1988	9	15	6	2025
468	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Lifecycle/Renewal	1900	15	25	10	2025
469	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Lifecycle/Renewal	2013	13	25	12	2025
470	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Lifecycle/Renewal	2014	12	25	13	2025
471	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional	1988	18	20	2	2025
472	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional	1988	18	20	2	2025
473	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional	2002	18	20	2	2025
474	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional	2002	8	10	2	2025
475	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional		11	15	4	2025
476	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		13	15	2	2025
477	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		13	15	2	2025
478	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		12	15	3	2025
479	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		13	15	2	2025
480	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		13	15	2	2025
481	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		13	15	2	2025
482	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		17	20	3	2025
483	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		18	20	2	2025
484	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		18	20	2	2025
485	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		18	20	2	2025
486	Replace	B1 - Basement 1 - B1KIT - Kitchen	Fair	3	Aged But Functional		16	20	4	2025
487	Replace	Building Exterior	Fair	3	Aged But Functional		27	30	3	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
453	1	16000	EA	0		1.138	31	$ 23,852.48	No dataplate	No dataplate
454	1	5000	EA	0		1.138	31	$ 7,453.90	No dataplate	No dataplate
455	1	5000	EA	0		1.138	31	$ 7,453.90	NA	HYDR0
456	1	5000	EA	0		1.138	31	$ 7,453.90	No dataplate	No dataplate
457	1	5000	EA	0		1.138	31	$ 7,453.90	No dataplate	No dataplate
458	1	5000	EA	0		1.138	31	$ 7,453.90	No dataplate	No dataplate
459	1	7500	EA	0		1.138	31	$ 11,180.85	No dataplate	No dataplate
460	1	12000	EA	0		1.138	31	$ 17,889.36	No dataplate	No dataplate
461	2	2500	EA	0		1.138	31	$ 7,453.90		
462	425000	1.5	SF	0		1.138	31	$ 950,372.25		
463	49100	7.5	SF	0		1.138	31	$ 548,979.74		
464	24600	18	SF	0		1.138	31	$ 660,117.38		
465	1	21500	EA	0		1.138	31	$ 32,051.77	Stero Co.	STPCW-20
466	3	4500	EA	0		1.138	31	$ 20,125.53	No dataplate	No dataplate
467	3	4500	EA	0		1.138	31	$ 20,125.53	No dataplate	No dataplate
468	1	14000	EA	0		1.138	31	$ 20,870.92	Stephan	NA
469	1	14000	EA	0		1.138	31	$ 20,870.92	Univex	No dataplate
470	1	14000	EA	0		1.138	31	$ 20,870.92	Univex	No dataplate
471	1	30000	EA	0		1.138	31	$ 44,723.40	Groen	
472	1	30000	EA	0		1.138	31	$ 44,723.40	Groen	
473	1	30000	EA	0		1.138	31	$ 44,723.40	Groen	
474	1	7000	EA	0		1.138	31	$ 10,435.46	Cleveland	
475	1	6300	EA	300	15 ton	1.138	31	$ 30,900.11	No dataplate	No dataplate
476	1	4600	EA	0		1.138	31	$ 6,857.59	No dataplate	No dataplate
477	1	4600	EA	0		1.138	31	$ 6,857.59	Larkin	No dataplate
478	1	4600	EA	0		1.138	31	$ 6,857.59	BOHN	No dataplate
479	1	4600	EA	0		1.138	31	$ 6,857.59	No dataplate	No dataplate
480	1	4600	EA	0		1.138	31	$ 6,857.59	BOHN	No dataplate
481	1	4600	EA	0		1.138	31	$ 6,857.59	No dataplate	No dataplate
482	1	25000	EA	0		1.138	31	$ 37,269.50	No dataplate	No dataplate
483	1	25000	EA	0		1.138	31	$ 37,269.50	No dataplate	No dataplate
484	1	25000	EA	0		1.138	31	$ 37,269.50	No dataplate	No dataplate
485	1	25000	EA	0		1.138	31	$ 37,269.50	No dataplate	No dataplate
486	1	25000	EA	0		1.138	31	$ 37,269.50	No dataplate	No dataplate
487	6500	55	SF	0		1.138	31	$ 532,953.85		

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
453	No dataplate		10/30/2025	E498F174-B981-488B-B57D-236DE2E00E10			blue
454	No dataplate	D	11/09/2025	BD907405-EF30-4D03-889E-8891B2F62DCE			blue
455	7279# FRT		10/30/2025	D2BE21D2-411F-421C-9C73-7A072955DAF9			blue
456	No dataplate	B	11/09/2025	C4344411-4634-4AF7-B07B-CFC56E36E1F4			blue
457	No dataplate	A	11/09/2025	06437D11-3864-4A3A-8A9A-9BA4D84F78DB			blue
458	No dataplate	C	11/09/2025	2EDC969E-5B39-4E2A-924F-3B40D122EA5C			blue
459	No dataplate		10/30/2025	BB761CE4-091D-462A-99B0-046D742DD15C			blue
460	No dataplate		10/30/2025	0135AF0A-9A59-4A67-938B-203AA99ACB0A			blue
461			10/30/2025	89EC05FE-0A01-41F0-A636-F9045A17E048			blue
462			10/30/2025	F306A7B0-D3AD-4BC4-B0F5-9AE4C28634F1			blue
463			10/30/2025	E813153F-0266-4027-8BAC-E0E510A1F746			blue
464			10/30/2025	233E1038-9A6E-491E-A9E4-30F4C293156B			blue
465	75068-7-07	FLIGHTWASH	10/30/2025	1D64A39D-BA6B-4785-BCE3-CB688C748888		EQ-1040914	green
466	No dataplate	EXHAUST HOOD	11/09/2025	978FE68E-73BD-4B15-B818-0BB240D3B0FF		EQ-1037031	green
467	No dataplate	EXHAUST HOOD	11/09/2025	658D0A00-C03F-4D63-8E51-47A353A630FA		EQ-1037032	green
468	NA		11/09/2025	894004F8-9D12-48D6-8B0A-53BE2AFFBA32		FSE-1037385	orange
469	No dataplate		11/09/2025	83A25032-324E-4217-A1AC-40880AA77CE6		FSE-1041197	green
470	No dataplate		11/09/2025	94336977-90F6-46D9-928E-C8FC68F9F00E		FSE-1041785	green
471			10/30/2025	5F7E94DB-18B6-427F-B54D-674FA5489758		FSE-1037271	green
472			10/30/2025	3167BD6D-D9F3-42F4-9EEC-79EC2B6E77FF		FSE-1037272	green
473			10/30/2025	7D20B741-2430-41EB-B22E-341C70D08026		FSE-1039485	green
474			10/30/2025	5EA9B874-2204-4727-9019-39F759CF745F		FSE-1039496	green
475	No dataplate		11/09/2025	092D73A9-A0EE-4EEB-834C-E7D7380673AB	7 small ones make this large one.		blue
476	No dataplate		10/30/2025	1890EFD5-A72C-42C9-BCDC-B0BA40722581			blue
477	No dataplate		10/30/2025	1175D7CD-F099-40BE-BA6A-878D2A7515CE			blue
478	No dataplate		10/30/2025	EFBEBB66-0410-4224-AA3B-A38516BB0D9B			blue
479	No dataplate		10/30/2025	4EF8643A-1EBB-422B-9E23-D0B9619B50D4			blue
480	No dataplate		10/30/2025	8770472C-9E6F-454B-92C3-6B5A0235AEDE			blue
481	No dataplate		10/30/2025	B2C2B5F2-F91C-4144-89E0-23B9C72B1A98			blue
482	No dataplate		10/30/2025	DB2E8A91-C989-4557-A5B1-8427C89F4EF1			blue
483	No dataplate		10/30/2025	3B929F5A-61A5-4F28-AF0A-DC28BD6ABE50			blue
484	No dataplate		10/30/2025	9DF28259-6411-4BF3-B378-53FF2F0B4E19			blue
485	No dataplate		10/30/2025	8453CCBA-9C02-44BC-826A-62C5B0BC61B9			blue
486	No dataplate		10/30/2025	0A9F826D-E515-4AD4-A38B-FEB4C3ABF4F6			blue
487			10/30/2025	DF57C82F-7B74-47BC-8DB2-6E290B045BBB			blue

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
488	Sacramento County Main Jail	9859395	129498	EQ-1034722	D2021	Grease Trap/Interceptor	Grease Trap/Interceptor, Underground		3
489	Sacramento County Main Jail	9960675	130187		G2081	Irrigation System	Controllers & Valves, Repairs & Adjustments		3
490	Sacramento County Main Jail	10000530	130187		G2081	Irrigation System	Pop-Up Spray Heads, Commercial		3
491	Sacramento County Main Jail	9859688	129956	EQ-1042303	E1033	Laundry Equipment	Dryer, Commercial	200 LB	3
492	Sacramento County Main Jail	9859531	129439	EQ-1042305	E1033	Laundry Equipment	Dryer, Commercial, 101 to 200 LB	200 LB	3
493	Sacramento County Main Jail	9859579	129826	EQ-1042304	E1033	Laundry Equipment	Dryer, Commercial, 51 to 75 LB		3
494	Sacramento County Main Jail	9996295	129806		E1033	Laundry Equipment	Linen Press, Commercial	6000 CFM	3
495	Sacramento County Main Jail	9996283	129804		E1033	Laundry Equipment	Linen Press, Commercial	6000 CFM	3
496	Sacramento County Main Jail	9859768	129481	EQ-1042306	E1033	Laundry Equipment	Washer, Commercial	80 LB	3
497	Sacramento County Main Jail	9859819	129669	EQ-1042307	E1033	Laundry Equipment	Washer, Commercial	80 LB	3
498	Sacramento County Main Jail	9859359	129509	EQ-1042311	E1033	Laundry Equipment	Washer, Commercial	80 LB	3
499	Sacramento County Main Jail	9922845	130286		B2053	Overhead/Dock Door	Steel, 12'x12' (144 SF)		2
500	Sacramento County Main Jail	9959442	130297		B2053	Overhead/Dock Door	Steel, 12'x12' (144 SF)		2
501	Sacramento County Main Jail	9960673	130192		G2021	Parking Lots	Pavement, Asphalt		3
502	Sacramento County Main Jail	9960667	130191		G2021	Parking Lots	Pavement, Asphalt		3
503	Sacramento County Main Jail	9959449	130473		D1011	Passenger Elevator	Hydraulic, 9 Floors, 3000 to 4000 LB	4000 LB	3
504	Sacramento County Main Jail	9959434	130473		D1011	Passenger Elevator	Hydraulic, 9 Floors, 3000 to 4000 LB	4000 LB	3
505	Sacramento County Main Jail	9959447	130473		D1011	Passenger Elevator	Hydraulic, 9 Floors, 3000 to 4000 LB	4000 LB	3
506	Sacramento County Main Jail	9996275	129910		D1011	Passenger Elevator	Overhead Traction	4500 LB	3
507	Sacramento County Main Jail	9959452	130470		D1011	Passenger Elevator	Overhead Traction, 6-15 Floors	2500 LB	3
508	Sacramento County Main Jail	9959417	130469		D1011	Passenger Elevator	Overhead Traction, 6-15 Floors	2500 LB	3
509	Sacramento County Main Jail	9996261	129908		D1011	Passenger Elevator	Overhead Traction, 6-15 Floors, 2000 to 5000 LB	4500 LB	3
510	Sacramento County Main Jail	9996272	129909		D1011	Passenger Elevator	Overhead Traction, 6-15 Floors, 2000 to 5000 LB	4500 LB	3
511	Sacramento County Main Jail	9996255	129907		D1011	Passenger Elevator	Overhead Traction, 6-15 Floors, 2000 to 5000 LB	4500 LB	3
512	Sacramento County Main Jail	9960672	130310		G2066	Retaining Wall	Concrete Cast-in-Place		3
513	Sacramento County Main Jail	9927108	130388		G2031	Roof Pavers	Composite Pavers		3
514	Sacramento County Main Jail	9859814	129654	EQ-1027655	D2011	Storage Tank	Domestic Water	1000 GAL	3
515	Sacramento County Main Jail	9859522	129585	EQ-1042126	D2011	Storage Tank	Domestic Water	720 GAL	3
516	Sacramento County Main Jail	9859601	129476	EQ-1037101	D3015	Storage Tank	Fuel, 276 to 500 GAL	500 GAL	3
517	Sacramento County Main Jail	9859704	129489	EQ-1037102	D3015	Storage Tank	Fuel, 66 to 100 GAL	75 GAL	3
518	Sacramento County Main Jail	9859798	129456	EQ-1037103	D3015	Storage Tank	Fuel, 66 to 100 GAL	75 GAL	3
519	Sacramento County Main Jail	9859377	129503	EQ-1037100	D3015	Storage Tank	Fuel, Interior	10000 GAL	3

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
488	Replace	S1 - Site	Fair	3	Aged But Functional	1989	18	20	2	2025
489	Repair	S1 - Site	Fair	3	Aged But Functional		8	10	2	2025
490	Replace/Install	S1 - Site	Fair	3	Aged But Functional		18	20	2	2025
491	Replace	B1 - Basement 1 - B1LN - Laundry	Fair	3	Aged But Functional		12	15	3	2025
492	Replace	B1 - Basement 1 - B1LN - Laundry	Fair	3	Lifecycle/Renewal	2018	8	15	7	2025
493	Replace	B1 - Basement 1 - B1LN - Laundry	Fair	3	Lifecycle/Renewal	2018	8	15	7	2025
494	Replace	B1 - Basement 1 - B1LN - Laundry	Fair	3	Lifecycle/Renewal		9	15	6	2025
495	Replace	B1 - Basement 1 - B1LN - Laundry	Fair	3	Lifecycle/Renewal		9	15	6	2025
496	Replace	B1 - Basement 1 - B1LN - Laundry	Fair	3	Lifecycle/Renewal	2022	4	10	6	2025
497	Replace	B1 - Basement 1 - B1LN - Laundry	Fair	3	Lifecycle/Renewal	2022	4	10	6	2025
498	Replace	B1 - Basement 1 - B1LN - Laundry	Fair	3	Lifecycle/Renewal	2022	4	10	6	2025
499	Replace	01 - First Floor - 01CC - Central Control	Fair	3	Aged But Functional		27	30	3	2025
500	Replace	01 - First Floor - 01CC - Central Control	Fair	3	Aged But Functional		27	30	3	2025
501	Seal & Stripe	S1 - Site	Fair	3	Aged But Functional		3	5	2	2025
502	Mill & Overlay	S1 - Site	Fair	3	Aged But Functional		21	25	4	2025
503	Renovate	All building - Court Elevator	Fair	3	Aged But Functional	1989	27	30	3	2025
504	Renovate	All building - Court Elevator	Fair	3	Aged But Functional	1989	27	30	3	2025
505	Renovate	All building - Court Elevator	Fair	3	Aged But Functional	1989	27	30	3	2025
506	Renovate	09 - Ninth Floor - Secure Elevator Control Room	Fair	3	Lifecycle/Renewal	1989	32	35	3	2025
507	Reconfigure	Lobby to Accessible Corridor	Fair	3	Retrofit/Adaptation	1989	35	35	0	2025
508	Reconfigure	Lobby to Accessible Corridor	Fair	3	Retrofit/Adaptation	1989	35	35	0	2025
509	Renovate	09 - Ninth Floor - Secure Elevator Control Room	Fair	3	Aged But Functional	1989	32	35	3	2025
510	Renovate	09 - Ninth Floor - Secure Elevator Control Room	Fair	3	Aged But Functional	1989	32	35	3	2025
511	Renovate	09 - Ninth Floor - Secure Elevator Control Room	Fair	3	Aged But Functional	1989	32	35	3	2025
512	Replace	S1 - Site	Fair	3	Lifecycle/Renewal	1989	37	50	13	2025
513	Replace	Roof Level - Throughout	Fair	3	Lifecycle/Renewal		21	30	9	2025
514	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2014	12	30	18	2025
515	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2015	11	30	19	2025
516	Replace	B1 - Basement 1 - B1FPMP - Fire Pump	Fair	3	Aged But Functional	1989	23	25	2	2025
517	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	23	25	2	2025
518	Replace	01 - First Floor - Generator Room	Fair	3	Aged But Functional	1989	23	25	2	2025
519	Replace	S1 - Site	Fair	3	Aged But Functional	1988	23	25	2	2025

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
488	1	12000	EA	0		1.138	31	$ 17,889.36	No dataplate	No dataplate
489	4000	0.4	SF	0		1.138	31	$ 2,385.25		
490	4000	1	SF	0		1.138	31	$ 5,963.12		
491	1	7800	EA	0		1.138	31	$ 11,628.08	Milnor	MLG 310
492	1	7800	EA	0		1.138	31	$ 11,628.08	Milnor	M170
493	1	4900	EA	0		1.138	31	$ 7,304.82	Milnor	MLG 310
494	1	12000	EA	0		1.138	31	$ 17,889.36	No dataplate	No dataplate
495	1	12000	EA	0		1.138	31	$ 17,889.36	No dataplate	No dataplate
496	1	12000	EA	0		1.138	31	$ 17,889.36	Milnor	MWF125J7
497	1	12000	EA	0		1.138	31	$ 17,889.36	Milnor	MWF77J7
498	1	12000	EA	0		1.138	31	$ 17,889.36	Milnor	MWF125J7
499	1	3200	EA	0		1.138	31	$ 4,770.50		
500	1	3200	EA	0		1.138	31	$ 4,770.50		
501	33000	0.45	SF	0		1.138	31	$ 22,138.08		
502	33000	3.5	SF	0		1.138	31	$ 172,185.09		
503	1	120000	EA	0		1.138	31	$ 178,893.60	ThyssenKrupp	No dataplate
504	1	120000	EA	0		1.138	31	$ 178,893.60	ThyssenKrupp	No dataplate
505	1	120000	EA	0		1.138	31	$ 178,893.60	ThyssenKrupp	No dataplate
506	1	320000	EA	0		1.138	31	$ 477,049.60	Armor	MR 35
507	1	320000	EA	0		1.138	31	$ 477,049.60	No dataplate	No dataplate
508	1	320000	EA	0		1.138	31	$ 477,049.60	No dataplate	No dataplate
509	1	320000	EA	0		1.138	31	$ 477,049.60	Armor	MR 35
510	1	320000	EA	0		1.138	31	$ 477,049.60	Armor	MR 35
511	1	320000	EA	0		1.138	31	$ 477,049.60	Armor	MR 35
512	400	130	SF	0		1.138	31	$ 77,520.56		
513	10000	33	SF	0		1.138	31	$ 491,957.40		
514	1	6000	EA	0		1.138	31	$ 8,944.68	Bryan	LDTV 15-5-1-2
515	1	6000	EA	0		1.138	31	$ 8,944.68	NST Niles Steel Tank	National Board 101035
516	1	5500	EA	0		1.138	31	$ 8,199.29	Simplex	
517	1	1300	EA	0		1.138	31	$ 1,938.01	Simplex	
518	1	1300	EA	0		1.138	31	$ 1,938.01	Simplex	
519	1	35000	EA	0		1.138	31	$ 52,177.30	Fiberglass	No dataplate

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
488	No dataplate	GREASE INTERCEPTOR	11/09/2025	D4FC55B2-254B-4193-88C3-1F5386A2F3A2		EQ-1034722	green
489			10/29/2025	2693B5E0-0D68-4F6E-804D-6BE07CB271D8			blue
490			10/29/2025				blue
491	MCC1701638	DRYER #2	10/30/2025	2C3EC446-E22E-4B91-A734-6B03237D82F0		EQ-1042303	green
492	MCB 5207701	DRYER #3	10/30/2025	58CA2944-7A73-4C4A-A5DF-D1912C93CB93		EQ-1042305	green
493	MCC1701639	DRYER #1	10/30/2025	B4DAFCFA-6BC8-4F62-98A9-406DBF88E23E		EQ-1042304	green
494	No dataplate		11/09/2025	A1FCDFD7-A109-4B05-99B3-1B038531BDD5		No lint extractor in our cost	blue
495	No dataplate		11/09/2025	6828545A-7441-4C0D-A85C-9F8C8779805E		No lint extractor in our cost	blue
496	AZB/2220554809	WASHER #1	11/09/2025	8B2793A7-3343-46FE-BA4F-B6C794B3FC79		EQ-1042306	orange
497	AZC/2220554811	WASHER #3	11/09/2025	79DE6AF3-B64F-4682-BA21-5870057BFAA0		EQ-1042307	orange
498	AZB/2220554810	WASHER #2	11/09/2025	ABF4767A-1B9D-4533-A4B8-717AD98382F3		EQ-1042311	orange
499			10/29/2025	13F6440D-4622-47E9-A943-6ADAE83C59B6			blue
500			10/30/2025	97C59134-9B37-4152-AE0A-8AD2C3B9D475			blue
501			10/29/2025	9F117A46-C3ED-407A-AC6D-8A43DF895846			blue
502			10/30/2025	D8DD2888-D7E4-4BCA-9CEB-8D6B5E7B76FF			blue
503	No dataplate		10/29/2025	296C72EB-9F2B-4CCF-8BBD-0FB1B50BE6BD			blue
504	No dataplate		10/28/2025	296C72EB-9F2B-4CCF-8BBD-0FB1B50BE6BD			blue
505	No dataplate		10/29/2025	296C72EB-9F2B-4CCF-8BBD-0FB1B50BE6BD			blue
506	858002	D	11/02/2025	D1D32348-A1D2-47C9-A047-62F2FA6E4386			blue
507	No dataplate		10/28/2025	4A5E6AC3-2D57-48C7-B227-7EB10D2810D4			blue
508	No dataplate		10/25/2025	94803A68-FFEA-4549-BF3F-57C4B8DC937B			blue
509	858001	B	11/09/2025	F93CDBDE-B866-4F15-8025-7BC890DA77BF			blue
510	858004	C	11/09/2025	058E7092-35D5-496F-85A2-20FBF58BEA11			blue
511	858003	A	11/09/2025	366AF1DF-D00A-478F-87CC-B5E91884244B			blue
512			10/30/2025	A590DBF7-6789-4A73-80B6-5F94024E6AB5			blue
513			10/29/2025	9D2420BA-C4CC-4F55-AB61-38B18A44574A	Location roof		blue
514	100249	DA TANK	11/09/2025	FD797605-9911-497E-A572-29A90158DF1B		EQ-1027655	orange
515	105681-01	HWH TANK 1	11/09/2025	D77D3A92-7856-4BE5-A590-A8EC97DC2CDE		EQ-1042126	green
516	UNK	FIRE PUMP DAY TANK	10/30/2025	73F1BBF7-74F0-4A11-A2D5-678B0B1466AD		EQ-1037101	green
517	UNK	DAY TANK # 1	10/30/2025	7F7AF334-6078-414C-A98A-1CBF6C034F56		EQ-1037102	green
518	UNK	DAY TANK # 2	10/30/2025	58C2ABD0-78EE-4306-B3D0-8616A7C2E95D		EQ-1037103	green
519	No dataplate	FUEL STORAGE TANK	11/09/2025	9EE62B18-2162-4BB8-9130-B1A90B5EFE57		EQ-1037100	green

No.	Location Name	Observation Id	Alternate Id	County ID	Uniformat Code	Component Description	Attributes	Capacity	Criticality
520	Sacramento County Main Jail	9859504	129379	EQ-1038689	D2061	Supplemental Components	Air Receiver Tank, Process Support, 120 GAL	120 GAL	3
521	Sacramento County Main Jail	9859457	129417	EQ-1038691	D2061	Supplemental Components	Air Receiver Tank, Process Support, 120 GAL	120 GAL	3
522	Sacramento County Main Jail	9859701	129800	EQ-1039182	D2061	Supplemental Components	Compressed Air Dryer, Process Support	100 CFM	3
523	Sacramento County Main Jail	9922856	129989		C1071	Suspended Ceilings	Acoustical Tile (ACT)		3
524	Sacramento County Main Jail	9922846	130200		D2016	Toilet	Commercial Water Closet		3
525	Sacramento County Main Jail	9959463	130444		C1094	Toilet Partitions	Metal		3
526	Sacramento County Main Jail	9922838	130233		D2016	Urinal	Standard		3
527	Sacramento County Main Jail	9959762			C2017	Wall Finishes	any surface		3
528	Sacramento County Main Jail	9959459	130480		C2011	Wall Finishes	Ceramic Tile		3
529	Sacramento County Main Jail	9959465	130433		C2012	Wall Finishes	Wood Paneling, Raised Architectural Wainscot		3
530	Sacramento County Main Jail	9859711	129678	EQ-1028936	E1091	Waste Handling Equipment	Trash Compactor, 12 CY or 50,000 LB		3
531	Sacramento County Main Jail	9959763			D2016	Drinking Fountain	Wall-Mounted, Bi-Level		3
532	Sacramento County Main Jail	10015278			G3011	Storage Tank	Site Water, Underground, 10000 GAL		3
533	Sacramento County Main Jail	10314023			F1024	Classroom	New Construction		3

No.	Action Description	Location Description	Condition	Condition Score	Plan Type	Effective Year in Service	Effective Age	Effective Lifespan	Effective RUL	Fiscal Year Observed
520	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2003	23	30	7	2025
521	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Lifecycle/Renewal	2003	23	30	7	2025
522	Replace	B1 - Basement 1 - B1BLR - Boiler	Fair	3	Aged But Functional	2002	18	20	2	2025
523	Replace	All building - Throughout	Fair	3	Aged But Functional		23	25	2	2025
524	Replace	All building - Throughout	Fair	3	Aged But Functional		28	30	2	2025
525	Replace	All building - Throughout	Fair	3	Aged But Functional		18	20	2	2025
526	Replace	All building - Throughout	Fair	3	Aged But Functional		27	30	3	2025
527	Prep & Paint	All Building - Throughout	Fair	3	Lifecycle/Renewal		8	10	2	2025
528	Replace	All building - Throughout	Fair	3	Lifecycle/Renewal	1989	37	40	3	2025
529	Replace	01 - First Floor - 01CRTCST - Court Customer Space	Fair	3	Aged But Functional		27	30	3	2025
530	Replace	01 - First Floor - 01DOCK - Loading Dock	Fair	3	Lifecycle/Renewal	1987	11	15	4	2025
531	Replace	Main entrance	Failed	5	Performance/Integrity		15	15	0	2025
532	Replace	Mechanical room	Failed	5	Performance/Integrity		30	30	0	2025
533	Reconfigure	Each Floor	NA	6	Retrofit/Adaptation		35	35	0	2026

No.	Quantity	Unit Cost	Unit Of Measure	Unit Cost Markup Factor (%)	Unit Cost Markup Reason	Location Factor Markup2	Global Markup (%)	Total Cost	Make	Model
520	1	6000	EA	0		1.138	31	$ 8,944.68	Brunner	NATL. BD. 61668D
521	1	6000	EA	0		1.138	31	$ 8,944.68	Brunner	NATL. BD. 76476K
522	1	5600	EA	0		1.138	31	$ 8,348.37	Kaeser	TA 11
523	294600	3.5	SF	0		1.138	31	$ 1,537,143.26		
524	32	1300	EA	0		1.138	31	$ 62,016.45		
525	30	850	EA	0		1.138	31	$ 38,014.89		
526	8	1100	EA	0		1.138	31	$ 13,118.86		
527	500000	1.5	SF	0		1.138	31	$ 1,118,085.00		
528	196400	18	SF	0		1.138	31	$ 5,270,205.46		
529	75000	28	SF	0		1.138	31	$ 3,130,638.00		
530	1	20000	EA	0		1.138	31	$ 29,815.60	Dynaco	Dynaco
531	1	1500	EA	0		1.138	31	$ 2,236.17		
532	1	40000	EA	300	Piping removal and manual disasser	1.138	31	$ 196,191.20		
533	3300	180	SF	0		1.138	31	$ 885,523.32		

No.	Serial Number	Asset Tag	Date Assessed	Import Code	Comments Public	County ID2	Asset Traffic Light
520		DOOR AIR RECEIVER TANK	11/09/2025	E745AA7E-B4F0-4FC4-B4F8-9BDF785CA9CD		EQ-1038689	green
521		CONTROL AIR RECEIVER TAN	11/09/2025	12661D91-3E06-42EE-A9E1-30E9DC4D72F5		EQ-1038691	green
522	1212	AD1	11/09/2025	2FF71EA4-3419-4B5D-ADFD-6E2C5EC4B1BA		EQ-1039182	green
523			10/30/2025	26758F14-D48C-411A-9E78-BC562B961F1D			blue
524		Toilet	10/30/2025	FC723071-3CF4-4753-9B8D-3D0E6D3B90AF			blue
525		Toilet Partitions	10/30/2025	4770DE54-9AA4-416B-BAA3-FF4528FF6D39			blue
526			10/30/2025	769DF27C-217F-4253-A091-11E564E01B92			blue
527			07/20/2025				blue
528			10/30/2025	397EA588-A283-4ACD-8EFC-FB9427A41836			blue
529			10/29/2025	17829FE4-4FB0-4139-AD87-7E8A6DB84B69			blue
530		TRASH COMPACTOR DOOR	11/09/2025	91A2B07E-4A1A-4B4C-8AA1-1527D253CF44		EQ-1028936	orange
531			07/24/2025		Drinking fountain needs replacement.		blue
532			11/12/2025		Solar water storage tank has been decommissioned and needs t		grey
533			02/11/2026				grey